A Brain-Friendly Guide

Head First PHP & MySQL



Avoid embarrassing mishaps with web forms





Load all the key syntax directly into your brain



Hook up your PHP and MySQL code



Flex your scripting knowledge with dozens of exercises

O'REILLY*

Lynn Beighley & Michael Morrison

Head First PHP & MySQL

Web Programming/PHP

What will you learn from this book?

Ready to take your static HTML web pages to the next level, and build database-driven sites using PHP and MySQL? Then Head First PHP & MySQL is your hands-on guide to getting dynamic sites running, fast. Get your hands dirty building real applications, ranging from a video game high-score message board to an online dating site. By the time you're through, you'll be validating forms, working with session IDs and cookies, performing database queries and joins, handling file I/O operations, and more.



Why does this book look so different?

We think your time is too valuable to spend struggling with new concepts. Using the latest research in cognitive science and learning theory to craft a multi-sensory learning experience, Head First PHP & MySQL uses a visually rich format designed for the way your brain works, not a text-heavy approach that puts you to sleep.

"PHP and MySQL are
two of today's most
popular web development technologies,
and this book shows
readers why. Building
a site without them
is now as unthinkable as doing web
design without CSS.
This book is a great
introduction and is
laugh-out-loud funny.
It's the book I wish
I had learned from."

—Harvey Quamen, Associate Professor of English and Humanities Computing, University of Alberta

"Reading Head First PHP & MySQL is like taking a class from the 'cool' teacher. It makes you look forward to learning."

> —Stephanie Liese, Web Developer

US \$44.99 CAN \$44.99 ISBN: 978-0-596-00630-3







Head First PHP & MySQL

by Lynn Beighley and Michael Morrison

Copyright © 2009 O'Reilly Media, Inc. All rights reserved.

Printed in the United States of America.

Published by O'Reilly Media, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly Media books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (*safari.oreilly.com*). For more information, contact our corporate/institutional sales department: (800) 998-9938 or *corporate@oreilly.com*.

Series Creators: Kathy Sierra, Bert Bates

Series Editor: Brett D. McLaughlin

Editor: Sanders Kleinfeld

Design Editor: Louise Barr

Cover Designers: Louise Barr, Steve Fehler

Production Editor: Brittany Smith

Proofreader: Colleen Gorman

Indexer: Julie Hawks

Page Viewers: Julien and Drew

Michael's nephew Julien generously lent his Superman powers to help get this book finished.

Printing History:

December 2008: First Edition.





Drew is, at this very moment, installing a new kitchen in Lynn's new old house.

The O'Reilly logo is a registered trademark of O'Reilly Media, Inc. The *Head First* series designations, *Head First PHP & MySQL*, and related trade dress are trademarks of O'Reilly Media, Inc.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and O'Reilly Media, Inc., was aware of a trademark claim, the designations have been printed in caps or initial caps.

While every precaution has been taken in the preparation of this book, the publisher and the authors assume no responsibility for errors or omissions, or for damages resulting from the use of the information contained herein.

No hardwood floors, UFOs, Elvis look-alikes, or virtual guitars were harmed in the making of this book. But a few broken hearts were mended thanks to some careful mismatching!

ISBN: 978-0-596-00630-3

|M|

For my parents, who frequently use web applications and are always there for me.

- Lynn Beighley

To Rasmus Lerdorf, who single-handedly sparked the language that would eventually become PHP as we know it now. Enduring proof that it really only takes one person to lead us all down a new, more enlightened path.


- Michael Morrison

Author(s) of Head First PHP & MySQL



Lynn Beighley is a fiction writer stuck in a technical book writer's body. Upon discovering that technical book writing actually paid real money, she learned to accept and enjoy it. After going back to school to get a Masters in Computer Science, she worked for the acronyms NRL and LANL. Then she discovered Flash, and wrote her first bestseller. A victim of bad timing, she moved to Silicon Valley just before the great crash. She spent several years working for Yahoo! and writing other books and training courses. Finally giving in to her creative writing bent, she moved to the New York area to get an MFA in Creative Writing. Her Head First-style thesis was delivered to a packed room of professors and fellow students. It was extremely well received, and she finished her degree, finished Head First SQL, and just finished Head First PHP & MySQL. Whew!

Lynn loves traveling, writing, and making up elaborate background stories about complete strangers. She's a little scared of UFOs.



Michael Morrison


Michael Morrison has been an enthusiastic contributor to the online world ever since he ran a BBS on his Commodore 64 way back when being a nerd was far less cool than it is these days. A few thousand baud later, he still marvels at how far we've come, and how fast. Michael doesn't run a BBS anymore, but he's still very much involved in the modern equivalents and the tools we use to build them. He spends most of his "official" time writing about web-related technologies, having authored or co-authored over fifty books ranging from mobile game programming to XML. He entered the Head First foray with Head First JavaScript, and hasn't looked back.

Michael is also the founder of Stalefish Labs (www.stalefishlabs.com), an entertainment company specializing in games, toys, and interactive media. And he's been known to actually spend time offline (gasp!) skateboarding, playing ice hockey, and hanging out next to his koi pond with his wife, Masheed. He even sleeps every once in a while.

viii

how to use this book

Intro



In this section we answer the burning question: "So why DID they put that in a PHP & MySQL book?"

xxvii

Who is this book for?

If you can answer "yes" to all of these:

- Are you a web designer with HTML or XHTML experience and a desire to take your web pages to the next level?
- Do you want to go beyond simple HTML pages to learn, understand, and remember how to use PHP and MySQL to build web applications?
- Do you prefer stimulating dinner party conversation to dry, dull, academic lectures?

this book is for you.

Who should probably back away from this book?

If you can answer "yes" to any of these:

- Are you completely unfamiliar with basic programming concepts like variables and loops?
 - (But even if you've never programmed before, you'll probably be able to get the key concepts you need from this book.)
- Are you a kick-butt PHP web developer looking for a reference book?
- Are you afraid to try something different? Would you rather have a root canal than mix stripes with plaid? Do you believe that a technical book can't be serious if it creates an alien abduction database?

this book is not for you.



ENote from marketing: this book is for anyone with a credit card. J

xxviii

intro

We know what you're thinking

"How can this be a serious PHP and MySQL book?"

"What's with all the graphics?"

"Can I actually learn it this way?"

We know what your brain is thinking

Your brain craves novelty. It's always searching, scanning, waiting for something unusual. It was built that way, and it helps you stay alive.

So what does your brain do with all the routine, ordinary, normal things you encounter? Everything it can to stop them from interfering with the brain's real job—recording things that matter. It doesn't bother saving the boring things; they never make it past the "this is obviously not important" filter.

How does your brain *know* what's important? Suppose you're out for a day hike and a tiger jumps in front of you, what happens inside your head and body?

Neurons fire. Emotions crank up. Chemicals surge.

And that's how your brain knows...

This must be important! Don't forget it!


But imagine you're at home, or in a library. It's a safe, warm, tiger-free zone. You're studying. Getting ready for an exam. Or trying to learn some tough technical topic your boss thinks will take a week, ten days at the most.

Just one problem. Your brain's trying to do you a big favor. It's trying to make sure that this *obviously* non-important content doesn't clutter up scarce resources. Resources that are better spent storing the really *big* things. Like tigers. Like the danger of fire. Like how to quickly hide the browser window with the YouTube video of space alien footage when your boss shows up.

And there's no simple way to tell your brain, "Hey brain, thank you very much, but no matter how dull this book is, and how little I'm registering on the emotional Richter scale right now, I really do want you to keep this stuff around."


UFO footage on YouTube is obviously more interesting to your brain than some computer book.





Your brain thinks THIS is important

> Great. Only 750 more dull, dry, boring pages.



you are here >

XXIX

user_id = 1

We think of a "Head First" reader as a learner.

So what does it take to *learn* something? First, you have to *get* it, then make sure you don't *forget* it. It's not about pushing facts into your head. Based on the latest research in cognitive science, neurobiology, and educational psychology, *learning* takes a lot more than text on a page. We know what turns your brain on.

Some of the Head First learning principles:

Make it visual. Images are far more memorable than words alone, and make learning much more effective (up to 89% improvement in recall and transfer studies). It also makes things more understandable. Put the words within or near the graphics they relate to, rather than on the bottom or on another page, and learners will be up to twice as likely to solve problems related to the content.

Use a conversational and personalized style. In recent studies, students performed up to 40% better on post-learning tests if the content spoke directly to the reader, using a first-person, conversational style rather than taking a formal tone. Tell stories instead of lecturing. Use casual language. Don't take yourself too seriously. Which would you pay more attention to: a stimulating dinner party companion, or a lecture?

Error! Pass-phrase unknown.

00

Get the learner to think more deeply. In other words, unless you actively flex your neurons, nothing much happens in your head. A reader has to be motivated, engaged, curious, and inspired to solve problems, draw conclusions, and generate new knowledge. And for that, you need challenges, exercises, and thought-provoking questions, and activities that involve both sides of the brain and multiple senses.

Get—and keep—the reader's attention. We've all had the "I really want to learn this but I can't stay awake past page one" experience. Your brain pays attention to things that are out of the ordinary, interesting, strange, eye-catching, unexpected. Learning a new, tough, technical topic doesn't have to be boring. Your brain will learn much more quickly if it's not.

Touch their emotions. We now know that your ability to remember something is largely dependent on its emotional content. You remember what you care about. You remember when you feel something. No, we're not talking heart-wrenching stories about a boy and his dog. We're talking emotions like surprise, curiosity, fun, "what the...?", and the feeling of "I Rule!" that comes when you solve a puzzle, learn something everybody else thinks is hard, or realize you know something that "I'm more technical than thou" Bob from engineering doesn't.

Small correction. We actually do have a heart-wrenching story about a boy and his dog - the dog was abducted by aliens, and you'll be helping the boy find him!

xxx intro

Metacognition: thinking about thinking

If you really want to learn, and you want to learn more quickly and more deeply, pay attention to how you pay attention. Think about how you think. Learn how you learn.

Most of us did not take courses on metacognition or learning theory when we were growing up. We were expected to learn, but rarely taught to learn.

But we assume that if you're holding this book, you really want to learn how to build database-driven web sites with PHP and MySQL. And you probably don't want to spend a lot of time. If you want to use what you read in this book, you need to remember what you read. And for that, you've got to understand it. To get the most from this book, or any book or learning experience, take responsibility for your brain. Your brain on this content.

The trick is to get your brain to see the new material you're learning as Really Important. Crucial to your well-being. As important as a tiger. Otherwise, you're in for a constant battle, with your brain doing its best to keep the new content from sticking.

So just how DO you get your brain to treat PHP & MySQL like it was a hungry tiger?

There's the slow, tedious way, or the faster, more effective way. The slow way is about sheer repetition. You obviously know that you are able to learn and remember even the dullest of topics if you keep pounding the same thing into your brain. With enough repetition, your brain says, "This doesn't feel important to him, but he keeps looking at the same thing over and over and over, so I suppose it must be."


The faster way is to do **anything that increases brain activity**, especially different types of brain activity. The things on the previous page are a big part of the solution, and they're all things that have been proven to help your brain work in your favor. For example, studies show that putting words within the pictures they describe (as opposed to somewhere else in the page, like a caption or in the body text) causes your brain to try to makes sense of how the words and picture relate, and this causes more neurons to fire. More neurons firing = more chances for your brain to get that this is something worth paying attention to, and possibly recording.

A conversational style helps because people tend to pay more attention when they perceive that they're in a conversation, since they're expected to follow along and hold up their end. The amazing thing is, your brain doesn't necessarily care that the "conversation" is between you and a book! On the other hand, if the writing style is formal and dry, your brain perceives it the same way you experience being lectured to while sitting in a roomful of passive attendees. No need to stay awake.

But pictures and conversational style are just the beginning...

I wonder how
I can trick my brain
into remembering
this stuff...

00



Neuron, schmeuron. Some of us are here to rock!



you are here > xxxi

Here's what WE did:

We used **pictures**, because your brain is tuned for visuals, not text. As far as your brain's concerned, a picture really is worth a thousand words. And when text and pictures work together, we embedded the text in the pictures because your brain works more effectively when the text is within the thing the text refers to, as opposed to in a caption or buried in the text somewhere.

We used **redundancy**, saying the same thing in *different* ways and with different media types, and *multiple senses*, to increase the chance that the content gets coded into more than one area of your brain.

We used concepts and pictures in **unexpected** ways because your brain is tuned for novelty, and we used pictures and ideas with at least *some* **emotional** content, because your brain is tuned to pay attention to the biochemistry of emotions. That which causes you to feel something is more likely to be remembered, even if that feeling is nothing more than a little **humor**, **surprise**, or **interest**.

We used a personalized, **conversational style**, because your brain is tuned to pay more attention when it believes you're in a conversation than if it thinks you're passively listening to a presentation. Your brain does this even when you're *reading*.

We included more than 80 *activities*, because your brain is tuned to learn and remember more when you *do* things than when you *read* about things. And we made the exercises challenging-yet-do-able, because that's what most people prefer.

We used **multiple learning styles**, because you might prefer step-by-step procedures, while someone else wants to understand the big picture first, and someone else just wants to see an example. But regardless of your own learning preference, everyone benefits from seeing the same content represented in multiple ways.

We include content for **both sides of your brain**, because the more of your brain you engage, the more likely you are to learn and remember, and the longer you can stay focused. Since working one side of the brain often means giving the other side a chance to rest, you can be more productive at learning for a longer period of time.


And we included **stories** and exercises that present **more than one point of view**, because your brain is tuned to learn more deeply when it's forced to make evaluations and judgments.

We included **challenges**, with exercises, and by asking **questions** that don't always have a straight answer, because your brain is tuned to learn and remember when it has to work at something. Think about it—you can't get your body in shape just by watching people at the gym. But we did our best to make sure that when you're working hard, it's on the right things. That **you're not spending one extra dendrite** processing a hard-to-understand example, or parsing difficult, jargon-laden, or overly terse text.

We used **people**. In stories, examples, pictures, etc., because, well, because you're a person. And your brain pays more attention to people than it does to things.











xxxii intro



Here's what YOU can do to bend your brain into submission

So, we did our part. The rest is up to you. These tips are a starting point; listen to your brain and figure out what works for you and what doesn't. Try new things.

Cut this out and stick it on your refrigerator.

Slow down. The more you understand, the less you have to memorize.

Don't just read. Stop and think. When the book asks you a question, don't just skip to the answer. Imagine that someone really is asking the question. The more deeply you force your brain to think, the better chance you have of learning and remembering.

2 Do the exercises. Write your own notes.

We put them in, but if we did them for you, that would be like having someone else do your workouts for you. And don't just *look* at the exercises. **Use a pencil.** There's plenty of evidence that physical activity while learning can increase the learning.

Read the "There are No Dumb Questions"

That means all of them. They're not optional sidebars—they're part of the core content! Don't skip them.

Make this the last thing you read before bed. Or at least the last challenging thing.

Part of the learning (especially the transfer to long-term memory) happens after you put the book down. Your brain needs time on its own, to do more processing. If you put in something new during that processing time, some of what you just learned will be lost.

5 Drink water. Lots of it.

Your brain works best in a nice bath of fluid. Dehydration (which can happen before you ever feel thirsty) decreases cognitive function.

(6) Talk about it. Out loud.

Speaking activates a different part of the brain. If you're trying to understand something, or increase your chance of remembering it later, say it out loud. Better still, try to explain it out loud to someone else. You'll learn more quickly, and you might uncover ideas you hadn't known were there when you were reading about it.

7 Listen to your brain.

Pay attention to whether your brain is getting overloaded. If you find yourself starting to skim the surface or forget what you just read, it's time for a break. Once you go past a certain point, you won't learn faster by trying to shove more in, and you might even hurt the process.

8 Feel something.

Your brain needs to know that this *matters*. Get involved with the stories. Make up your own captions for the photos. Groaning over a bad joke is *still* better than feeling nothing at all.

Write a lot of code!

There's only one way to learn to program: writing a lot of code. And that's what you're going to do throughout this book. Coding is a skill, and the only way to get good at it is to practice. We're going to give you a lot of practice: every chapter has exercises that pose problems for you to solve. Don't just skip over them—a lot of the learning happens when you solve the exercises. We included a solution to each exercise—don't be afraid to peek at the solution if you get stuck! (It's easy to get snagged on something small.) But try to solve the problem before you look at the solution. And definitely get it working before you move on to the next part of the book.

PHP and MySQL let you build real-world web applications - don't forget to upload them and try them out on a real web server.

you are here ▶ xxxiii

Read Me

This is a learning experience, not a reference book. We deliberately stripped out everything that might get in the way of learning whatever it is we're working on at that point in the book. And the first time through, you need to begin at the beginning, because the book makes assumptions about what you've already seen and learned.

We begin by teaching simple programming concepts and database connection basics, then more complicated PHP functions and MySQL statements, and finally more complex application concepts.

While it's important to create applications that allow users to add data to and retrieve data from your web application, before you can do that you need to understand the syntax of both PHP and MySQL. So we begin by giving you PHP and MySQL statements that you can actually try yourself. That way you can immediately do something with PHP and MySQL, and you will begin to get excited about them. Then, a bit later in the book, we show you good application and database design practices. By then you'll have a solid grasp of the syntax you need, and can focus on *learning the concepts*.

We don't cover every PHP and MySQL statement, function, or keyword.

While we could have put every single PHP and MySQL statement, function, and keyword in this book, we thought you'd prefer to have a reasonably liftable book that would teach you the most important statements, functions, and keywords. We give you the ones you need to know, the ones you'll use 95 percent of the time. And when you're done with this book, you'll have the confidence to go look up that function you need to finish off that kick-ass application you just wrote.

We support PHP 5 and MySQL 5.0.

Because so many people still use PHP 4 or 5, we avoid any PHP 4, 5, or 6 specific code wherever possible. We suggest you use PHP 5 or 6 and MySQL 5 or 6 while learning the concepts in this book. In developing this book, we focused on PHP 5 and MySQL 5, while making sure our code was compatible with later versions.

You need a web server that supports PHP.

PHP has to be run through a web server to work correctly. You need Apache or some other web server installed on your local machine or a machine to which you have some access so that you can run MySQL commands on the data. Check out Appendixes ii and iii for instructions on how to install and extend PHP and MySQL.

xxxiv Intro

You can actually use PHP 4 with this book by making a few modifications to the code. Check them out in #1 of Appendix i.

We use MySQL.

While there's Standard SQL language, in this book we focus on the particular syntax of MySQL. With only a few syntax changes, the code in this book should work with Oracle, MS SQL Server, PostgreSQL, DB2, and quite a few more Relational Database Management Systems (RDBMSs) out there. You'll need to look up the particular PHP functions and syntax if you want to connect to these other RDBMSs. If we covered every variation in syntax for every command in the book, this book would have many more pages. We like trees, so we're focusing on MySQL.

The activities are NOT optional.

The exercises and activities are not add-ons; they're part of the core content of the book. Some of them are to help with memory, some are for understanding, and some will help you apply what you've learned. **Don't skip the exercises**. The crossword puzzles are the only thing you don't have to do, but they're good for giving your brain a chance to think about the words and terms you've been learning in a different context.

The redundancy is intentional and important.

One distinct difference in a Head First book is that we want you to *really* get it. And we want you to finish the book remembering what you've learned. Most reference books don't have retention and recall as a goal, but this book is about *learning*, so you'll see some of the same concepts come up more than once.

The examples are as lean as possible.

Our readers tell us that it's frustrating to wade through 200 lines of an example looking for the two lines they need to understand. Most examples in this book are shown within the smallest possible context, so that the part you're trying to learn is clear and simple. Don't expect all of the examples to be ultra robust, or always complete—they are written specifically for learning, and aren't necessarily fully-functional.

We've placed all of the example code and applications on the Web so you can copy and paste parts of them into your text editor or MySQL Terminal, or upload them as-is to your own web server for testing. You'll find it all at

http://www.headfirstlabs.com/books/hfphp/

The Brain Power exercises don't have answers.

For some of them, there is no right answer, and for others, part of the learning experience of the Brain Power activities is for you to decide if and when your answers are right. In some of the Brain Power exercises, you will find hints to point you in the right direction.

Several of the examples are full-blown web applications that do some pretty powerful things.

you are here > xxxv

The technical review team

Jereme Allen



David Briggs



Will Harris



Stephanie Liese



Steve Milano



Technical Reviewers:

Jereme Allen is a senior level web developer with experience utilizing state of the art technologies to create web applications. He has nine plus years of experience utilizing PHP, MySQL, as well as various other frameworks, operating systems, programming languages and development software.

David Briggs is a technical author and software localization engineer living in Birmingham, England. When he's not being finicky about how to guide users through a particularly tricky piece of software, he likes nothing better than to get out in the local park with his wife, Paulette, and Cleo, the family dog.

Will Harris spends his days running an IT department that provides services to 11 companies on 4 continents, and he is the Vice President of the Las Vegas PASS (Professional Association for SQL Server) chapter. At night, he hops into a phone booth and puts on his web 2.0 suit, helping the designers and developers at Powered By Geek ensure that their data platforms are flexible, portable, maintainable, and FAST, using MySQL and Rails. He also enjoys spending time with his wife, Heather, his beautiful children, Mara and Ellie, and his dog, Swiper.

Stephanie Liese is a technical trainer and web developer in Sacramento, California. When she isn't extolling the virtues of standards compliant code or debugging a CSS layout, you will find her sweating it out in a hot yoga class.

XXXVI intro



Chris Shiflett nhnwamen

If Steve Milano isn't slinging code for The Day JobTM or playing punk rock with his band, Onion Flavored Rings, in some unventilated basement, he's probably at home with his laptop, neglecting feline companion, Ralph, and human companion, Bianca.

Harvey Quamen gave up a computer programming career to join the jet-setting, paparazzi-filled, high profile world of academia. He's currently an Associate Professor of English and Humanities Computing at the University of Alberta, where he teaches courses on cyberculture, 20th-century literature, and web development-including PHP and MySQL.

Chris Shiflett is the Chief Technology Officer of OmniTI, where he leads the web application security practice and guides web development initiatives. Chris is a thought leader in the PHP and web application security communities—a widely-read blogger at shiflett.org, a popular speaker at industry conferences worldwide, and the founder of the PHP Security Consortium. His books include Essential PHP Security (O'Reilly) and HTTP Developer's Handbook (Sams).

Acknowledgments

Our editors:

Many thanks go to **Brett McLaughlin** for the awesome storyboarding session that got us on the right track, and his ruthless commitment to cognitive learning.

The book would not exist if not for the heroic effort, patience, and persistence of **Sanders Kleinfeld**. He always managed to catch the balls, or was it cats, we were juggling when we inevitably dropped one (or three!), and we appreciate it. We hope he gets a chance to put his feet up for a couple of days before taking on another project as difficult as this one.

Brett McLaughlin

The O'Reilly team:



Thanks to **Lou Barr** for her phenomenal design skill, making this book such a visual treat.

Thanks also to **Brittany Smith** for all her hard work at the last minute, and to **Caitrin McCullough** for getting the example web sites up and running. And to **Laurie Petrycki** for having faith that we could write another great Head First book.



Sanders Kleinfeld

And more:



Lou Barr

Finally, a big thanks goes out to **Elvis Wilson** for putting together the alien YouTube videos for Chapter 12. Excellent job! Especially seeing as how he's merely a simple caveman art director.

you are here >

xxxvii

Safari® Books Online



When you see a Safari® icon on the cover of your favorite technology book that means the book is available online through the O'Reilly Network Safari Bookshelf.

Safari offers a solution that's better than e-books. It's a virtual library that lets you easily search thousands of top tech books, cut and paste code samples, download chapters, and find quick answers when you need the most accurate, current information. Try it for free at http://safari.oreilly.com.


xxxviii

intro

1 add life to your static pages










You've been creating great web pages with HTML, and a

sprinkling of CSS. But you've noticed that visitors to your site can't do much other than passively look at the content on the pages. The communication's one-way, and you'd like to change that. In fact, you'd really like to *know what your audience is thinking*. But you need to be able to allow users to **enter information into a web form** so that you can find out what's on their minds. And you need to be able to **process the information** and **have it delivered to you**. It sounds as if you're going to need more than HTML to take your site to the next level.

this is a new chapter


HTML is static and boring



2 Chapter 1

PHP brings web pages to life

PHP allows you to manipulate web page content on the server just before a page is delivered to the client browser. It works like this: A PHP script runs on the server and can alter or generate HTML code at will. An HTML web page is still delivered to the browser, which doesn't know or care that PHP is involved in tweaking the HTML on the server. With PHP in the mix, the web server is able to dynamically generate HTML web pages on the fly.



With a little help from the server

you are here >

Pogs in space

Meet Owen. Owen's lost his dog, Fang. But finding his dog isn't just a matter of searching the neighborhood. You see, Fang was abducted by aliens, which expands Owen's search to the entire galaxy. Owen knows some HTML and CSS, and he thinks a custom web site may help solve his problem by allowing other people to share their own alien abduction experiences.

But to get information from others, Owen's going to need a web form that's capable of receiving user input, lots of it, and notifying him about it. Not a problem—HTML has plenty of tags for whipping together web forms.






Details are sketchy, but we do know that Fang was whisked into the sky in a beam of light


Owen knows some HTML and CSS and thinks he might be able to use the web to help track down his dog, Fang.





A form helps Owen get the whole story

Owen's new web site, AliensAbductedMe.com, aims to connect Owen with alien abductees who might be able to shed some light on Fang's disappearance. Owen knows he needs an HTML form to solicit abduction stories from visitors and that it must find out if they've run into Fang during their interstellar journeys. But he needs your help getting it up and running. Here's what he has in mind for the form.



you are here >

Forms are made of HTML

Owen's Report an Abduction form is built entirely out of HTML tags and attributes. There are text fields for most of the questions, radio buttons to find out if his visitor saw Fang, and a text area for additional comments. And the form is set up to deliver form data to Owen's email address.

If you need a refresher on creating HTML forms, check out Chapter 14 of Head First HTML with CSS & XHTML

the form action.

Owen will get the contents of this form sent to him at "mailto" is a protocol that allows this email address - change form data to be delivered via email. Owen's email address to yours to test out the form. Share your story of alien abduztion: <form method="post" action="mailto:owen@aliensabductedme.com"> This value tells the server how <label for="firstname">First name:</label> to send the data. It will be <input type="text" id="firstname" name="firstname" />
 "post" or "get". We'll explain <label for="lastname">Last name:</label> the difference a bit later. <input type="text" id="lastname" name="lastname" />
 <label for="email">What is your email address?</label> Input tags tell the form <input type="text" id="email" name="email" />
 to expect information. <label for="whenithappened">When did it happen?</label> <input type="text" id="whenithappened" name="whenithappened" />
 <label for="howlong">How long were you gone?</label> <input type="text" id="howlong" name="howlong" />
 The type attribute tells the <label for="howmany">How many did you see?</label> form action to expect text <input type="text" id="howmany" name="howmany" />
 <label for="aliendescription">Describe them:</label> <input type="text" id="aliendescription" name="aliendescription" size="32" />
 <label for="whattheydid">What did they do to you?</label> <input type="text" id="whattheydid" name="whattheydid" size="32" />
 <label for="fangspotted">Have you seen my dog Fang?</label> Yes <input id="fangspotted" name="fangspotted" type="radio" value="yes" /> No <input id="fangspotted" name="fangspotted" type="radio" value="no" />
 <img src="fang.jpg" width="100" height="175"</pre> alt="My abducted dog Fang." />
 <label for="other">Anything else you want to add?</label> <textarea id="other" name="other"></textarea>
 <input type="submit" value="Report Abduction" name="submit" /> </form> w The submit button tells The form is bracketed with the form to execute open and close <form> tags No surprises here - the form

is pure, 100% HTML code!

6 Chapter 1




Try out the Report an Abduction form.

Download the code for the Report an Abduction web page from the Head First Labs web site at

www.headfirstlabs.com/books/hfphp. It's in the chapter01 folder. The folder contains Owen's web form in report.html, as well as a style sheet (style.css) and an image of Fang (fang.jpg).

Open the report.html page in a text editor and change Owen's email address to yours. Then open the page in a web browser, enter some alien abduction information in the form, and click the Report Abduction button.






So, what do you think? Did you receive the form data as an email message in your Inbox?

www.it-ebooks.info

The HTML form has problems

Owen's Report an Abduction form is up and running, but he doesn't get much information from users. Is Fang's abduction really such an isolated incident... or is something wrong with his form? Let's see what the users have to say about it.



B Chapter 1

The form looks OK. Does the problem have something to do with that mailto part?



Yes. The HTML form code is fine, but mailto isn't a good way to deliver form data.


Owen's form is perfectly fine until the user clicks the Report Abduction button. At that point you rely on mailto to package up the form data in an email. But this email doesn't get sent automatically—it's created in the default email program on the user's computer instead. And the real kicker... the user has to **send the email themselves** in order for the data to get sent to you! So you have no control over the email delivery, meaning that it may or may not successfully make the trip from your web form through their browser to their email client and back to you as an email message. Not good.

You need a way to take control of the delivery of the web form. More specifically, you need PHP to package the form data into an email message, and then make sure it gets sent. This involves shifting your attention from the **client** (HTML, mailto, etc.) to the **server** (PHP).

| | THE PERSON NAMED IN COLUMN |
|---|--|
| | Aliens Abducted Me - Report an Abduction Sham your suny of alien abouction |
| The form's wonderful until you click Report Abduction – then all bets are off! | First source: Last name: What is your antall address? When did a happen? How long wore you gone? How many did you nee? Describe them: What did they do to you? Hove you seem my dig Fang? Yes @ No @ |
| pers are on; | Anything the you wout to add? |

0

HTML acts on the CLIENT




The server's role here is limited to just **delivering** the web page to the browser. When the user submits the form, the browser (client!) is left to its own devices to work out how to get the form data sent via email. The client isn't equipped to deliver form data—that's a job for the server.

10 Chapter 1

PHP acts on the SERVER

PHP lets you take control of the data a user types into the form by emailing it to you **transparently**. The user types his abduction story into the form, hits the Report Abduction button, and he's done! The PHP code creates the email message, sends it to you, and then generates a web page confirmation for the user.




you are here >

11

PHP scripts run on the server


PHP code runs on the server and is stored in PHP **scripts** that usually have a .php file extension. PHP scripts often look a lot like normal HTML web pages because they can contain both HTML code and CSS code. In fact, when the server runs a PHP script the end result is always pure HTML and CSS. So every PHP script ultimately gets turned into HTML and CSS once it's finished running on the server.

Let's take a closer look at how a PHP script changes the flow of Owen's web form.



PHP is a <u>server-side</u> programming language - it runs on a web server.

The server returns a pure HTML web page that was generated by the PHP script.



www.it-ebooks.info

13

Okay. But what actually causes a PHP script to get run on the server?




A form element's action attribute is what connects a form to a PHP script, causing the script to run when the form is submitted.

Forms are created using the HTML <form> tag, and every <form> tag has an action attribute. Whatever filename you set the action attribute to is used by the web server to process the form when it is submitted. So if Owen's PHP script is named report.php, then the <form> tag that connects it to the form looks like this:

<form action = "report.php" method = "post">

This is the filename of your -PHP script When the user clicks the Report Abduction button in the form, the form action causes the report.php script to be run **on the server** to process the form data.



The action attribute of the <form> tag is what causes the PHP script to run on the server when the form is submitted.



14 Chapter 1

Dumb Questions

Q: What does PHP stand for?

A: PHP is an acronym that originally stood for Personal Home Pages. Somewhere along the way the acronym was changed to mean PHP: Hypertext Processor. The latter is considered a recursive acronym because it references itself—the acronym (PHP) is inside the acronym. Clever? Confusing? You decide!

Q: Even though my web browser shows that a web page has a name that ends in . php, it's still pure HTML? How is that?

A: It's possible because the page **originates** as PHP code on the server but is **transformed** into HTML code before making its way to the browser. So the server runs the PHP code and converts it into HTML code before sending it along to the browser for viewing. This means that even though a .php file contains PHP code, the browser never sees it—it only sees the HTML code that results from running the PHP code on the server.

Q: But don't all web pages originate on the server, even pure HTML pages in .html files?

A: Yes. All of the files for a web site are stored on the server—.html, .css, .php, etc. But they aren't all processed by the server. HTML and CSS files, as well as image files, are sent directly to the client browser without worrying about what's actually inside them. PHP files are different because they contain code that's processed and run on the web server. It's not the PHP code that's sent to the browser, it's the results of running the PHP code that are sent, and these results are pure HTML and CSS.

Use PHP to access the form data

So Owen needs a PHP script that can get the alien abduction form information to him more reliably than the mailto technique. Let's create it. It's perfectly normal Don't worry about understanding everything yet—we'll get to that: for a PHP script to include regular HTML tags and attributes. ><html> PHP scripts <head> often start out <title>Aliens Abducted Me - Report an Abduction</title> looking a lot like HTML web pages. This entire block of </head> script code is PHP...the <body> rest of the script is normal HTML <h2>Aliens Abducted Me - Report an Abduction</h2> <?php Ah, here's where \$when it happened = \$ POST['whenithappened']; This chunk of PHP things get code grabs the \$how long = \$ POST['howlong']; interesting - this form data so that is the beginning \$alien description = \$ POST['description']; it can be displayed of the actual as part of a \$fang spotted = \$ POST['fangspotted']; PHP code. confirmation page. \$email = \$ POST['email']; echo 'Thanks for submitting the form.
'; echo 'You were abducted ' . Swhen it happened; Here we use echo ' and were gone for ' . \$how long . '
'; PHP to generate echo 'Describe them: ' . \$alien description . '
'; HTML code from the form data. echo 'Was Fang there? ' . \$fang spotted . '
'; echo 'Your email address is ' . \$email; 2> </body> Just like a normal web page, </html> this PHP script finishes up by closing out open HTML tags.

16

Chapter 1



Change Owen's form to use a PHP script to process the form data.


Create a new text file called **report.php**, and enter all of the code on the facing page. This is the script that will process Owen's web form.

The PHP script isn't connected to the form yet, so open the report.html page in a text editor and change the form action to report.php instead of mailto.

<form action = "report.php" method = "post">

Open the report.html page in a web browser, enter some alien abduction information in the form, and click Report Abduction.





| Write down why or why not, and what you think is going on. | | |
|--|-----|--|
| | ••• | |
| ••••• | | |
| | | |

Do you think this is how the PHP script is supposed to work?

17

PHP scripts must live on a server!

Unless you happen to have a web server running on your local computer, the report.php script can't run when you submit the Report an Abduction form. Remember, PHP is a programming language, and it needs an environment to run in. This environment is a web server with PHP support. PHP scripts and web pages that rely on the scripts **must** be placed on a real web server, as opposed to just opening a script directly from a local file system.

If you do have a web server installed locally and it has PHP support, then you can test out PHP scripts directly on your local computer.

Web browsers know nothing about PHP and, therefore, have no ability to run PHP scripts.



Unlike HTML web pages, which can be opened locally in a web browser, PHP scripts must always be "opened" through a URL from a web server.

This PHP script is just a bunch of meaningless code to the web browser.

The web server understands this PHP code and runs the script!




Web servers with PHP support are equipped to run PHP scripts and turn them into HTML web pages that browsers can understand.

A quick way to tell if a web page is being delivered by a web server is to look for the URL starting with "http:". Web pages opened as local files always start with "file:".

PHP scripts must be run on a web server or they won't work.

Get your PHP scripts to the server

It's perfectly fine to create and edit PHP scripts on your local computer. But you need to put the files on a web server to run them. PHP files are often placed alongside HTML files on a web server. There's nothing magical about putting PHP scripts on a web server—just upload them to a place where your web pages can access them. Uploading files to a web server requires the help of a utility, such as an FTP (File Transfer Protocol) utility.



Uploading your PHP scripts to a web server isn't enough—that web server must also have PHP installed on it. Some web servers include PHP by default, some don't.

there are no Dumb Questions

Q: How do I know if my web server has PHP installed?

A: You could ask your web administrator or web hosting company, or you could just perform a little test yourself. Create a text file called test.php and enter the following code into it:



Now upload test.php to your web server, and then enter its URL into a web browser. If PHP is installed on your server, you'll see lots of detailed information about PHP, including its version. Bingo!



If you don't have PHP installed on your web server, check out Appendix ii.

You'll find instructions here for getting PHP up and running on your web server.


Remember to delete phpinfo() script when you're done, so no one else can see it

you are here >



Upload the Report an Abduction files to a web server, and try out the form...again.

Upload report.html, report.php, style.css, and fang.jpg to a web server that has PHP installed. Enter the URL of the report.html page into your browser, fill out the form with alien abduction information, and click the Report Abduction button.



Anything else you want to add?

Cool. Now you just need to add some PHP code to take care of emailing the form data.



That's right. The report.php script's still missing code to email the alien abduction data to Owen.

But that's not a problem because PHP offers a function, a pre-built chunk of reusable code, that you can use to send email messages. You just need to figure out what the email message needs to say and then use PHP to create and send it.

Time out! We don't even know how the original report.php script works, and now we're charging ahead into sending emails. This is like majorly overwhelming...hello!?

It's true. Doing more with PHP requires knowing more about PHP.


So in order to add email functionality to Owen's report.php script, you're going to have to dig a little deeper into PHP and get a solid handle on how the script works up to this point.




you are here >

The server turns PHP into HTML

A big part of understanding how a PHP script works is getting a handle on what happens to the script when it runs on the server. Most PHP scripts contain both PHP code and HTML code, and the PHP's run and turned into HTML before the server passes the whole thing off as HTML to the client web browser. In Owen's report.php script, PHP code generates most of the HTML content in the body of the confirmation page. The HTML code surrounding it is delivered unchanged.




22 Chapter 1



Deconstructing Owen's PHP script

The report.php script is triggered by the Report an Abduction form, and its job (at the moment) is to take the form data and generate a confirmation web page. Let's see how.

The first chunk of code is pure HTML. It just sets up the page we're building, including a few HTML tags required of all pages.



Here's where things start to get interesting. We're ready to break out of HTML code and into PHP code. The <?php tag opens a section of PHP code—everything following this tag is pure PHP.

```
<?php <
```

This code grabs the form data and stores it away in individual variables so that we can easily access it later. PHP **variables** allow you to store values, be they numbers, text, or other kinds of data.

```
$when_it_happened = $_POST['whenithappened'];
$how_long = $_POST['howlong'];
$alien_description = $_POST['description']; 
$fang_spotted = $_POST['fangspotted']
$email = $_POST['email'];
```

Now we're talking! Here the variables we just created are put to work by inserting them into dynamically generated HTML code. The echo command outputs HTML code that gets returned directly to the web browser.

```
echo 'Thanks for submitting the form.<br/>
echo 'You were abducted ' . $when_it_happened;<br/>
echo ' and were gone for ' . $how_long . '<br/>
echo 'Describe them: ' . $alien_description . '<br/>
echo 'Was Fang there? ' . $fang_spotted . '<br/>
'Your email address is ' . $email;
```

The ?> tag matches up with <?php and closes up a section of PHP code. From here on, we're back to normal HTML code.

This ends the PHP code - after - this we're back to normal HTML.

Now wrap up the page by closing out the HTML tags we opened earlier.

```
</body>
</html>
Don't forget, we're generating an HTML web page, so wrap up the HTML code.
```

24 Chapter 1



report.php

Yes, this HTML code is pretty minimal - ideally you'd have a DOCTYPE, <meta> tag, etc., but we're keeping things simple here.

From here on, we're dealing with PHP code...at least until we get to the closing ?> tag.

Each line of PHP code assigns the data from a form field to a new variable.

This PHP code blends variables into HTML code that's output to the browser.

A few PHP rules to live by

Owen's report.php script reveals a few fundamental rules of the PHP language that apply to all PHP scripts. Let's take a look at them.




you are here >

Finding the perfect variable name

In addition to starting with a \$, PHP variable names are also are case-sensitive. But that's not all—there are other important rules governing how you name variables. Some of these rules are syntax rules, meaning your code will break if you ignore them, while other rules are just good ideas passed down from wise old PHP coders.

Let's start with the official rules that will absolutely cause problems if you ignore them when naming variables. Follow these rules to create **legal** variable names. A variable is a container that you can store data in, and every variable has a unique name.



These rules will stop your code working if you don't follow them, but there are a couple more rules that are good to follow as more of a coding convention. These rules help make PHP code a little more consistent and easier to read.

✓ Use all lowercase for variable names.

Separate words in a multi-word variable name with underscores.

These last two rules won't break your code if you ignore them, and you'll certainly run across PHP code that doesn't adhere to them yet works just fine. This is because they are just a stylistic convention—but they will serve you well as you begin creating and naming variables of your own.

PHP variable names must begin with a dollar sign, and cannot contain spaces.

26 Chapter 1

Dumb Questions

Q: Does it matter whether I put PHP commands in uppercase or lowercase?

A: Yes and no. For the most part, PHP isn't case-sensitive, so you can get away with mixing the case of most commands. That means you can use echo, ECHO, or EchC when echoing content. However, as a matter of convention, it's a very good idea to be consistent with case in your scripts. Most PHP coders prefer lowercase for the vast majority of PHP code, which is why you'll see echo used throughout the example code in the book.

O: So even if it's a bad coding convention, I can mix and match the case of PHP code?

A: No, not entirely. The huge exception to the case insensitivity of PHP is variable names, which apply to data storage locations that you create. So let's take the Semail variable used in the Report an Abduction script as an example. This variable name is case-sensitive, so you can't refer to it as SEMAIL or SeMail. All variable names in PHP are case-sensitive like this, so it's important to name variables carefully and then reference them consistently in your code. More on variable names in just a moment.

Q: Is it really OK to put both PHP and HTML code in the same file?

A: Absolutely. In fact, in many cases it's absolutely necessary to do so.

Q: Why would I want to do that?

A: Because the whole idea behind a web server is to serve up HTML web pages to browsers. PHP doesn't change that fact. What PHP allows you to do is change the HTML content on the fly with things like today's date, data pulled from a database, or even calculated values such as the order total in a shopping cart. So PHP allows you to manipulate the HTML that goes into web pages, as opposed to them just being created statically at design time. It's very common to have HTML code for a page with PHP code sprinkled throughout to plug in important data or otherwise alter the HTML programmatically.

Does PHP code embedded in an HTML file have to be on its own line, or can I embed it in an HTML line, like as part of an HTML tag attribute?

A: Other than needing to place your PHP code within the <?php and ?> tags, there are no restrictions in how you embed it in HTML code. In fact, it's often necessary to wedge a piece of PHP code into the middle of HTML code, like when you're setting the attribute of an HTML tag. This is a perfectly legitimate usage of PHP.

O: I've seen PHP code that's enclosed by <? as the start tag instead of <?php. Is that right?

A: Not really. Technically speaking, it's legal, but it isn't recommended. A server setting must be enabled for the short open tag (<?) to work. The usual <?php tag always works, so it's better to use that and know that your code will just work.

O: If a web server always returns pure HTML code to a client browser, why do URLs show the PHP script name, like webpage.php?

Remember that every web page is the result of a two-sided communication involving a request from the client browser and a response from the web server. The URL is the basis of the request, while the content returned from the server is the response. PHP scripts are requested just like normal HTML web pages through URLs entered into the browser or linked from other pages, or as form actions. That explains why the URL for a PHP "page" shows the name of the PHP script.

The other half of the equation is the response from the server, which is the resulting code that's generated by the PHP script. Since most PHP scripts generate HTML code, it makes sense that the code is HTML and not PHP. So it's no accident that a URL references a .php file on a server, which causes PHP code to be executed on the server, ultimately resulting in pure HTML content being returned to the browser.

Q: Can PHP variables store any other kinds of data?

A: Absolutely. You can use variables to store Boolean (true/false) data. And numeric data can be either integer or floating-point (decimal). There are also arrays, which store a collection of data, as well as objects, which associate a collection of data with code that is used to manipulate the data. Arrays are covered a little later in this chapter, while objects are tackled in Chapter 12. There is also a special data type called NULL, which represents no value. For example, a variable that hasn't been assigned a value is considered NULL.

you are here >






There's a problem with the alien description form data in Owen's report.php script. Circle the lines of code that you think relate to the problem, and write down what they do. Any idea what's wrong?

```
<html>
 <head>
   <title>Aliens Abducted Me - Report an Abduction</title>
 </head>
 <body>
   <h2>Aliens Abducted Me - Report an Abduction</h2>
 <?php
  $when_it_happened = $_POST['whenithappened'];
  $how_long = $_POST['howlong'];
  $alien_description = $_POST['description'];
  $fang_spotted = $_POST['fangspotted']
  $email = $ POST['email'];
  echo 'Thanks for submitting the form. <br />';
  echo 'You were abducted ' . Swhen_it_happened;
  echo ' and were gone for ' . Show_long . '<br />';
  echo 'Describe them: ' . $alien_description , '<br />';
  echo 'Was Fang there? ' . $fang_spotted . '<br />';
  echo 'Your email address is ' . Semail;
</body>
</html>
```

you are here >


29

report.php




Variables are for storing script data

PHP variables are storage containers that store information kinda like how a cup stores a beverage. Since the <code>\$alien_description</code> variable is empty, we know that the form data is never making its way into it. So the <code>\$alien_description</code> variable remains empty despite our attempt to **assign** data to it.





One way to fix the script would be to just assign the exact string we're expecting to the Salien description variable, like this:



This code works in that it most definitely stores the text 'little green men' in the \$alien_description variable. But we solved one problem by creating another one—this code causes the alien description to always be the same regardless of what the user enters into the form.



Somehow the assignment of alien description form data to the \$alien description variable is coming up empty.

\$alien_description = \$_POST['description'];

What do you think this code is doing wrong?

The problem obviously has something to do with that \$_POST thingy. But I have no idea what it is.



The problem does have to do with \$_POST, which is a mechanism used to pass along form data to a script.

The dollar sign at the beginning of \$_POST is a clue... \$_POST is a storage container! More specifically, \$_POST is a **collection** of storage locations used to hold data from a web form. In Owen's case, it holds all the data that gets sent to our report.php script when someone fills out the form and clicks the Report Abduction button. So in order to access the form data and do anything with it, we have to go through \$_POST. Remember this code?


```
$when_it_happened = $_POST['whenithappened'];
$how_long = $_POST['howlong'];
$alien_description = $_POST['description'];
$fang_spotted = $_POST['fangspotted'];
$email = $_POST['email'];

Same deal here, except holding the duration of the abduction is assigned to the variable show_long.

Same deal here, except to the variable show_long.

The piece of form data holding the duration of the abduction is assigned to the variable show_long.
```

So the data in each field of the Report an Abduction form is accessed using \$_POST. But what exactly is \$_POST... a variable?




you are here >

\$_POST transports form data to your script

\$ POST is a special kind of PHP storage container known as an **array**, which stores a collection of variables under a single name. When someone submits Owen's form, the data they've typed into the form fields is stored in the \$ POST array, whose job is to pass the data along to the script.

Each element in the \$ POST array corresponds to a piece of data entered into a form field. To access the data for a specific form field, you use the name of the field with \$ POST. So the duration of an abduction is stored in \$ POST['howlong']. The HTML code for Owen's form reveals how form names relate to data stored in \$ POST.





Aliens Abducted Me - Report an Abduction

Sham your story of alien abduction:

First name:

34 Chapter 1





36 Chapter 1




Fix the script and test it out.

Change the broken line of code in report.php, and then upload it to your web server. Open the report.html page in your browser, fill out the form with alien abduction information, and click the Report Abduction button to submit it to the newly repaired script.





you are here >

Sharpen your pencil



Your work is not quite done. The confirmation web page generated by the PHP script needs to use those new variables to display more information about the alien abduction.





report.html

<label for="other">Anything else you want to add?</label>
<textarea id="other" name="other"></textarea>

<input type="submit" value="Report Abduction" name="submit" />

The period allows you to stick multiple strings of text together as — one — a process known

Write PHP code to create four new variables that store the missing form data: \$name, \$how_many, \$what_they_did, and \$other. Hint: Create the \$name variable so that it stores the user's full name.

the key to accessing form data from PHP.

This space separates

the first

and last

names

fname = f POST['firstname'].' f POST['lastname'];

fhow many = f POST['howmany'];

fwhat they did = f POST['whattheydid'];


fother = f POST['other'];

40

as concatenation

</body>

Your work is not quite done. The confirmation web page generated by the PHP script needs to use those new variables to display more information about the alien abduction.





Tweak Owen's script and try out the changes.

Add the code for the new variables to report.php, as well as the code that echoes the variables to the browser as formatted HTML. Then upload the script to your web server, open the report.html page in your browser, and fill out the form with alien abduction information. Finally, click the Report Abduction button to submit the form and see the results.

Dumb Questions

Q: What actually happens when I concatenate multiple strings together using periods?

A: Concatenation involves sticking more than one string together to form a completely new string. The end result of concatenating strings is always a single string, no matter how many strings you started with. So when you concatenate strings as part of an echo command, PHP combines the strings together into one first, and then echoes that string to the browser.

When I concatenate a variable with a string, does the variable have to contain text?

A: No. Although concatenation always results in a string, variables don't have to contain strings in order for you to concatenate them. So say a variable contains a number, PHP converts the number to a string first and then concatenates it.

Q: What happens to PHP code on the browser?

A: Nothing. And that's because PHP code is never seen by a browser. PHP code runs on the server and gets turned into HTML code that's sent along to the browser. So the browser is completely unaware of PHP's existence—web pages arrive as pure HTML and CSS.

Q: OK, so how exactly does the server turn PHP code into HTML and CSS code?

A: First off, remember that by default the code in a PHP script is assumed to be HTML code. You identify PHP code within a script by placing it between <?php and ?> tags. The server sees those tags and knows to run the code inside them as PHP, and all of the code outside of those tags is passed along to the browser as HTML.

Q: Right. But that still doesn't explain how the PHP code gets turned into HTML/CSS code. What gives?

A: Ah, that's where the echo command enters the picture. You can think of the echo command as outputting information beyond the confines of the <?php and ?> tags. So the echo command is the key to PHP's ability to dynamically generate HTML/CSS code. By concatenating strings of text with PHP variables, you can construct HTML code on-the-fly, and then use echo to output it to the browser as part of the resulting web page. A good example of this is in Owen's report.php script when the

br /> tag is tacked on to the end of a piece of text to generate a line break in HTML.

The confirmation web page is helpful to the user but it's no good to me. I still need the form data sent to me in an email.



The PHP script still needs to email the form data to Owen.

As it stands, the report .php script is grabbing the data from the Report an Abduction form and generating an HTML confirmation page for the user. But it's not yet solving the original problem of emailing a message to Owen when the form is submitted. He just wants to receive a simple text email message that looks something like this:

Similar to the confirmation web page, this email message consists of static text combined with form data.

Alf Nader was abducted last November and was gone for 11 hours.

Number of aliens: dozens

Alien description: little green men

What they did: asked me about UFO regulations

Fang spotted: no


Other comments; Please vote for me.

This email message can be generated from PHP code by putting together a string that combines static text such as "Other comments:" with form field data stored in variables.

| Write down how you'd put together an email message string | |
|---|--|
| from static text and PHP variables. | |
| | |
| *************************************** | |

Creating the email message body with PHP

You've already seen how a period can be used in PHP code to concatenate multiple strings of text together into a single string. Now you need to use concatenation again to build an email message string with variables Most text editors will sprinkled in among static text. automatically wrap the Variables and static text are code to the next line even concatenated into a single email if you don't put in your message string using periods. own line break (return). ' and was gone for ' . Show long . '.' ' was abducted ' . \$when it happened . \$msg = \$name ! 'Number of aliens:' . Show many . 'Alien description: ' . Salien description . 'What they did: ' . \$what they did . 'Fang spotted: ' . \$fang spotted . 'Other comments \(\)' . \$other; Remember, each variable holds a string of text One problem with building such a large string is that it requires a huge line that was pulled from the of PHP code that's difficult to read and understand. You can break the Report an Abduction form PHP code across multiple lines to make it easier to follow. Just make sure to separate the code in spots where the spacing doesn't matter, like **between** two concatenated strings, not in the middle of a string. Then put a



14 Chapter 1

That PHP code sure is pretty. But with no formatting, won't the email message be all jumbled together?




Yes. Just because the PHP code is organized nicely doesn't mean its output will automatically look good.

Organizing PHP code so that **you** can better understand it is completely different than formatting the output of PHP code that users will see. You'll normally use HTML tags to format the output of PHP code since in most cases PHP is used to dynamically generate a web page. But not in this case.

Here we're generating an email message, which is plain text, not HTML. We need to deal with the fact that the message currently looks like this:

Alf Nader was abducted last November and was gone for 11 hours. Number of aliens: dozensAlien description: little green menWhat they did: asked me about UFO regulationsFang spotted: noOther comments: Please vote for me.



bumb Questions

Q: Is there a way to use HTML formatting in emails you send from a PHP script?

A: There is. But it requires an additional step that involves setting the content type header for the message. Headers and content types are a bit beyond the scope of this discussion, which is why we're sticking with pure text email messages for Owen's email responses. You'll learn more about headers in Chapter 6, so you'll definitely gain the knowledge to revisit HTML emails later.



How would you reformat the plain text email message so that it is easier to read?


you are here > 45

Even plain text can be formatted... a little

Since Owen's sending email messages as plain text with no HTML formatting, he can't just stick in

/> tags to add line breaks where the content's running together. But he can use newline characters, which are escaped as \n. So wherever \n appears in the email text, a newline will be inserted, causing any content after it to start on the next line. Here's the new email message code with newlines added:

Escape characters in PHP start with a backslash (\).



46

Chapter 1

double quotes (\"), and of course, newlines (\n).

© or © for the copyright symbol. PHP has a very small set of escape characters that are helpful for escaping things that might be confused with the PHP language itself, such as single quotes (\'),

Newlines need double-quoted strings

The problem with Owen's code is that PHP handles strings differently depending on whether they're enclosed by single or double quotes. More specifically, newline characters (\n) can only be escaped in double-quoted strings. So the Abduction Report email message must be constructed using double-quoted strings in order for the newlines to work.

But there's more to the single vs. double quote story than that. Single-quoted strings are considered raw text, whereas PHP processes double-quoted strings looking for variables. When a variable is encountered within a double-quoted string, PHP inserts its value into the string as if the strings had been concatenated. So not only is a double-quoted string necessary to make the newlines work in the email message, but it also allows us to simplify the code by sticking the variables directly in the string.

Concatenation is no longer necessary since variables can be referenced directly within a double-quoted string.

\$msg = "\$name was abducted \$when it happened and was gone for \$how long.\n" "Number of aliens: \$how many\n" .

"Alien description: \$alien description\n" .

"What they did: Swhat_they_did\n" interpreted properly thanks to the double-quoted string.

"Other comments: Sother";

There's no need for a newline at the very end since this is the last line of the email message.

But we still need to break the message into multiple concatenated strings so that the code's easier to read across multiple lines.

Dumb Questions

: If double-quoted strings are so cool, why have we used mostly single-quoted strings up until now?

A: Well, keep in mind that single-quoted strings are not processed by PHP in any way, which makes them ideal for strings that are pure text with no embedded variables. So we'll continue to use single-quoted strings throughout the book unless there is a compelling reason to use a double-quoted string instead. The most important thing about using single vs. double quotes around strings is to try and be as consistent as possible.

Q: What happens if I need to use a single quote (apostrophe) within a single-quoted string, as in 'He's lost!'?

A: This is where escape characters come in handy. To use a single quote inside of a single-quoted string, just escape it as \ ', like this: 'He\'s lost!'. The same applies to a double quote inside of a double-quoted string—use \". You don't have to escape quotes when they don't conflict, such as a single quote inside of a double-quoted string: "He's lost!".


Q: So single-quoted strings support \ ' but not \n. How do I know what escape characters I can use within single quotes?

A: Single-quoted strings only allow the \ ' and \ \ escape characters-all other escape characters can only be used in doublequoted strings.


you are here >

Assemble an email message for Owen

With the body of the email message generated as a string, you can move on to assembling the rest of Owen's email. An email message is more than just a message body—there are several different parts. Although some are optional, the following pieces of information are used in pretty much all emails:




This is the kind of email message Owen hopes to receive upon someone submitting an alien abduction report.



This sample email message reveals that most of the content is in the body of a message, which you've already finished. All that's left is coming up with a message subject, "from" and "to" email addresses... and of course, somehow using PHP to actually send the message!

Variables store the email pieces and parts


We already have the message body stored in \$msg, but we're still missing the message subject and "from" and "to" email addresses. The subject and the "to" email address can just be set as static text in new variables, while the "from" email address is already stored away in the \$email variable thanks to the form-handling code we wrote earlier in the chapter.



www.it-ebooks.info

Sending an email message with PHP


So you're ready to write the PHP code to actually *send* the email message to Owen. This requires PHP's built-in mail() function, which sends a message based on information you provide it.



The PHP mail() function sends an email message from within a script.


These three pieces of information are required by the mail() function, so you always need to provide them. The "from" email address isn't required but it's still a good idea to include it. To specify the "from" field when calling the mail() function, an additional function argument's required, along with some string concatenation.

The text 'From:' must be prepended to the email address when specifying the address of the email sender




50 Chapter 1

We have to use double quotes here since we're using the \r and \n escape characters.



Just add the code that calls mail () to your script.

The line of code that calls the mail () function is all you need to send the email message. Make sure this code appears in the script **after** the code that creates the email variables, and you're good to go. Here's the complete code for Owen's report.php script, including the call to the mail () function.



Generate an HTML web page on the fly that confirms the successful form submission.

Send the

message.

email


you are here >

report.php



Finish up Owen's script and then try it out.


Add the three new email variables (\$to, \$subject, and \$msg) to the report.php script, as well as the call to the mail() function. Make sure the \$to variable is set to **your** email address, not Owen's! Upload the script to your web server, open it in your browser, and fill out the form with alien abduction information. Click the Report Abduction button to submit the form. Wait a few seconds and then go check your email Inbox for the message.






You may need to configure PHP on your web server so it knows how to send email.

the mail () function doesn't work for you, the problem may be that email support isn't properly configured for your PHP installation. Check out www.php.net/mail for details on how to configure email features on your web server.



Owen starts losing emails

The good news is that Owen's getting emails now. The bad news is that he's getting lots and lots of emails. So many that he's having difficulty keeping track of them. His Inbox is packed, and he's already accidentally deleted some... Owen needs a better way to store the alien abduction data.





Got aliens on the brain? Shake them loose by matching each HTML and PHP component to what you think it does.

| HTML | A software application for viewing and interacting with web |
|------|---|
| F | a software application for viewing and interacting with web |

pages that acts as the client side of web communications.

PHP A PHP command that is used to output content, such as

pure text or HTML code.

web form These tags are used to enclose PHP code so that the web

server knows to process it and run it.

A built-in PHP array that stores data that has been browser

submitted using the "post" method.

A programming language used to create scripts that run <?php ?>

on a web server.

All strings must be enclosed within these. variable

A software application for delivering web pages that quotes

acts as the server side of web communications.

A markup language used to describe the structure of echo web page content that is viewed in a web browser.

A name used to describe built-in PHP variables

\$_POST that are accessible to all scripts.

A series of input fields on a web page that is used to

web server get information from users.

A built-in PHP function that sends an email message.


array

A storage location in a PHP script that has its own

unique name and data type. superglobal

A type of PHP data storage that allows you to store

multiple pieces of information in a single place. mail()



Your PHP & MySQL Toolbox

In Chapter 1, you learned how to harness PHP to bring life to Owen's web form. Look at everything you've learned already...

PHP

A server-side scripting language that lets you manipulate web page content on the server before a page is delivered to the client browser.

PHP script

A text file that contains PHP code to carry out tasks on a web server.

MySQL

An application that lets you store data in databases and tables and insert and retrieve information using the SQL language. client-side

SQL

A query language for interacting with database applications like MySQL.

variable

A storage container for a piece of data. In PHP, variables must start with a dollar sign, like this: fvariable name.

\$ POST

A special variable that holds form data.

<?php ?>

These tags must surround all PHP code in your PHP scripts.

mail()

The PHP function for sending an email. It takes the email subject, email body text, and the destination email address as parameters (you can optionally specify a From address too).

Interpreted solely by the client

Interpreted by a web server, not

www.it-ebooks.info

web browser.

server-side

a client machine.

echo

The PHP command for sending output to the browser window. Its syntax is:

echo 'Hello World';

array

A data structure that stores a set of values. Each value has an index that you can use to access it

escape character

Used to represent characters in PHP code that are difficult to type or that might conflict with other code, such as In (newlines).

2 Connecting to MySQL





* How it fits together *

We have to plug in the interweb before we can connect the web site configuraturer.

I'm not letting her anywhere near my web application.



Knowing how things fit together before you start

building is a good idea. You've created your first PHP script, and it's working well. But getting your form results in an email isn't good enough anymore. You need a way to save the results of your form, so you can keep them as long as you need them and retrieve them when you want them. A MySQL database can store your data for safe keeping. But you need to hook up your PHP script to the MySQL database to make it happen.

Owen's PHP form works well. Too well...



60 Chapter 2


MySQL excels at storing data


Owen really needs a way to store the alien abduction report data in a safe place other than his email Inbox. What he needs is a **database**, which is kinda like a fancy, ultra-organized electronic file cabinet. Since the information in a database is extremely organized, you can pull out precisely the information you need when you need it.

Databases are managed by a special program called a **database server**, in our case a **MySQL** database server. You communicate with a database server in a language it can understand, which in our case is **SQL**. A database server typically runs alongside a web server on the same server computer, working together in concert reading and writing data, and delivering web pages.

The "SQL" in MySQL stands for Structured Query Language.

MySQL stores data inside of database tables.





With alien abduction data safely stored in a MySQL database, Owen can analyze the reports from everyone who answered "yes" to the Fang question at his convenience. He just needs to use a little SQL code to talk to the database server. SQL is the query language used to communicate with a MySQL database.

Owen needs a MySQL database


So it's decided: MySQL databases are good, and Owen needs one to store alien abduction data. He can then modify the report.php script to store data in the table instead of emailing it to himself. The table will keep the data safe and sound as it pours in from abductees, giving Owen time to sift through it and isolate potential Fang sightings. But first things first... a database!

Creating a MySQL database requires a MySQL database server and a special software tool. The reason is because, unlike a web server, a database server has to be communicated with using SQL commands.

I've always heard the tool makes all the difference in getting a job done right. How do I know what MySQL tool to use to create a database and table?

Creating MySQL databases and tables requires communicating with a MySQL database server.

MySQL terminal is a command line window that provides access to a command line where you can enter SQL commands.



MySQL terminal

phpMyAdmin graphical tool

DATE OF THE PARTY OF THE PARTY

phpMyAdmin is a graphical tool that allows you to create databases and tables through a web interface.

Two popular MySQL tools are the MySQL terminal and phpMyAdmin. Both tools let you issue SQL commands to create databases and tables, insert data, select data, etc., but phpMyAdmin goes a step further by also providing a point-and-click web-based interface. Some web hosting companies include phpMyAdmin as part of their standard MySQL service, while the MySQL terminal can be used to access most MySQL installations.



You must have a MySQL database server installed before turning the page.

It's impossible to help Owen without one! If you already have a MySQL database server installed and working, read on. If not, turn to Appendix ii and follow the instructions for getting it installed. If you're using a web hosting service that offers MySQL, go ahead and ask them to install it. Several pieces of information are required to access a MySQL database server. You'll need them again later, so now is a good time to figure out what they are. Check off each one after you write it down.


| My database user name: My database password: You need to check all of these. | If you're afraid this book might fall into the wrong hands, feel free to skip writing this one down. |
|--|---|
| is up and running. Check one of the bound of | ormation in hand, all that's left is confirming that the server oxes below to confirm that you can successfully access your excess MySQL server using the MySQL terminal. |
| to check one LII I can successfully ac | other MySQL tool that works, write it down here. |
| | you are here > 63 |

you are here >


Create a MySQL database and table

Some MySQL installations already include a database. If yours doesn't, you'll need to create one using the CREATE DATABASE SQL command in the MySQL terminal. But first you need to open the MySQL terminal in a command-line window—just typing **mysql** will often work. You'll know you've successfully entered the terminal when the command prompt changes to **mysql>**.

To create the new alien abduction database, type CREATE DATABASE aliendatabase; like this:



The SQL code to create a table is a little more involved since it has to spell out exactly what kind of data's being stored. Let's take a look at the SQL command before entering it into the terminal:




To actually create the new table, type the big CREATE TABLE command into the MySQL terminal. (You can find the code for the command on the web at www.headfirstlabs.com/books/hfphp.) After successfully entering this command, you'll have a shiny new aliens abduction table.

```
File Edit Window Help PhoneHome

mysql> CREATE TABLE aliens_abduction (
    first_name varchar(30),
    last_name varchar(30),
    when it_happened varchar(30),
    how_long varchar(30),
    how_many varchar(30),
    alien_description varchar(100),
    what_they_did varchar(100),
    fang_spotted varchar(10),
    other varchar(100),
    email varchar(50)
);


Query OK, 0 rows affected (0.14 sec)
```

Your MySQL installation may offer the phpMyAdmin web-based tool, which lets you access your databases and tables graphically. You can use the phpMyAdmin user interface to click your way through the creation of a database and table, or enter SQL commands directly just as if you're in the MySQL terminal. Click the SQL tab in phpMyAdmin to access a text box that acts like the MySQL terminal.



So the SQL tab of the phpMyAdmin application provides a way to issue SQL commands just as if you were using the MySQL terminal.

you are here > 65



One of the most important things to note in this statement is that the values in the second set of parentheses have to be in the **same order as the database column names**. This is how the INSERT statement matches values to columns when it inserts the data.

The INSERT statement in action

Here's how an INSERT statement can be used to store alien abduction data in Owen's new aliens abduction table.

This is the name of the table the data is being inserted into, NOT the name of the database.

Your column names are in the first set of parentheses and divided by commas.



Order matters!

The values to be inserted must be listed in exactly the same order as the column names.

INSERT INTO aliens_abduction (first_name, last_name,

when_it happened, how_long, how_many, alien_description,

what they did, fang spotted, other, email)

VALUES ('Sally', 'Jones', '3 days ago', '1 day', 'four',

'green with six tentacles', 'We just talked and played with a dog',

'yes', 'I may have seen your dog. Contact me.

Who's really the funny looking alien here?


The values for each column are in the second set

of parentheses and also

divided by commas.

'sally@gregs-list.net')

Unlike PHP statements, SQL statements don't end in a semicolon when used in PHP code. All of these values contain text, not numbers, so we put single quotes around each one.




Sharpen your pencil

The aliens_abduction table is shown below, but it doesn't have any data yet. Write Sally's alien abduction data into the table. It's OK to write some of the data above the table and use arrows if you don't have room.

These are the column names:

aliens abduction

| | Vi | | | | | | | | |
|------------|-----------|------------------|----------|----------|-------------------|---------------|--------------|-------|-------|
| first_name | last_name | when_it_happened | how_long | how_many | alien_description | what_they_did | fang_spotted | other | email |
| | | | | | <u> </u> | | | | |



Dumb Questions

I'm not sure I understand the difference between a database and a table. Don't they both just store data?

A: Yes. Tables serve as a way to divide up the data in a database into related groups so that you don't just have one huge mass of data. It's sort of like the difference between throwing a bunch of shoes into a huge box, as opposed to first placing each pair in a smaller box—the big box is the database, the smaller shoeboxes are the tables. So data is stored in tables, and tables are stored in databases.

Q: What exactly is the MySQL terminal? How do I find it on my computer?

A: The MySQL terminal is a **technique** for accessing a MySQL database server through a command-line interface. In many cases the MySQL terminal is not a unique program, but instead a connection you establish using the command line from a "generic" terminal program, such as the terminal application in Mac OS X. How you access the MySQL terminal varies widely depending on what operating system you are using and whether the MySQL server is local or remote (located somewhere other than your computer). Appendix ii has more details about how to go about accessing the MySQL terminal.

Q: What about phpMyAdmin? Where can I find that?

A: Unlike the MySQL terminal, phpMyAdmin is a web-based application that allows access to a MySQL database. It is actually a PHF application, which is why you always access it from a web server, as opposed to installing it as a local client application. Many web hosting companies offer phpMyAdmin as part of their standard MySQL hosting plan, so it may already be installed for you. If not, you can download and install phpMyAdmin yourself. It is available for free download from www.phpmyadmin.net. Just remember that it must be installed on a web server and configured to have access to your MySQL databases, just like any other PHP and MySQL application.

Q: I have both the MySQL terminal and phpMyAdmin available. Which one should I use to access my database?

A: It's totally a personal preference. The upside to phpMyAdmin is that you can explore your databases and tables visually without having to enter SQL commands. That can be very handy once you get comfortable with SQL and don't want to manually enter commands for every little thing. However, for now it's a good idea to focus on really understanding how to interact with your MySQL data using SQL commands, in which case either tool works just fine.



Store an alien abduction sighting in your database with an SQL INSERT statement.

Using a MySQL tool such as the MySQL terminal or the SQL tab of phpMyAdmin, enter an INSERT statement for an alien abduction. As an example, here's the INSERT statement for Sally Jones' abduction:

```
INSERT INTO aliens_abduction (first_name, last_name,
   when_it_happened, how_long, how_many, alien_description,
   what_they_did, fang_spotted, other, email)

VALUES ('Sally', 'Jones', '3 days ago', '1 day', 'four',
   'green with six tentacles', 'We just talked and played with a dog',
   'yes', 'I may have seen your dog. Contact me.',
   'sally@gregs-list.net')
```

```
File Edit Window Help PugsinSpace

mysql> INSERT INTO aliens_abduction (first_name, last_name,
    when_it_happened, how_long, how_many, alien_description,
    what_they_did, fang_spotted, other, email)

VALUES ('Sally', 'Jones', '3 days ago', '1 day', 'four',
    'green with six tentacles', 'We just talked and played with a dog',
    'yes', 'I may have seen your dog. Contact me.',
    'sally@gregs-list.net');

Query OK, 1 rows affected (0.0005 sec)
```


Executing the INSERT statement in the MySQL terminal results in a new row of data being added to the aliens_abduction table.

| | nk we can con | Action and the second s | |
|-------|---------------|--|------|
| ••••• | | | |
| | | | |
| | | | |


you are here > 69

Use SELECT to get table data

Inserting data into a table is handy and all, but it's hard not to feel a certain sense of unease at the fact that you haven't confirmed that the data actually made its way into the table. It's kind of like depositing money into a savings account but never being able to get a balance. The SELECT statement is how you "get the balance" of a table in a database. Or more accurately, SELECT allows you to request columns of data from a table.



To check an INSERT, you need a quick way to look at **all of the data** in a table, not just a few columns. The SELECT statement offers a shortcut for just this thing:




70 Chapter 2



Make sure the alien abduction INSERT statement worked by SELECTing the table data.

Execute a SELECT query using a MySQL tool to view all of the contents of the aliens_abduction table. Make sure the new row of data you just inserted appears in the results.


SELECT * FROM aliens abduction



How many rows of data does your table have in it?

you are here > 71

So you're telling me I have to write an INSERT statement every time I want to add a new alien abduction report to my database? This MySQL stuff suddenly isn't looking so appealing.






statements in a MySQL tool is not a workable solution.

in his Inbox, but managing the data manually by issuing SQL


How do you think Owen's MySQL data insertion problem can be solved?


Let PHP handle the tedious SQL stuff




PHP lets data drive Owen's web form


PHP improves Owen's alien abduction web form by letting a script **send the form data** *directly* **to a database**, instead of sending it to Owen's email address and Owen entering it manually. Let's take a closer look at exactly how the application works now that PHP is in the picture.







Not only does Owen need a script to put the data in the database, but he also needs a script to search and view the data. In fact, this could serve as the main page for his web site. The index.php script connects to the database, retrieves alien abduction data, and shows it to Owen.



you are here +

Connect to your database from PHP


Before a PHP script can insert or retrieve data from a MySQL database, it must connect to the database. Connecting to a MySQL database from PHP is similar in many ways to accessing a database from a MySQL tool, and it requires the same pieces of information. Remember the three checkboxes you filled out earlier in the chapter? Here they are again, along with a new one for the name of the database—go ahead and write them down one more time,

Your web hosting service or webmaster may tell you this, or if your web server and MySQL database server are running on the same machine, you can use the word "localhost".

| My MySQL server location (IP address or hostname): | |
|--|--|
| My database user name: | |
| My database password: | The name of the database you created earlier, which is |
| My database name: | aliendatabase. If for some |

The database server host location, username, password, and database name are all required in order to establish a connection to a MySQL database from a PHP script. Once that connection is made, the script can carry out SQL commands just as if you were entering them manually in a MySQL tool.

The name of the database you created earlier, which is aliendatabase. If for some reason you named your database something else or decided to use a database that was already created, use that name instead.



Insert data with a PHP script

Issuing a MySQL query from PHP code first requires you to establish a connection with the database. Then you build the query as a PHP string. The query isn't actually carried out until you pass along the query string to the database server. And finally, when you're finished querying the database, you close the connection. All of these tasks are carried out through PHP script code. Here's an example that inserts a new row of alien abduction data:

```
These should be YOUR
                                                                                 four values, not Owen's
                        Connect to the
                       MySQL database
<?php
  $dbc = mysqli connect('data.aliensabductedme.com', 'owen', 'aliensrool', 'aliendatabase'

    You may be able to use 'localhost' for your
database location instead of a domain name.

    or die('Error connecting to MySQL server.');
  squery = "INSERT INTO aliens abduction (first name, last name, when it happened, how long, "
    "how many, alien description, what they did, fang spotted, other, email) " .
    "VALUES ('Sally', 'Jones', '3 days ago', '1 day', 'four', 'green with six tentacles', " .
    "'We just talked and played with a dog', 'yes', 'I may have seen your dog. Contact me.',
    "'sally@gregs-list.net')";
                                                          _ Build the INSERT query
as a string in PHP code.
                                                                                             Be really careful with
  $result = mysqli query($dbc, $query) <
                                                                                             the quotes and double
                                                 Issue the INSERT query
                                                                                             quotes here, as well
    or die('Error querying database.');
                                                                                             as spaces before and
                                                 on the MySQL database.
                                                                                             after quotes!
  myscli_close($dbc);
                                             These functions require
?>
                                             your web server to have
                                             PHP version 4.1 or greater.
                   What do you think each of these PHP/functions is doing in the script?
                   mysqli connect()
                   mysqli query()
                   mysqli close()
```

Use PHP functions to talk to the database

There are three main PHP functions used to communicate with a MySQL database: mysqli_connect(), mysqli_query(), and mysqli_close(). If you see a pattern it's no accident—all of the modern PHP functions that interact with MySQL begin with mysqli_.

mysqli connect()

Connect to a MySQL database using the four pieces of information you already learned about. mysqli query()

Issue a query on a MySQL database, which often involves storing or retrieving data from a table. An older set of PHP functions that interact with MySQL begin with mysql, without the "i" The "i" stands for "improved," and the mysqli_functions are now preferred.


mysqli_close()

Close a connection with a MySQL database.

Using these three functions typically involves a predictable sequence of steps.

Connect to a database with the mysqli connect() function.

Provide the server location, username, and password to get permission to interact with the MySQL database server. Also specify the database name since this is a connection to a specific database.



Create an SQL query and store it as a string in a PHP variable.


To communicate with the database server, you have to use SQL commands. For example, an INSERT statement is needed to add data to the aliens_abduction table. There's nothing special about the variable name we chose, but a straightforward name like \$query works fine.



78 Chapter 2


Issue the query with the mysqli_query() function.


Use the \$query variable with the mysqli_query() function to talk to the MySQL database server and add data to the aliens_abduction table. You have to tell mysqli_query() both the name of the connection you created back in Step 1 and the name of the variable that holds your query from Step 2.



Close the database connection with the mysqli_close() function.

Finally, mysqli close () tells the MySQL database server that you are finished communicating with it.





\$query = "INSERT INTO aliens_abduction (first_name, last_name, when_it_happened, how_long, " .
"how many, alien_description, what_they_did, fang_spotted, other, email) " .
"VALUES ('Sally', 'Jones', '3 days ago', '1 day', 'four', 'green with six tentacles', " .
"'We just talked and played with a dog', 'yes', 'I may have seen your dog. Contact me.', " .
"'sally@gregs_list.net')";

sresult = mysqli query (\$dbc, \$query) the MySQL server. The code stored in the or die ('Error querying database.'); fquery variable is SQL code, not PHP code.

4 mysqli_close (\$abc); Here's where we close the connection

Let's take a closer look at each one of these PHP database functions, starting with mysqli connect()...

you are here > 79

Get connected with mysqli_connect()

For our PHP script to be able to create a connection to the database with the mysqli_connect() function, you'll need a few pieces of information that you're starting to get very familiar with. Yes, it's the same information you used earlier when working with the MySQL terminal, plus the name of the database.

- O Connect with mysqli_connect().
- Assemble the query string.
- Execute the query with mysqli_query().
- Close the connection with mysqli_close().

Your username and password

Who?

You'll need your own username and password for your own database server. These will either be set up by you or given to you by your web hosting company when MySQL is first installed. If you set up your own MySQL, follow the instructions to give yourself a secure username and password.

The name of your database

What?

In our example, we've named the database aliendatabase. Yours will be whatever name you decided to give it when you set it up earlier, or if your web hosting company created your database for you, you'll be using that name.

The location of the database (a domain name, an IP address or localhost)

Where?

In our example, we're using the location of Owen's (fictional) database. You need to use the location of your own MySQL server. Often, this is localhost if the database server is on the same machine as your web server. Your web hosting company will be able to tell you this. It may also be an IP address or a domain name like Owen's, such as yourserver.yourisp.com.


The location, username, password, and name of the MySQL database in the mysqli_connect() function must all have quotes around them.

The result of calling the function is a database connection and a PHP variable that you can use to interact with the database. The variable is named \$dbc in the example, but you can name it anything you like.

The mysqli_connect() function treats the location, username, password, and database name as strings, so you must quote them.

80

Chapter 2



Here are some examples of PHP database connection strings. Look at each one and then write down whether or not it will work, and how to fix it. Also circle any of the code you find problematic. \$dbc = mysqli connect('data.aliensabductedme.com', 'owen', 'aliensrool', 'aliendatabase'); \$dbc = mysqli connect('data.aliensabductedme.com', 'owen', 'aliensrool', "aliendatabase") \$fangisgone = mysqli_connect('data.aliensabductedme.com', 'owen', 'aliensrool', 'aliendatabase'); \$dbc = mysqli connect('localhost', 'owen', 'aliensrool', 'aliendatabase'); \$dbc = mysqli connect('data.aliensabductedme.com', 'owen', '', 'aliendatabase'); \$dbc = mysqli connect('data.aliensabductedme.com', 'owen', 'aliensrool'); mysqli_select_db(\$dbc, 'aliendatabase');

Sharpen your pencil Solution

Here are some examples of PHP database connection strings. Look at each one and then write down whether or not it will work, and how to fix it. Also circle any of the code you find problematic.

| and now to fix it. Also circle any of the code you find problematic. | |
|--|-------|
| <pre>\$dbc = mysqli_connect('data.aliensabductedme.com', 'owen', 'aliensrool', 'aliendatabase');</pre> | |
| This connection string will work | |
| You need a semicolon here to In this book, we're using single quotes for PHP statement and reserving double quotes for SQL queries. \$dbc = mysqli_connect('data.aliensabductedme.com', 'owen', 'aliensrool', "aliendatabase") | rings |
| This won't work because it's missing a semicolon. The double quotes will work just like the single quotes. | |
| | |
| Not a very descriptive name for | |
| a database connection. | |
| (\$fangisgone) = mysqli_connect('data.aliensabductedme.com', 'owen', 'aliensrool', 'aliendatabase'); | |
| This will work, although it's not a very good name for a database connection | |
| | |
| This assumes the database server is located on | |
| the same server computer as the web server. | |
| <pre>\$dbc = mysqli connect(('localhost', 'owen', 'aliensrool', 'aliendatabase');</pre> | |
| | |
| This will work, assuming the web server and database server are on the same machine. | |
| and the state of t | |
| An empty database password | |
| is not a good idea. | |
| <pre>\$dbc = mysqli_connect('data.aliensabductedme.com', 'owen', (') 'aliendatabase');</pre> | |
| This will work only if you set a blank password for the database. Not a good idea, though! You should always have a password set for each database. | |
| Leaving off the fourth argument | |
| requires you to call mysqli_select_dbit to select the database. | () |
| <pre>\$dbc = mysqli_connect('data.aliensabductedme.com', 'owen', 'aliensrool'); mysqli_select_db(\$dbc, 'aliendatabase');</pre> | |
| Sorry, this is a trick question. In mysgli_connect(), that fourth item, the name of the database, is optional. You can leave it out of the function and use mysgli_select_db() to specify the name of the database instead. So this code is the same as if you had passed all four arguments to mysgli_connect(). | |

It seems like it would be easy to screw up one of the pieces of information used to connect to the database. How do I know for sure if the connection worked?



This is where the PHP die() function comes in handy.

The PHP die() function terminates a PHP script and provides feedback about code that failed. While it won't reveal precisely what went wrong, die() tells us that something's up and that we need to fix it. If something's wrong with one of the four connection variables for mysqli_connect(), or if the database server can't be located, the die() function will stop the rest of the PHP script from running and show the error message in parentheses.


The die() function is called if the connection isn't created.

If one of our four strings in the mysqli_connect() function isn't right, we'll get feedback.

\$dbc mysqli_connect('data.aliensabductedme.com', 'owen', 'aliensrool', 'aliendatabase')
or dis('Error connecting to MySQL server.');

This message is echoed to the web page if the connection fails.

A semicolon isn't necessary here / since "or die(...)" is technically a continuation of a single statement



84 Chapter 2

Build the INSERT query in PHP

SQL queries in PHP are represented as strings, and it's customary to store a query in a string before passing it along to the mysqli query() function. Since SQL queries can be fairly long, it's often necessary to construct a query string from smaller strings that span multiple lines of code, Owen's INSERT query is a good example of this:

Connect with mysgli_connect().

Assemble the query string.

Execute the query with mysqli_query().

Close the connection with mysqli_close().

The period tells PHP to tack this string onto the string on the next line.

This is a PHP string variable that now holds the INSERT query.

\$query = "INSERT INTO aliens abduction (first name, last name,

"when it happened, how long, how many, alien description, " .

"what they did, fang spotted, other, email) " .

"VALUES ('Sally', 'Jones', '3 days ago', '1 day', 'four', " .

"'green with six tentacles', 'We just talked and played with a dog', " .

"'yes', 'I may have seen your dog. Contact me.', " .

"'sally@gregs-list.net')";

The query string is broken across multiple lines to make the query more readable - the periods tell PHP to turn this into one big string.

Since this entire piece of code is PHP code. it must be terminated with a semicolon

With the INSERT query stored in a string, you're ready to pass it along to the mysqli query() function and actually carry out the insertion.

Dumb Questions

Why is an INSERT into a database called a query? Doesn't "query" mean we're asking the database for something?

A: Yes, "query" does mean you're asking for something...you're asking the database to do something. In MySQL database applications, the word "query" is quite general, referring to any SQL command you perform on a database, including both storing and retrieving data.

Q: Why isn't the INSERT statement just created as one big string?

A: Keep in mind that the INSERT statement is stored as one big string, even though it is created from multiple smaller strings. Ideally, the INSERT statement would be coded as a single string. But like many SQL statements, the INSERT statement is quite long and doesn't fit on a "normal" line of code. So it's easier to read the query string if it's coded as smaller strings that are glued together with periods.

Q: Is it really necessary to list the column names when doing an INSERT?

A: No. You can leave off the column names in the INSERT statement. In which case, you must provide values for all of the columns in the table in the same order that they appear in the table structure. Knowing this, it's generally safer and more convenient to specify the column names.

Query the MySQL database with PHP

The mysqli_query() function needs two pieces of information to carry out a query: a database connection and an SQL query string.

Connect with mysqli_connect().

Assemble the query string.

Execute the query with mysqli_query().

Close the connection with mysqli_close().

```
mysqli_query (database_connection, query); This is the SQL query that
This is a database connection that's already been
established via the mysqli_connect() function.

This is a database connection that's already been we stored in a string.
```

The database connection required by the mysqli_query() function was returned to you by the mysqli_connect() function. Just in case that's a bit fuzzy, here's the code that established that connection:

Remember, these connection - variables will be different for your database setup.

```
Sdbc = mysqli_connect('data.aliensabductedme.com', 'owen', 'aliensrool', 'aliendatabase')

or die('Error connecting to MySQL server.');

The connection to the database was stored away earlier in the database.
```

So you have a database connection (\$dbc) and an SQL query (\$query). All that's missing is passing them to the mysqli query () function.

This code shows that calling the mysqli_query() function isn't just a one-way communication. The function talks back to you by returning a piece of information that's stored in the \$result variable. But no actual data is returned from the INSERT query—the \$result variable just stores whether or not the query issued by mysqli_query() was successful.

An SQL query is a <u>request</u> written in SQL code that is sent to the database server.

The mysqli_query() function requires a <u>database connection</u> and <u>a query string</u> in order to carry out an SQL query.

86 Chapter 2

Close your connection with mysqli_close()

Since we're only interested in executing the single INSERT query, the database interaction is over, at least as far as the script is concerned. And when you're done with a database connection, you should close it. Database connections will close by themselves when the user navigates away from the page but, just like closing a door, it's a good habit to close them when you're finished. The PHP mysqli_close() function closes a MySQL database connection.

mysqli_close(database_connection);



This is where you pass the database connection variable that we've been using to interact with the database.

In the case of Owen's script, we need to pass mysqli_close() the actual database connection, which is stored in the \$dbc variable.



This variable holds a reference to the database connection, which was created by mysqli_connect() back when the connection was first opened.

But if database connections are closed automatically, why bother?



Database servers only have a certain number of connections available at a time, so they must be preserved whenever possible.

And when you close one connection, it frees that connection up so that a new one can be created. If you are on a shared database, you might only have five connections allocated to you, for example. And as you create new database-driven applications, you'll want to keep your supply of available connections open as much as you can.

Connect with mysqli_connect().

Assemble the query string.

Execute the query with mysqli_query().

Close the connection with mysqli_close().

It's a good habit to close a MySQL database connection when you're finished with it.

you are here >

Dumb Questions

Q: Couldn't you just put all the SQL code directly in the mysqli_query() function in place of the \$query variable?

A: You could, but it gets messy. It's just a bit easier to manage your code when you store your queries in variables, and then use those variables in the mysqli query() function.

Q : Should the code that issues the <code>INSERT</code> query be doing anything with the result?

A: Perhaps, yes. So far we've been using die () to terminate a script and send a message to the browser if something goes wrong. Eventually you may want to provide more information to the user when a query's unsuccessful, in which case you can use the result of the query to determine the query's success.



BULLET POINTS

- Database connections need a location, a username, a password, and a database name.
- The mysqli_connect() function creates a connection between your PHP script and the MySQL database server.
- The die () function exits the script and returns feedback if your connection fails.
- Issuing an SQL query from PHP code involves assembling the query in a string and then executing it with a call to mysqi query().
- Call the mysqli_close() function to close a MySQL database connection from PHP when you're finished with it.



Replace the email code in Owen's report.php script so that it inserts data into the MySQL database, and then try it out.

Remove the code in the report.php script that emails form data to Owen. In its place, enter the code that connects to your MySQL database, builds a SQL query as a PHP string, executes the query on the database, and then closes the connection.


Here's the new PHP database code you've been working on. Don't enter the <?php?> tags in report php since you're adding this code to a spot in the script that's already inside the tags.

Upload the new report.php file to your web server, and then open the report.html page in a browser to access the Report an Abduction form. Fill out the form and click Report Abduction to store the data in the database. Now fire up your MySQL tool and perform a SELECT query to view any changes in the database.



| Is this correct? Write down if you think this is what the script should be doing, and why. |
|---|
| |
| |
| |

you are here > 89



90 Chapter 2

\$_POST provides the form data

The good news is that the report.php script already has the form data stored away in variables thanks to the \$_POST superglobal. Remember this PHP code?

```
$name = $_POST['firstname'] . ' ' . $_POST['lastname'];
$when_it_happened = $_POST['whenithappened'];
$how_long = $_POST['howlong'];
$how_many = $_POST['howmany'];
$alien_description = $_POST['aliendescription'];
$what_they_did = $_POST['whattheydid'];
$fang_spotted = $_POST['fangspotted'];
$email = $_POST['email'];
$other = $_POST['email'];
$cher = $_POST['other'];
**Remember, the name you use for i_POST needs to match up with the name of an HTML form field.
```

So you already have the form data in hand, you just need to incorporate it into the alien abduction INSERT statement. But you need to make a small change first. Now that you're no longer emailing the form data, you don't need the \$name variable. You do still need the first and last name of the user so that they can be added to the database—but you need the names in separate variables.

```
sfirst_name = $_POST['firstname']; The user's name is now stored in separate variables so that it can be inserted into distinct columns of the aliens_abduction table.
```

| Exercise | Write the PHP code to create Owen's INSERT query string that is stored in the \$query variable, making sure that it stores actual form data in the aliens_abduction table upon being executed. |
|----------|--|
| | |
| | |
| | |
| | |



Write the PHP code to create Owen's INSERT query string that is stored in the \$query variable, making sure that it stores actual form data in the aliens_abduction table upon being executed.

The column names appear in the SQL statement exactly as they did before.

fquery = "INSERT INTO aliens abduction (first name, last name, when it happened, how long, ".

"how many, alien description, what they did, fang spotted, other, email) ".

"VALUES ('ffirst_name', 'flast_name', 'fwhen_it_happened', 'fhow_long', 'fhow_many', ".

"falien_description', 'fwhat_they_did', 'ffang_spotted', 'fother', 'femail')";

Instead of static data about Sally Jones' abduction, now we insert whatever data the user entered into the form.

The order of the variables must match the order of the column names for the data to get stored in the correct columns of the table.

Dumb Questions

Do I have to create all those variables to store the \$_POST data? Can't I just reference the \$_POST data directly into the \$query string?

A: Yes, you can. There's nothing stopping you from putting \$_POST directly in a query. However, it's a good coding habit to isolate form data before doing anything with it. This is because it's fairly common to process form data to some degree before inserting it into a database. For example, there are clever ways for hackers to try and hijack your queries by entering dangerous form data. You'll learn how to thwart such attempts in Chapter 6. To keep things simple, this chapter doesn't do any processing on form data, but that doesn't mean you shouldn't go ahead and get in the habit of storing form data in your own variables first before sticking it in a query.

OK, so does it matter where you use single quotes versus double quotes? Can I use single quotes around the whole query and double quotes around each variable?

A: Yes, it matters. And no, you can't use single quotes around the whole query with double quotes around the variables. The reason is because PHP treats strings differently depending on whether they appear inside single quotes or double quotes. The difference between the two is that single quotes represent exactly the text contained within them, while some additional processing takes place on the text within double quotes. This processing results in a variable inside of double quotes getting processed and its value placed in the string in lieu of the variable name. This is quite handy, and is why double quotes are generally preferred for building SQL query strings.

Q: Couldn't you just build query strings by concatenating the variables with the SQL code?

A: Yes, and if you went the concatenation route, you could certainly use single quotes instead of double quotes. But query strings tend to be messy as it is, so anything you can do to make them more readable is a good thing—embedding variables directly in a double-quoted string instead of concatenating them with single quotes definitely makes query strings easier to understand.



Let's use everything we've learned to finish Owen's form-handling PHP script so that it can successfully store alien abduction data in a database. Finish the PHP code below to complete the ${\tt report.php}$ script.

| php</td <td></td> | |
|-------------------|--|
| ••••• | ······································ |
| | |
| | n_it_happened = \$_POST['whenithappened']; |
| | _long = \$_POST['howlong']; |
| 15000000000 | _many = \$_POST['howmany']; |
| | en_description = \$_POST['aliendescription']; |
| | t_they_did = \$_POST['whattheydid']; |
| | g_spotted = \$_POST['fangspotted']; |
| | <pre>il = \$_POST['email'];</pre> |
| soth | er = \$_POST['other']; |
| \$dbc | = |
| • | |
| "h | ry = "INSERT INTO aliens_abduction (first_name, last_name, when_it_happened, how_long, " . bw_many, alien_description, what_they_did, fang_spotted, other, email) " . ALUES ('\$first_name', '\$last_name', '\$when_it_happened', '\$how_long', '\$how_many', " . \$alien_description', '\$what_they_did', '\$fang_spotted', '\$other', '\$email')"; |
| Şres | ult = |
| | |
| • | |
| | |
| echo | 'Thanks for submitting the form. '; |
| echo | 'You were abducted ' . Swhen it happened; |
| echo | ' and were gone for ' . Show long . ' '; |
| echo | 'Number of aliens: ' . Show many . ' '; |
| echo | 'Describe them: ' . Salien description . ' '; |
| echo | 'The aliens did this: ' . \$what they did . ' '; |
| echo | 'Was Fang there? ' . \$fang spotted . ' '; |
| echo | 'Other comments: ' . Sother . ' '; |
| echo | 'Your email address is ' . \$email; |
| 7> | |
| | |
| | |
| | |






Change Owen's script to use actual form data when you do an INSERT.

Remove the <code>\$name</code> variable in the report.php script, add the <code>\$first_name</code> and <code>\$last_name</code> variables, and modify the <code>\$query</code> variable to use form variables instead of static text in the <code>INSERT</code> statement. Upload the new version of the script and then try it out by submitting the form in the report.html page a few times, making sure to enter different data each time.



Now use your MySQL tool to carry out a SELECT and view the contents of the aliens_abduction table.

The rew alien abduction reports appear in the table just as you would expect!



There's an extra row of data for Sally Jones from before you fixed the INSERT query. Don't worry, you learn how to remove unwanted data in the next chapter.

Owen needs help sifting through his data

The new and improved report.php script is doing its job and automating the process of adding alien abduction reports to the database. Owen can just sit back and let the reports roll in... except that there's a new problem. More data isn't exactly making it any easier to hone in on alien abduction reports involving a potential Fang sighting.

I'm really stoked that I've now got a database automatically filled with alien abduction reports submitted by users. But it doesn't help me isolate the reports that might help me find Fang.

Owen needs a way to find specific data, such as alien abductions where Fang was spotted.

You know what column of the database contains the information in question: fang_spotted. This column contains either yes or no depending on whether the abductee reported that they saw Fang. So what you need is a way to select only the reports in the aliens_abduction table that have a value of yes in the fang spotted column.

You know that the following SQL query returns all of the data in the table:

SELECT * FROM aliens abduction

The SQL SELECT statement lets you tack on a clause to control the data returned by the query. It's called WHERE, and you tell it exactly how you want to filter the query results. In Owen's case, this means only selecting alien abduction reports where the fang_spotted column equals yes.

Remember, without the WHERE clause, this causes all of the data in the table to be selected.

The name of the column The value the column must be set to in order for adata to be selected

SELECT * FROM aliens abduction WHERE fang spotted = 'yes'

This part of the SELECT query stays the same - the WHERE clause takes care of whittling down the results.

This clause reduces the data returned by the query, yielding only the data where the fang_spotted column is set to yes.

96

Chapter 2




Try out the SELECT query with a WHERE clause to find specific data.

Use a SELECT query with a WHERE clause in your MySQL tool to search for alien abduction data that specifically involves Fang sightings.



Owen's on his way to finding Fang



98

Chapter 2



Even though you haven't seen it all put together yet, match each HTML, PHP, and MySQL component to what you think it does.

| 17.4 | 1 | |
|-------|------|------|
| alien | data | base |

This is the SQL code the PHP script passes to the

MySQL server.

aliens_abduction table

This runs PHP scripts and returns HTML pages to browsers,

often communicating with a database along the way.

report.html

The name of the database that contains the

aliens abduction table.

report.php

The HTML form uses this request method to send the

data in the form to a PHP script.

POST

This is where the data from the report.html form

will eventually end up being stored.

web server

This is where Owen collects data from the user.

MySQL database server

This PHP function closes a connection to the MySQL server.

Submit button

This is the name of Owen's PHP script that processes the data users enter into his report.html form.

query

This PHP function sends a query to the MySQL server.

್ ಕ

This HTML element is used by visitors to the site

mysqli_connect()

when they finish filling out the form.

mysqli_close()

This is another name for the software that runs MySQL

and all the databases and tables it contains.

mysqli_query()

This optional PHP function tells the database server


which database to use.

mysqli_select_db()

This opens a connection between the PHP script and

the MySQL server so they can communicate.

www.it-ebooks.info



100 Chapter 2



Dumb Questions

It's pretty cool that I've learned how to insert data into a MySQL table but I'm still a little confused about how the table and its database were created. What gives?

A: Good question. It's true that you need to understand how to create your own tables, not just use code presented to you. So far you've created a table without much understanding of the CREATE TABLE syntax. That's fine for Owen's single table, but when you need to create multiple tables of your own design, it isn't good enough. You'll need to take a closer look at the data you're storing in new tables and think about the best way to represent it. This is the main focus of the next chapter... are you ready?

you are here >

101

3 create and populate a database



* Creating your own data *


Are you Jamaican? Because Jamaican me crazy!



You don't always have the data you need.

Sometimes you have to *create the data* before you can use it. And sometimes you have to *create tables* to hold that data. And sometimes you have to *create the database* that holds the data that you need to create before you can use it. Confused? You won't be. Get ready to learn how to create databases and tables of your very own. And if that isn't enough, along the way, you'll build your very first PHP & MySQL application.

this is a new chapter



104 Chapter 3

Elmer needs an application

An **application** is a software program designed to fulfill a particular purpose for its users. Elmer needs an application that will keep track of his email address list and allow him to send out email to the people on the list by clicking a single form button. Here's how he wants it to work:

Go to a web page and enter an email message.

Click a Submit button on the page, and the message gets sent to the entire MakeMeElvis.com email list.

Let the email list build itself by allowing new customers to sign up through a web form.

With this laundry list of application needs, it's possible for Elmer to visualize his application in all its glory... A web application is a dynamic web site that is designed to fulfill a particular purpose for its users.


This email stuff sounds a lot like Owen's Alien Abduction application, but the difference here is that Elmer's email list will build itself, and his email messages will go out to the entire list. Elmer's app is all about automation!



The MakeMeElvis.com web application consists of two main components: a form to send email messages to people on Elmer's email list and a form to allow new customers to join the email list. With these two forms in mind, sketch a design of Elmer's application.

105

Visualize Elmer's application design



106 Chapter 3

So where do we begin in building a
PHP and MySQL application? Should we
write the PHP script and then create the table
to hold the data? Or should we make the table
first and then the script?



Joe: I don't see how it really matters. We're going to need the table *and* the script before the application will work.

Frank: That's true, but I think we should write the script first so we can test out the PHP code before connecting it to the database.

Jill: But the PHP script's entirely dependent on the database. It'll be hard to test the script if we don't have a database for it to connect to.

Frank: Couldn't we create the script but just leave out the specific code that connects to the database? We could do everything but actually interact with the database. That might still be helpful, right?

Joe: Not necessarily. Remember, the script's only job is to take data entered into an HTML form and stick it in a database. Or if it's sending an email to the mailing list, the script reads from the database and generates an email message for each user. Either way, the database is critical to the script.

Jill: True, but we didn't even think about the HTML form. Where does that fit into all of this? I'm thinking we need to create the database before we can even think about writing the script.

Frank: That's it! First we create the HTML form, then we figure out what data goes in the database, and when that's done we tie it all together with the script.

Joe: I'm not sure if that really makes sense. How can we create an HTML form when we aren't 100% sure what data we need to get from the user?

Jill: Joe's right. The HTML form still leads back to us needing to have the data for the application figured out first. The data drives everything, so we should probably build the database and table first, then the HTML form, and then the script that reacts to the form submission.

Frank: I'm sold. Let's do it!

Joe: I still think we probably need to come up with specific steps of how this application is going to come together...

| from design to implementation with MakeMeElvis.com. | |
|---|--|
| | |
| •••••••••••••••••••••••••••••••••••• | |
| | |
| | |

PLAN AHEAD

We really need a plan of attack for putting together Elmer's application. By breaking it down into steps, we can focus on one thing at a time and not get overwhelmed.

Create a database and table for the email list.

This table will hold the first names, last names, and email addresses of everyone on Elmer's mailing list.



Create an Add Email web form and PHP script for adding a new customer to the list.

Here's where we'll build a form and script that will allow a customer to easily enter their first name, last name, and email address, and then add them to the email list.



Create a Send Email web form and PHP script for sending an email to the list.

Finally, we'll build a web form that will allow Elmer to compose an email message and, more importantly, a script that will take that message and send it to everyone stored in his email list table.



It all starts with a table

Actually, it all starts with a database, which is basically a container for storing data. Remember, in the last chapter, how databases are divided internally into more containers called **tables**.


Like days and weeks in a calendar, a table's made up of columns and rows of data. **Columns** consist of one specific type of data, such as "first name," "last name," and "email." **Rows** are collections of columns where a single row consists of one of each column. An example of a row is "Wency, Werlitz, wwer@starbuzzcoffee.com."

A database is a container for storing data in a very structured way.

-A column

| lay | Monday | Tuesday | Wednesday | Thursday | Friday | Saturday | F) >> | first_name | last_name | email |
|-----|--------|---------|-----------|----------|--------|----------|----------------|------------|------------|---------------------|
| | 2 | 3 | 4 | 5 | 6 | 7 | These data | | | email |
| | 0 | 10 | -11 | 12 | 13 | 14 | structures are | Jon | Matthews 1 | ionathon@wishiwasel |
| 5 | 16 | 17 | 18 | 19 | 20 | 21 | both tables. | Joe 8ob | Werlitz / | wwwer@starbuzzcoffe |

Generally, all the tables in a database have some relationship to each other, even if that affiliation is sometimes loose. It's common for a web application to consist of multiple tables that are connected to one another through their data. But all the tables are still made up of columns and rows.



Tables store data in a grid-like pattern of columns and rows.

Dumb Questions


Q: Where's database data actually stored? Can I see the files?

A: Database data is typically stored in files on a hard disk. And although you could certainly look at them, they wouldn't tell you much. Database files are binary files that can't just be opened and looked at. That's why we have SQL—to allow us to peer into a database and interact with the data stored within it.

Make contact with the MySQL server

Elmer's application design needs a database and a table. Most of the day-to-day work of dealing with a database involves interacting with tables, but you can't just jump in and start creating tables without creating a database to hold them first.

The CREATE DATABASE command is the SQL command used to create a database. Once that's done, you can move on to creating a table with the CREATE TABLE command. But before you can use either of those commands, you have to connect to your MySQL database server. You did this back in the last chapter, and it required a few pieces of important information.



As well as letting a PHP script make a connection to a database and perform database actions, the database server location, username, and password are the key to using the MySQL terminal or phpMyAdmin. And these tools are pretty helpful for getting a database application off the ground with the initial database and table creation.

Since creating a database and table for Elmer's application only has to happen once, it makes sense to use an SQL query to create them manually. So fire up your MySQL tool of choice, and get ready to knock out the first step of Elmer's application, creating a database and table for the email list.



Create a database for Elmer's emails

To create a new table and database for Elmer's email list, first we need to create the elvis_store database, which will hold the email_list table. We'll use SQL commands to create both. The SQL command used to create a database is CREATE DATABASE, which you used briefly in the previous chapter. Let's look a bit closer at how it works,

CREATE DATABASE database name database to be created

You need to specify the name of the new database after the command CREATE DATABASE. Here's the SQL statement to create Elmer's database:

CREATE
DATABASE
is the SQL
command used
to create a new
database.

CREATE DATABASE elvis store

When you execue this statement on a MySQL database server, the database will be created.

mysql> CREATE DATABASE elvis_store; & Query OK, 1 row affected (0.01 sec)

When you run SQL commands in the terminal, you always add a semicolon to the end...but not when you issue SQL queries through the PHP mysqli_query() function.

elvis store

Creating the elvis_store database with the CREATE DATABASE command results in a shiny new database but no table to actually store data in yet...



SQL statements only end with semicolons when you use the terminal.

In your PHP code, your SQL statements don't need to end with a semicolon. The MySQL terminal is different, however, and requires a semicolon at

the end of every SQL statement. This is because the terminal is capable of running multiple SQL statements, whereas in PHP, you only submit one statement at a time.

The database is created, but it can't hold any data without a table.

you are here >

111

Create a table inside the database

You have to know what kind of data you want to store in a table before you can create the table. Elmer wants to use the first and last names of people on his email list to make the email messages he sends out a bit more personal. Add that information to the email address, and Elmer's email_list table needs to store three pieces of data for each entry.

Each piece of data in a table goes in a column, which needs a name that describes the data. Let's use first_name, last_name, and email as our **column names**. Each **row** in the table consists of a single piece of data for each of these columns, and constitutes a single entry in Elmer's email list.

The email_list table is one of many tables that could be stored in the elvis_store database.

elvis store






Table rows are horizontal, and table columns are vertical. So now we know that the first name, last name, and email address of a customer must be created as columns in the email_list table. Problem is, MySQL tables are highly structured and expect you to provide more than just the name of a column of data. You have to tell the database a bit more about **what kind** of data you intend to store in the column.



112 Chapter 3

We need to define our data

When you create a table, you have to tell the MySQL server what type of data each column will hold. Data types are required for all MySQL columns, and each column in a table holds a particular type of data. This means some columns may hold text, some may hold numeric values, some may hold time or dates, and so on. MySQL has a variety of data types, and you need to know which one suits your particular data. Let's suppose Elmer has a table named products that keeps track of the items for sale at his store:



To create a table, you need to know what type of data is stored in each table column.

an error if you try to insert anything except a date in that column.

type of data. So if you have a column that holds a date, you will receive

BRAIN

Why do you think using different data types is better than using just text to store everything?

you are here >

113

Take a meeting with some MySQL data types

These are a few of the most useful MySQL data types. Remember, you can use any of them to describe the data stored within a particular column of table data. It's their job to store your data for you without mucking it up.



114 Chapter 3

Dumb Questions

Q: Why would I ever use a CHAR when a VARCHAR does the same thing with more flexibility?

A: The answer is accuracy and efficiency. From a design perspective, you should always design your tables to model your data as rigidly as possible. If you know without a shadow of a doubt that a state column will always hold exactly a two-character abbreviation, then it makes sense to only allot two characters of storage for it with CHAR (2). However, if a password column can contain up to 10 characters, then VARCHAR (10) makes more sense. That's the design side of things. So CHAR is a little more efficient than VARCHAR because it doesn't have to keep track of a variable length. Therefore, it's more desirable when you know for certain a text column has an exact length.

Q: Why do I need these numeric types like INT and DEC?

A: It all comes down to database storage and efficiency. Choosing the best matching data type for each column in your table will reduce the size of the table and make operations on your data faster. Storing a number as an actual number (INT, DEC, etc.) instead of text characters is usually more efficient.


Q: Is this it? Are these all the types?

A: No, but these are the most commonly used ones. We'll get up and running with these for now, rather than bogging things down by looking at data types you may never need.



Match each MySQL data type to each description of some data you might store in a table.

| Data Type | Description |
|--------------|---|
| INT | Your full name |
| CHAR(1) | A two letter state abbreviation |
| DATE | Cost of an Elvis wig: 48.99 |
| TIME | How much money Elvis's best-selling album made. |
| VARCHAR (2) | Date of alien abduction: 2/19/2004 |
| DEC(4,2) | Number of Elvis sideburns in stock: 93 |
| VARCHAR (60) | Did you see Owen's dog? Y or N |
| CHAR(2) | Your email address |
| DATETIME | When you eat dinner |
| DEC(10,2) | How many aliens you saw when you were abducted |
| | When Elvis was born |



create and populate a database


Create your table with a query

We've got all the pieces that we need to create our table, even a good name (email_list). We also have names for the columns of data: first_name, last_name, and email. All that's missing is the data type for each column and an SQL statement to tie it all together and create the table. The SQL command to create your table is CREATE TABLE.

It begins with CREATE TABLE then your table name. Two parentheses hold a comma separated list of all the column names, each one followed by a data type. Here's what the command looks like:

Yep, we're still here...but we're almost ready to move on.

- Oreate a database and table for the email list.
- Create an Add Email web form and PHP script for adding a new customer to the list.
- Create a Send Email web form and PHP script for sending an email to the list.



The CREATE TABLE SQL command is used to create a new table in a database.

| _ Sharpen your pencil | |
|-----------------------|--|
| | Write an SQL query to create Elmer's email_list table with the three required columns of data: first_name, last_name, and email. |
| | |
| | |
| | |
| | |
| | |
| | |

| Solution | Write an SQL query to create Elmer's email_list table with the thre required columns of data: first_name, last_name, and email. |
|--|---|
| Here's the SQL commo the table, notice the | |
| The opening parenthesis opens the list of columns to create. | > (first_name VARCHAR(20), The comma separates the |
| •••• | last_name VARCHAR(20), columns being created email VARCHAR(60) This tells MySQL that the |
| The closing parenthesis closes the list of columns. | email column has a VARCHAR The name of the data type. The (60) means that the text it holds can be up to 60 characters long. |



Create Elmer's database and table.

Execute the CREATE DATABASE and CREATE TABLE queries using a MySQL tool to create the elvis_store database and the email_list table within it.

CREATE DATABASE elvis_store

CREATE TABLE email_list(first_name VARCHAR(20), last_name VARCHAR(20), email VARCHAR(60))

| Did both queries execute without a hitch? If not, write down what you think might have gone wrong. |
|--|
| |
| |

Hang on, something ain't right here. I entered the code to create the table exactly like we drew it up...and now I'm getting some weird error.

The CREATE TABLE statement's fine but the MySQL terminal doesn't know which database it's being created in not good.



Elmer's all shook up because his CREATE TABLE statement is flawless, yet the MySQL terminal's reporting an error.

```
mysql> CREATE TABLE email_list (
    first_name VARCHAR(20),
    last_name VARCHAR(20),
    email VARCHAR(60)
);
ERROR 1046 (3D000): No database selected
```

For some reason the CREATE TABLE statement failed in the MySQL terminal.

table database Getting the cart in front of the horse

Elmer has a legitimate problem that has to do with the fact that the MySQL terminal doesn't automatically know which database you're talking about when issuing commands. Sure, it knows that you just created the elvis_store database, but there could already be plenty of other databases stored on the same server—it can't just assume you're talking about the one you just created.

Fortunately, there is a simple solution that involves telling the MySQL terminal which database you want targeted by all subsequent statements...

there are no Dumb Questions

Q: What's up with the weird -> prompt I get sometimes in the MySQL terminal?

A: The -> prompt indicates that you're entering a single statement across multiple lines—MySQL is basically telling you that it knows you're still entering the same statement, even though you've hit Return to break it out across more than one line. Once you finish the statement and put the semicolon on the end, MySQL will execute it.

USE the database before you use it

So that the CREATE TABLE statement will work, Elmer needs to **select the database** in the MySQL terminal so that it knows what database the new table belongs to. The USE command chooses a database as the default database in the terminal, meaning that all subsequent commands apply to that database. Here's how it works:

The USE command tells MySQL what database you intend to use.


USE database name


Elmer should specify his database name (elvis_store) in a USE statement to select the database and access his new table.

USE elvis store like to USE.

The USE command selects a database as the default database for subsequent SQL statements.

The USE command chooses the database you want to work with.








First USE Elmer's database, then create the table.

Execute the USE query to select Elmer's elvis_store database in a MySQL tool, and then execute the CREATE TABLE query to create the email list table inside the database.

USE elvis store

CREATE TABLE email_list(first_name VARCHAR(20), last_name VARCHAR(20), email VARCHAR(60))



Oops! My CREATE TABLE statement had a typo in it, but it still got executed. Does SQL have an undo option?



There isn't exactly an undo option in SQL but it's certainly possible to fix mistakes.

However, first you need to find out exactly what kind of mistake has been made in order to fix it. Suppose the email_list table looks like this:

email_list

| first_naem | last_name | email | |
|------------|-----------|-------|--|
| | | | |

Circle what you think is wrong with this table. Any idea how you might fix it?


DESCRIBE reveals the structure of tables

Repairing a mistake in a table first involves finding the mistake. Even if you don't suspect a mistake, it's never a bad idea to check your work. The SQL DESCRIBE command analyzes the structure of a table, displaying a list of column names, data types, and other information.

DESCRIBE table name

Plugging in Elmer's table name gives us the following SQL statement:





bumb Questions

What's up with those other columns: Null, Key, Default, and Extra?

A: MySQL lets you set a number of options for each column in your table. These options control things like whether a column can be left empty or if it has a default value. We'll explore these a bit later when they become more critical to the application.

Q: So if I actually had data stored in my table, would it show up here?


A: No. DESCRIBE only shows you the table structure, not the data stored in it. But don't worry, you'll see the data in your table very soon... but first we have to learn how to actually put data into the table.

Q: Can I look at the same table structure using phpMyAdmin?

A: Yes. Graphical database tools such as phpMyAdmin allow you to view the structure of tables by issuing a DESCRIBE statement or by clicking a visual view of a table. It's entirely up to you which kind of tool you use to analyze your tables.

I fixed the typo and tried to run the CREATE TABLE query again. It didn't work. Surely I don't have to delete the typo'd table first... do I?

The first name column was accidentally misspelled first naem...oops!



Actually, you do. You can't recreate a table again with CREATE TABLE once it's been created.

Once you've created a table, it exists and **can't be overwritten** by a new CREATE TABLE query. If you want to recreate a table from scratch, you'll have to delete the existing one first, and then start over again.

In SQL, the DROP TABLE command is used to delete a table from a database. It deletes the table and anything you've stored in it. Since no data exists in a new table, we won't lose anything by dropping it and creating a new one with the first_name correction.




124

Chapter 3

Elmer's ready to store data

The CREATE DATABASE, USE, and CREATE TABLE SQL commands were successfully used to create Elmer's email list database and table. Elmer couldn't be more pleased, unless maybe the table was already filled with eager customers. That's a job for PHP...



Nice. With the database and table created, I'm ready to start storing some serious mailing list data.



for Elmer's email list.

there are no Dumb Questions

Hey, I have a copy of Head First SQL (great book, by the way). In that book, every time you show the code for an SQL statment, you put a semicolon after it. Why not here?

consists of three columns used to store the data

A: We're glad you enjoyed Head First SQL. The difference is that when you talk to MySQL directly, you need a semicolon so it knows where the end of the statement is. That's because it's possible to issue multiple statements to MySQL directly. In PHP, when you use the mysqli_query() function, you only execute a single SQL command at a time, so no semicolon is needed. But don't forget that you do still need a semicolon at the end of each PHP statement!

Q: So if my table has data in it and I drop it, all my data is deleted too?

A: That is true. So drop tables with care!

Q: So if I need to change a table with data in it, I'm out of luck?

A: Hey, no one is perfect. Everyone makes mistakes, and SQL offers the ALTER statement to help us change existing tables. We'll talk about this command a bit later on in the book.


Create the Add Email script

Elmer needs an HTML form that can collect names and email addresses from customers. Once he has those, he can grab them with a PHP script and store them in the email_list table. The web form (addemail.html) requires three input fields and a button. The form action is the most important code in the form since its job is to pass along the form data to the addemail.php script we're about to create.

Create a database and table for the email list.

Create an Add Email web form and PHP script for adding a new customer to the list.

Create a Send Email web form and PHP script for sending an email to the list.





Write an example query here that inserts data

?>

The addemail.php script processes data from the Add Email form. The script should take the data from the form, connect to the elvis_store database, and INSERT the data into the email_list table. Help Elmer by first writing an example SQL query to insert a new customer, and then use that query to finish the PHP script code.

| o Elmer's table. | |
|---|---|
| | |
| | |
| php</td <td></td> | |
| \$dbc = | |
| * | |
| \$first_name = \$_PO | ST['firstname']; |
| | |
| • · · · · · · · · · · · · · · · · · · · | |
| \$query = | *************************************** |
| | v |
| mysqli_query(| 18 |
| *************************************** | |
| echo 'Customer ad | ded.'; |
| 1 | |

you are here > 127

addemail.php



The addemail.php script is called upon to process data from the Add Email form. The script should take the data from the form, connect to the elvis_store database, and INSERT the data into the email_list table. Help Elmer by first writing an example SQL query to insert a new customer, and then use that query to finish the PHP script code.

INSERT INTO email_list (first_name, last_name, email) VALUES ('Julian', 'Oates', 'julian@breakneckpizza.com') The example INSERT query is rewritten as a PHP string that relies Here are the & POST on form data for the insertion array values that contain the submitted information saba = mysali connect ('data makemeelvis.com', 'elmer', 'theking', 'elvis store') <?php or die (Error connecting to MYSQL server."); \$first_name = \$_POST['firstname']; flast name = f POST['lastname']; femail = f POST['email']; squery = "INSERT INTO email list (first_name, last_name, email) ". "VALUES ('ffirst name', 'flast name', 'femail')"; mysqli_query(fdbc, fquery) or die ('Error querying database'); echo 'Customer added.'; mysqli close(fdbe); ?> If we wanted to be fancy here, we could put a link back to our addemail.php form with an HTML <a> tag.




Try out the Add Email form.

Download the code for the Add Email web page from the Head First Labs web site at www.headfirstlabs.com/books/hfphp. It's in the chapter03 folder. This code consists of Elmer's web form in addemail.html, a style sheet (style.css), and two images (elvislogo.gif and blankface.jpg).

Now create a new text file called **addemail.php**, and enter all of the code on the facing page. This is the script that will process Elmer's web form and add new customers to the email list table.


Upload all of these files to your web server and open the addemail.html page in a web browser. Enter a new customer in the form, and click Submit.

Don't forget to change the database connection variables to your own.



The insertion of the new customer to the email list is confirmed by the addemail php script

Check to see that the customer was added to the database by issuing a SELECT query in a MySQL tool.



Dumb Questions

Q: Is the star in the SQL SELECT command the same thing as an asterisk?


A: Yes, it's the same character on your keyboard, located above the 8 key. Hit SHIFT at the same time as the 8 to type one. But although it's exactly the same character as asterisk, in SQL lingo, it's always referred to as a star. This is a good thing, since saying "SELECT asterisk FROM..." is not as easy as saying "SELECT star FROM...".

Q: Are there other characters in SQL that have special meaning like the star does?

A: While SQL does have other special, or reserved, characters, the star is the only one you need to know about for right now. More importantly for our immediate purposes, it's the only one used in the SELECT part of an SQL statement.

| harpen your pe | With Elmer's email list starting to fill up, help him write some SQL queries that he can use to find specific customer data. |
|---|--|
| Select all of the d | lata for customers with a first name of Martin: |
| *************************************** | |
| Select only the la | ast name for customers with a first name of Bubba: |
| | |
| | ame and last name for the customer with an Is@objectville.net. |
| 211111111111111111111111111111111111111 | |
| Select all of the c | columns for customers with a first name of Amber of McCarthy: |
| 000000000000000000000000000000000000000 | |

130





With Elmer's email list starting to fill up, help him write some SQL queries that he can use to find specific customer data.

Select all of the data for customers with a first name of Martin:

SELECT * FROM email_list WHERE first_name = 'Martin'

The star selects all the columns in the table.

This WHERE clause trims down the query results to only those customers with a first name of Martin.

Select only the last name for customers with a first name of Bubba:

SELECT last_name FROM email_list WHERE first_name = 'Bubba'

Only the last name column is returned in the query results.

Select the first name and last name for the customer with an email address of Is@objectville.net.

SELECT first name, last name FROM email list WHERE email = 'Is@objectville.net'

You specify multiple columns of result data by separating the column names with commas.

Select all of the columns for customers with a first name of Amber and a last name of McCarthy:


SELECT * FROM email_list WHERE first_name = 'Amber' AND last_name = 'McCarthy'

The WHERE clause can be made dependent on multiple pieces of information, in this case a match for both a first name AND a last name

The other side of Elmer's application

Sending email messages to people on Elmer's email list is similar in some ways to adding people to the list because it involves an HTML web form and a PHP script. The big difference, is that sending an email message to the mailing list involves dealing with the *entire contents* of the email_list table, whereas the addemail.php script only deals with one row of data.

The Send Email web form allows Elmer to enter a subject and body of an email message, and then send it to his entire email list



The nuts and bolts of the Send Email script

The sendemail.php script must combine data from two different sources to generate and send email messages. On the one hand, the script needs to pull the names and email addresses of the email recipients from the email_list table in the elvis_store database. But it also has to grab the email subject and message body entered by Elmer into the Send Email web form (sendemail.html). Let's break down the steps involved.


- Use the \$_POST array to get the email subject and message body from the form.

 There's nothing new here. Clicking the Submit button in the sendemail.html form sends the form data to sendemail.php, where we capture it in variables with a little help from the \$ POST array.
- Run a SELECT query on the email_list table.

 The PHP mysqli_query() function runs a SELECT query to get the data for the email list. Since we want all of the data in the table, we can use SELECT *.
- Fetch the email data from the query result.

 Running a query alone doesn't provide access to data. We need to grab each row of data in the query results in order to have access to the first name, last name, and email address of each customer.
- Call the mail() function to send an email message to each customer.

Sending the emails involves looping through each customer in the email list, which corresponds to each row of data in the query results. The loop we create here starts at the first row of data, then moves on to the second row, and loops through the remaining rows of the data obtained by the SELECT query. We stop when we reach the end of the data.



Elmer's email address is stored in a

First things first, grab the data


We're already pretty well versed in extracting data from forms in PHP, so the first step is nothing new, just use the \$_POST superglobal to store away the email subject and message body in variables. While we're at it, let's go ahead and store Elmer's email address in a variable since we'll need it later when sending the emails.

```
$from = 'elmer@makemeelvis.com'; variable so that we know exactly where it is in case it ever needs to change.

$subject = $_POST['subject'];

$text = $ POST['elvismail']; The email message form data's stored in variables, too.
```

The remaining data required by the sendemail.php script comes from Elmer's MySQL database. Pulling customer data from the email_list table data into the script requires a SELECT query. Unlike before when we've used the MySQL terminal to issue a SELECT and look at table data, this time we're doing it in the sendemail.php script and issuing the query with mysqli query().



No, the \$result variable doesn't actually hold any query data.


If you try to echo the \$result variable directly, you'll see something like this:

Resource id #3

The <code>Sresult</code> variable stores an ID number for a MySQL resource, not the actual data returned by the query. What happens is the MySQL server temporarily stores the results of your query and gives them a resource number to identify them. You then use this resource ID with the PHP mysqli_fetch_array() function to grab the data one row at a time.


mysqli_fetch_array() fetches query results

Once our query executes, we can grab the results with the \$result variable. This variable's used with the mysqli_fetch_array() function to get the data in the table one row at a time. Each row of data is returned as an array, which we can store in a new variable named \$row.



Each time this code is executed by the web server, a row of data from the query results gets stored in the \$row array. You repeatedly call the mysqli_fetch_array() function to step through each row of the query results. So the first three calls to the mysqli_fetch_array() function retrieve the first three rows of data from the table, storing each column of the row as an item in the \$row array.

The mysqli_fetch_array() function stores a row of data in an array.





As a test to make sure we can actually get the customer data a row at a time, finish writing the PHP code to echo the first name, last name, and email address of each customer in the <code>email_list</code> table.

| <pre>\$query = "SELECT * FROM email_list";</pre> |
|---|
| <pre>\$result = mysqli_query(\$dbc, \$query);</pre> |
| <pre>\$row = mysqli_fetch_array(\$result);</pre> |
| |
| |
| |
| |
| |
| |
| ••••••••••••••••••••••••••••••••••••••• |
| ••••••••••••••••••••••••••••••••••••••• |
| ••••••••••••••••••••••••••••••••••••••• |
| |
| |
| |
| |
| |
| |
| |

Sharpen your pencil Solution

As a test to make sure we can actually get the customer data a row at a time, finish writing the PHP code to echo the first name, last name, and email address of each customer in the email list table.

\$query = "SELECT * FROM email list"; \$result = mysqli query(\$dbc, \$query); \$row = mysqli fetch array(\$result); echo frow['first name']. ' frow['last name'] ': ' frow['email'] '
; frow = mysqli fetch array(fresult); echo frow[first_name'] . ' . frow['last_name'] . ': ' . frow['email'] . '
; frow = mysgli fetch array(fresult); echo frow[first name']. ' . frow['last name'] . ': ' . frow['email'] . '
; frow = mysqli_fetch_array(fresult); echo frow ['first_name'] . ' . frow ['last_name'] . frow = mysgli fetch arry You have got to be kidding me. Repeating echo frowl first nam the same two lines of code over and over is about the dumbest thing I've ever seen. Surely there's a better way. echo from tch_array(fresult); Frow echo h_array(fresult); frow ech

There is a better way—we need a loop.

A **loop** is a mechanism in the PHP language that repeats a chunk of code until a certain condition's been met, like running out of data. So a loop can **cycle through each row of data** in a query result, taking any action we want to each row along the way.


138

Chapter 3

Looping for a WHILE


A while loop is a loop specifically geared toward repeating code **while a certain condition is met**. For example, you might have a variable in a customer service application named \$got_customers that keeps up with whether or not customers are waiting to be helped. If \$got_customers is set to true, you know there are more customers, so you might call the next_customer() function to get the next customer and help them. Here's how this scenario could be coded using a while loop:

A while loop repeats code while a condition is met.



When we look to see if there are more customers, we're **testing a condition**. The **condition** is the code in the parentheses, and it always poses a question that results in a yes/no answer. If it's yes, or **true**, then the action is performed. If it's no, or **false**, then we quit the loop.

When we call next_customer() and proceed to help them, we're **performing an action**. The action is the code inside the curly braces, which is repeated as long as the condition remains true. If the condition ever goes false, the loop exits and the action is not repeated again. Here's the general format of a while loop:





A while loop lets us loop through customers until there aren't any left!




How do you think a while loop could be used to loop through the customers in Elmer's email list table?

Looping through data with while

Applying a while loop to Elmer's email data lets us access the data a row at a time without duplicating any code. We know that mysgli fetch array() can take a table row and put the column values in the \$row array, but the function by itself won't get The while loop condition is the return through all of our data—it will store the first row and then stop. A value of the mysgli_fetch_array() while loop can call mysqli fetch array () to go through function, which is interpreted as each row of result data, one at a time, until it reaches the end. true if data is available or false if we're all out of data. while (\$row = mysqli fetch array (\$result)) echo \$row['first name'] . ' ' . \$row['last name'] . ': '. \$row['email'] . '
'; The first time through the The loop action consists The loop loop the from of an echo statement action gets array holds the that sticks the row data \$row first row of the run each together with a line time through email_list table. break at the end. the loop. 1st loop! email_list email last_name first_name julian@breackneckpizza.com Oates Julian jones@simuduck.com Jones Kevin sunshine@breakneckpizza.com Sanchez Amanda 2nd loop! \$row ``. More loops... The second time through the loop the frow array holds the second row of the. email_list table ... see a pattern here?

140 Chapter 3



bumb Questions

Q: How exactly does the while loop know to keep looping? I mean, a while loop's controlled by a true/false condition, and mysqli_fetch_array() returns some kind of resource ID, which is stored in \$row... That sure doesn't look like a true/false test condition.

A: Good observation. As it turns out, PHP is fairly liberal when it comes to how it interprets the "true" condition. In short, any value that is not zero (0) or false is considered true for the sake of a test condition. So when the mysqli_fetch_array() function returns a row of data, the \$row array is interpreted as true since it isn't set to 0 or false. And since the test condition is true, the loop keeps on chugging. What's interesting is what happens when no more data's available—the mysqli_fetch_array() returns false, which terminates the loop.

Q: So I can control a while loop with any kind of data, not just true/false values?

A: That's correct. But keep in mind that ultimately the while loop's interpreting the data as true or false. So the important thing to understand is what constitutes true or false when it comes to the interpretation of other types of data. And the simple answer is that anything other than 0 or false is always interpreted as true.

What happens to the while loop if no data is returned by the mysqli_fetch_array() function?

A: If the query doesn't result in any data, then the mysqli_fetch_array() function returns false. And this causes the while loop to never make it into the action code, not even once.

Q: So it's possible to have a loop that never loops?

A: Indeed it is. It's also possible to have a loop that never stops looping. Consider this while loop:

while (true) {

This is known as an **infinite loop** because the test condition never causes the loop to exit. Infinite loops are a very bad thing.

142 Chapter 3



BULLET POINTS

- A database is a container for storing data in a highly structured manner.
- Tables store data in a grid-like pattern of columns and rows within a database.
- The CREATE DATABASE SQL command is used to create a new database.
- The CREATE TABLE SQL command creates a table within a database and requires detailed information about the columns of data within the table.
- You can delete a table from a database with the DROP TABLE SQL command.
- The mysqli_fetch_array() function retrieves a row of data from the results of a database query.
- A while loop repeats a chunk of PHP code while a test condition is met.
- Create a database and table for the email list.
- Create an Add Email web formand PHP script for adding a new customer to the list.
- 3 Create a Send Email web form and PHP script for sending an email to the list.

Don't forget, we still have that last step to finish up.



PHP & MySQL Magnets

Use the magnets below to finish the code for the Send Email script so that Elmer can start sending emails to his customer list. As a refresher, here's how the mail() function works:


mail(to, subject, msg, 'From: ' . from);


```
<?php
  $from = 'elmer@makemeelvis.com';
  $subject =
  $dbc = mysqli_connect('data.makemeelvis.com', 'elmer', 'treking', 'elvis_store')
    or die('Error connecting to MySQL server.');
   $query = "SELECT * FROM email_list";
   $result = mysqli_query($dbc, $query)
    or die('Error querying database.');
   while($row = mysqli_fetch_array($result)) {
     $first_name = $row['first_name'];
     $last_name = $row['last_name'];
     $msg = "Dear $first_name $last_name,\n
     mysqli_close($dbc);
                                                                       sendemail.php
       msg
  subject
                    email.
     subject
                        POST
elvismail
```



PHP & MySQL Magnets

Use the magnets below to finish the code for the Send Email script so that Elmer can start sending emails to his customer list. As a refresher, here's how the mail () function works:





144 Chapter 3



Send an email to the mailing list using the Send Email form.

Download the code for the Send Email web page from the Head First Labs web site at www.headfirstlabs.com/books/hfphp. It's in the chapter03 folder. Similar to the Add Email page you saw earlier, this code consists of a web form in sendemail.html, a style sheet (style.css), and a couple of images (elvislogo.gif and blankface.jpg).

Create a new text file called **sendemail.php**, and enter all of the code on the facing page. Upload all of these files to your web server and open the sendemail.html page in a web browser. Enter an email message in the form, and click Submit.

Keep in mind that your email address will need to be on the mailing list in order for you to receive a message.

You've got mail...from Elmer!

At last, Elmer can send out his MakeMeElvis.com sale emails to everyone on his mailing list by using his new Send Email web form and PHP script. He can also use the output from the script to confirm that each message is successfully being sent. Each time the code in the script's while loop executes, he sees "Email sent to someone@somewhere.com" with the email address of the person in his database. The end result is more exposure for his products, and for better or worse, more Elvis look-alikes!




146

Chapter 3

Sometimes people want out

As with any blossoming new business, there are bumps in the road. It seems some Elvis fans have jumped ship on the King and want off Elmer's mailing list. Elmer wants to oblige, but that means he needs to remove the customers from his database.



www.it-ebooks.info

Removing data with DELETE

To delete data from a table, we need a new SQL command, DELETE. We'll use DELETE in a new Remove Email script that deletes customers' data from Elmer's mailing list. In fact, we need a new script and a new web form to drive it... but first we need DELETE.

The DELETE SQL command removes rows of data from a table. This makes it a command you should use very carefully since it's capable of wiping out a table full of data in the blink of an eye. Knowing this, here's the most dangerous form of DELETE, which deletes every row from a table.

Greate a database and table for the email list.

Create an Add Email web form and PHP script for adding a new customer to the list.

Greate a Send Email web formand PHP script for sending anemail to the list.

Oreate a Remove Email web form and PHP script for removing a customer from the list.

> Looks like we need a new step...sometimes design plans change!

DELETE FROM table name the table you want to delete rows from.

Without any other qualifiers, the DELETE command completely empties a table of all its data

So we can never delete anything from a table without deleting everything?

No, not at all. DELETE can be used to pinpoint a specific row or rows for deletion.


To precisely target the row or rows you want to delete with DELETE, you need to tack on a WHERE clause. If you recall from using it with the SELECT command, WHERE allows you to isolate specific rows in a query.



Sharpen your pencil


Suppose Elmer had 23 customers with a first name of Anne, 11 customers with a last name of Parker, and one customer with the name Anne Parker. Write down how many rows of data are deleted by each of these queries.

| DELETE FROM email_list WHERE first_name = 'Anne'; | |
|---|--|
| DELETE FROM email_list WHERE first_name = 'Anne' OR last_name = 'Parker'; | |
| DELETE FROM email_list WHERE last_name = Parker; | |



Use WHERE to DELETE specific data

By using a WHERE clause with the DELETE command, we target specific rows of data for deletion, instead of emptying an entire table. The WHERE clause lets us focus on just the row we want to remove, in this case one of Elmer's customers who wants to be removed from the mailing list.



The actual test within a WHERE clause performs a comparison that is carried out against every row in the table. In this example, the equal sign (=) tests each value in the email column to see which rows are equal to "pr@honey-doit.com". If the value in the email column of a row matches, then that row will be deleted.

| Write down why you think the email column is used in the |
|--|
| WHERE clause, as opposed to first_name or last_name: |
| |
| |

148 Chapter 3


clause narrows down a query to focus on specific rows of data.

Minimize the risk of accidental deletions

It's important to understand that although any column name can be used in a WHERE clause to match rows, there's a very good reason why we chose the email column for Elmer's DELETE query. Consider that if more than one row matches a WHERE clause, all of the matching rows will be deleted. So it's important for Elmer's WHERE clause to pinpoint exactly the row you want to delete.

What we're really talking about is uniqueness. It's fairly safe to assume that email addresses are unique within the email_list table, whereas first names and last names are not. You don't want to create a WHERE clause matching the first_name column to "Pat" just to delete a single customer—you'll end up deleting every customer named Pat! That's why Elmer's WHERE clause is carefully crafted to look for a specific match with the email column.

A WHERE clause in a DELETE statement lets you pinpoint the row you want to remove.





Try out the DELETE command on Elmer's database.

Fire up a MySQL tool and try a few DELETE commands to delete individual rows of data from the email_list table based on customers' email addresses. Just make sure to include a WHERE clause on each DELETE statement so that you don't accidentally wipe out the whole table!

The DELETE command's pretty handy, but ideally we'd delete rows of data using a web form and PHP script, right?




That's right. Deleting users by hand with individual queries is no way to manage a mailing list.


Since Elmer will inevitably face users who want to be removed from his mailing list in the future, it makes a lot of sense to develop a web-based user interface for removing customers. An HTML web form and PHP script should do the trick, not to mention a DELETE FROM query with a little help from a WHERE clause...




?>

Elmer has created a web form (removeemail.html) for deleting a customer from his mailing list. All the form accepts is an email address, which is entered into an HTML form field named email. Finish the code for Elmer's removeemail.php script that's called by the form to carry out each customer removal.







Greate a Send Email web formand PIIP script for sending anemail to the list.

customer to the list.

Create a Remove Email web formand PHP script for removing a customer from the list.





Remove a customer from the mailing list using the Remove Email form.

This is starting to feel a little familiar, eh? Download the code for the Remove Email web page from the Head First Labs web site at www.headfirstlabs.com/books/hfphp. It's in the chapter03 folder. This code consists of a web form in removeemail.html, a style sheet (style.css), and a couple of images (elvislogo.gif and blankface.jpg).

Create a new text file called **removeemail.php**, and enter all of the code on the facing page. Upload all of these files to your web server and open the removeemail.html page in a web browser. Enter the email address of a customer in the form, and click Remove to delete them from the database.








154 Chapter 3



PHP&MySQLcross

When you're finished perfecting Elmer's dance moves, see if you can hum along and finish this crossword puzzle.



Across


- 3. A MySQL database is divided into these.
- A persistent, highly organized, data structure that is typically stored in a file on a hard drive.
- This conditional clause can be added to SQL statements to control which rows are targeted.
- 8. This SQL command removes an entire table from a database.
- 9. Use this SQL command to choose rows from a table.
- 10. Use this MySQL data type to store a varying amount of text.
- Within a MySQL table, this holds a specific type of data.
- Keep doing something as long as a certain test condition remains true.

Down

- A MySQL data type that stores numbers without decimal places.
- 2. Use this SQL command to look at the structure of a table.
- When dynamic functionality is added to a web site via PHP and MySQL, it becomes an
- 5. Use this SQL command to destroy rows within a table.
- After creating a new database in a MySQL terminal, you must issue this command before you can do anything with the database.
- 11. A single collection of data in a table consisting of one of each column.



PHP&MySQLcross Solution



Your PHP & MySQL Toolbox

Not only did you help Elmer get his web application off the ground, but you also developed some valuable PHP and MySQL skills in this chapter. For instance...

while

A PHP looping construct that allows you to repeat a section of code as long as a certain condition remains true. One particularly handy usage of the while loop is in looping through rows of data in an SQL query result.

DELETE FROM tableName

Use this SQL statement to delete rows from a table. Depending on how you use the statement, you can delete individual rows or multiple rows.

WHERE

This SQL clause is used in conjunction with other SQL commands to build statements that target specific rows in a table. For example, you can isolate rows that have a column matching a specific value.

mysqli_fetch_array()

This built—in PHP function retrieves a single row of data from the results of a database query. You can call this function repeatedly to read row after row of data.

DROP TABLE tableName

This SQL statement drops an entire table from the database, meaning that the table is removed along with any and all data stored within it.

DESCRIBE tableName

If you need to find out the structure of a table, this SQL statement is what you need. It doesn't reveal any data, but it does show the column names and their respective data types.

SELECT * FROM tableName

This SQL statement selects rows from a table. When the star is used (*), all of the columns for the rows in the table are returned. You can be more specific by listing individual column names instead of the * if you don't want to get all of the column data back from the query.

4 realistic and practical applications

Your Application *
* on the Web

If I put a banana in my teacher's tailpipe, her car won't start, so no exam. But then the substitute might give the test, so he gets a banana, too. But then the substitute's substitute...



Sometimes you have to be realistic and rethink your plans.


Or plan more carefully in the first place. When your application's out there on the Web, you may discover that you haven't planned well enough. Things that you thought would work aren't good enough in the real world. This chapter takes a look at some real-world problems that can occur as you move your application from testing to a live site. Along the way, we'll show you more important PHP and SQL code.

this is a new chapter


159

Elmer has some irritated customers

Elmer's customer mailing list has grown by leaps and bounds, but his emails have generated some complaints. The complaints vary, but they all seem to involve customers receiving blank email messages or multiple messages, neither of which is good. Elmer needs to figure out what's gone wrong and fix it. His business depends on it.



BE Elmer the email list manager Your job is to play Elmer and figure out how those blank emails are getting sent. He suspects it has something to do with the sendemail.html form. Write down what Elmer thinks the problem is Make Me Elvis - Send Emai Private: For Elmer's use ONLY Write and send an email to mailing list members. Subject of email: Body of email: (Submit sendemail.html



162


Chapter 4

Protecting Elmer from... Elmer

So "operator error' is really the problem here—Elmer inadvertently clicks Submit without entering the email information, and blank emails get sent to the entire list. It's never safe to assume a web form will be used exactly the way it was intended. That's why it's up to you, the vigilant PHP scripter, to try and head off these kinds of problems by anticipating that some users will misuse your forms.

Let's take a look at the code in our current sendemail.php script to see how Elmer's empty email messages are getting created.

Our Send Email script uses the text from the form to build an email, even if the user didn't enter anything.



```
The text in the form is retrieved
<?php
                                                from 1 POST['subject'] and 1_
  $from = 'elmer@makemeelvis.com';
                                                POST L'elvismail'I, and is saved in
  $subject = $ POST['subject'];
                                                Esubject and Etext, respectively ...
  $text = $ POST['elvismail'];
  $dbc = mysqli connect('data.makemeelvis.com', 'elmer', 'theking', 'elvis store')
    or die ('Error connecting to MySQL server.');
  $query = "SELECT * FROM email list";
  $result = mysqli query($dbc, $query)
    or die ('Error querying database.');
  while ($row = mysqli fetch array($result)){
                                                         Problem is, we use stext in our
    $to = $row['email'];
                                                        message whether the variable
    $first name = $row['first name'];
    $last name = $row['last name'];
                                                        contains text or not ...
    $msg = "Dear $first name $last name, \n$text";
    mail ($to, $subject, $msg, 'From: ' . $from);
                                                           ... and we also use subject
    echo 'Email sent to: ' . $to . '<br />';
                                                           whether there's text in
                                                           it or not
  mysqli close($dbc);
?>
```


| sendemail.php script code to fix the blank email problem: | |
|---|--|
| | |
| | |

Demand good form data

Elmer's Send Email form's in need of **validation**, which is the process of checking to make sure form data is OK before doing anything with it. Elmer already uses validation even though he doesn't call it that. Whenever he receives an order for Elvis gear, he doesn't just immediately fill it and send it out... he validates it first!


In the case of an order, Elmer first checks to see if the customer's credit card is **valid**. If so, he fills the order and gets it ready to ship. But then he has to check if the customer's shipping address is complete. If that checks out, then Elmer goes ahead and sends out the order. A successful order for Elmer's store always hinges on the validation of the order data.

Validation means making sure the data you get is the data you expect.



To solve Elmer's blank email problem, we need to validate the form data delivered to the sendemail.php script. This means the form data is submitted from the client web page (sendemail.html) to the server, and the server (sendemail.php) checks to make sure all the data is present. We can add code to sendemail.php that examines the values in the text boxes and checks to make sure they aren't empty. If everything checks out OK, the script sends out the emails.


If everything's cool with this data, I'll send out those emails.



164 Chapter 4

The logic behind Send Email validation

Elmer needs to **validate** the data he gets from the sendemail.html form before he sends any emails. In fact, sending the emails should completely hinge on the data validation. What we really need PHP to do is **make a decision** based on the validity of the form data received by the sendemail.php script. We need code that says, "if the data is valid, go ahead and send the emails."



Dumb Questions

I've also heard of validating data on the client instead of on the server. How does that work?

A: The web browser is considered the client, so client-side validation would be any checking that occurs before the data's sent to the PHP script. Languages like JavaScript can do client-side validation. If you're interested in learning more, check out Head First JavaScript, which discusses client-side validation in depth.

Q: So why use server-side validation instead of client-side?

A: If we validate on the client, only part of the problem's solved. Elmer could potentially browse directly to sendemail.php and send out a blank email. But if we validate on the server, it solves both problems. Blank data in the form will be detected as well as blank data from the PHP script being directly loaded. This isn't to say that it's wrong to validate on the client. In fact, it's a very good idea. But the server is the last line of defense for catching bad form data, so server-side validation can't be ignored.

Your code can make decisions with IF

The PHP if statement lets your code make decisions based on whether or not something is true. Consider Elmer's orders again. Before filling an order, Elmer must get paid, which means charging the customer's credit card. If the customer gave Elmer the wrong card number, he can't fill the order. So Elmer performs a kind of real-world validation on every order that goes like this:

If the customer's credit card checks out, go ahead and fill the order.


We can translate this scenario to PHP code using the if statement, which is designed to handle just this kind of decision making.

The basic if statement has three parts:

- 1 The if keyword
 - This starts off the statement.
- The test condition


 The test condition, or conditional expression, is located in parentheses right after the if keyword. Here's where you put the statement that you want to determine the validity, or truth, of.
- The action

 The action of an if statement directly follows the test condition and is enclosed in **curly braces**. Here's where you put the PHP code you want to execute if the condition is, in fact, true.




Testing for truth


The heart of the if statement is its test condition, which is always interpreted as either true or false. The test condition can be a variable, a function call, or a comparison of one thing to another, as a few examples. Elmer's credit card validation relies on a function call as the test condition, which means the value returned by the function is either true or false.



It's quite common to use a comparison as a test condition, which typically involves comparing a variable to some value. For example, maybe Elmer wants to give a discount to customers who live in Nevada. He could create an if statement that carries out a comparison on part of the shipping address, like this:



This test condition performs a comparison for equality, which involves two equal signs (==). Equality comparisons aren't just for variables and strings. You can compare variables to numbers, variables to variables, and even perform calculations.



IF checks for more than just equality

An if statement can check for more than just equality. The test condition in your if statement can also check to see if a value is **greater than** another one. If it is, the result of the condition is true, and the action code is executed. Here are a few more tests you can use to control the decision of an if statement.

It's OK to write an if statement entirely on a single line as long as the action is relatively simple.

```
$small number = 2;
             Start out with
                                                                        Both of these conditions are true.
                                              $big number = 98065;
             these two variables.
There are two ways to check if things are
                                              if ($small number ♦ $big number) { echo 'True'; }
not equal: <> and !=. These give you
                                              if ($small number != $big number) { echo 'True'; }
the opposite results of an == equality test.
                                                                     This condition is false.
The greater than sign (>) checks to see
if the value on the left is greater than the
                                              if ($small number > $big number) ( echo 'True'; )
value on the right. If so, the condition is
true, otherwise it's false.
                                                                     This condition is true.
The less than sign (<) compares the value
on the left to the value on the right. If
                                              if ($small_number < $big_number) { echo 'True'; }
```


on the left to the value on the right. If the left value is smaller than the right, the condition is true.


```
This condition is false.
```

Greater than or equal to (>=) is like greater than (>) except it also results in true if the two values are equal.

```
if ($small_number >= $big_number) { echo 'True'; }
```

Less than or equal to (<=) is similar to less than, except it's also true if the values are equal.





Yes, you can compare strings in if test conditions.

They work based on the alphabet, with a being considered smaller than (less than) z. Using greater than and less than can help you when you need to present information in alphabetical order.

BE the test condition in the if statement

Your job is to play the if test condition and decide if you are true or false given the following variables.

```
$my_name = 'Buster';
$a_number = 3;
$a_decimal = 4.6;
$favorite_song = 'Trouble';
$another_number = 0;
$your_name = $my_name;
```

| (\$a_number == 3) | true or false |
|---------------------------------|---------------|
| (\$another_number == "") | true or false |
| (\$favorite_song == "Trouble") | true or false |
| (\$my_name == '\$your_name') | true or false |
| (\$my_name == "\$your_name") | true or false |
| (\$your_name == \$my_name) | true or false |
| (\$favorite_song == 'Trouble') | true or false |
| (\$a_number > 9) | true or false |
| (\$favorite food = 'hamburger') | true or false |

BE the test condition in the if statement Solution

Your job is to play the if test condition and decide if you are true or false given the following variables.

```
$my_name = 'Buster';
$a_number = 3;
$a_decimal = 4.6;
$favorite_song = 'Trouble';
$another_number = 0;
$your name = $my name;
```

```
($a_number == 3)

($another_number == "")

($favorite_song == "Trouble")

($my_name == '$your_name')

($my_name == "$your_name")

($your_name == $my_name)


($favorite_song == 'Trouble')

($a_number > 9)

($favorite_food = 'hamburger')

Should be == if
we intended this
to be a comparison.

there are no
Dumb Questions
```



O and an empty string evaluate as equal.

Because of those single quotes, the condition is actually asking if the string Buster equals the string "fyour_name", not the value contained in the variable fyour_name.

If a_number is 3, which is not greater than 9.

OK, this one's tricky. Since only one equal sign is used here, it's actually an assignment (=),

OK, this one's tricky. Since only one equal sign is used here, it's actually an assignment (=), not a comparison (==). And it ends up being true because anything other than O, NULL, or false gets interpreted by PHP as true.


Q: Okay, is a test condition the same thing we used to control while loops in Chapter 3?

A: It's exactly the same. And even though we used it to tell us when we had remaining rows of query data back in Chapter 3, we can devise more interesting test conditions for while loops by using different kinds of comparisons. You'll see that later in the book.

The logic behind Send Email validation

Elmer needs to **validate** the data he gets from the sendemail.html form before he sends any emails. In fact, sending the emails should completely hinge on the data validation. What we really need PHP to do is **make a decision** based on the validity of the form data received by the sendemail.php script. We need code that says, "if the data is valid, go ahead and send the emails."

But first we need to grab the form data and store it in a couple of variables:



This form data is all we need to check and see if there is data in each of the form fields. The logic might look something like this:

IF \$subject contains text AND \$body contains text

THEN send email

Or we could take the opposite approach and check to see if the form fields are both empty, in which case we could display a warning to the user:


IF \$subject is empty AND \$body is empty

THEN echo error message

Both of these examples have a problem in that their logic requires us to make two comparisons in a single if statement. One possible solution is to use two if statements...




| Write two if statements that check to see if both the subject and message body of Elmer's Send Email form are empty. Echo a warning message if they're empty. |
|---|
| |
| |
| |
| |
| |



PHP functions for verifying variables

Using == to check for an empty string works, but there's a better way that involves built-in PHP functions. The <code>isset()</code> function tests to see if a variable exists, which means that it's been assigned a value. The <code>empty()</code> function takes things one step further and determines whether a variable contains an <code>empty value</code>, which PHP defines as 0, an empty string ('' or ""), or the values <code>false</code> or NULL. So <code>isset()</code> only returns <code>true</code> if a variable has been assigned a value, while <code>empty()</code> only returns <code>true</code> if a variable has been set to 0, an empty string, <code>false</code>, or NULL.

Let's take a look at how these functions work:



I get it. We can use isset() and empty() to validate the \$subject and \$text form data.



That's half right. We're really just checking to make sure the form data isn't empty, so empty() is what we need.

The \$subject and \$text variables are assigned values from the \$_POST['subject'] and \$_POST['elvismail'] superglobals. If you test these variables with isset(), it will always return true regardless of whether or not they hold any actual text. In other words, isset() doesn't show you the difference between a blank form field and a filled out one. The empty() function checks to see if a variable is actually empty, which is what we need for form validation.

isset() checks that a variable exists and is set.

empty() checks to see if a variable has any contents.

Dumb Questions

 \mathbf{Q} : So what's the point of using isset() anyway?

A: The isset() function is extremely valuable when you need to know if a piece of data exists. For example, you can check if a form has been submitted via a POST request by passing the isset() function \$_POST. This ends up being an extremely handy technique, as you find out a little later in the chapter.

| Sharpen yo | |
|------------|---|
| 1 | Rewrite the two if statements that check to see if both the subject and message body of Elmer's Send Email form are empty, but this time, use the |
| | <pre>empty() function instead of == in the test conditions.</pre> |
| | |
| | |
| | |
| | |
| | |

| Solution | Rewrite the two if statements that check to see if both the subject and message body of Elmer's Send Email form are empty, but this time, use the empty () function instead of == in the test conditions. |
|-----------------------|---|
| A call to the empty() | if (empty(ssubject)) { - if (empty(stext)) { - echo 'You forgot the email subject and body text < br />'; - } - The rest of the code is - the same as before. |

What if we need to only take a certain action if a form field is not empty? Is there a notempty() function?

No, but there's an easy way to reverse the logic of any test condition... the negation operator.

We know the test condition that controls an if statement always results in a value of true or false. But what if our logic dictates that we need to check for the reverse of what a condition gives us? For example, it would be helpful to know if Elmer's form fields are **not empty** before sending a bunch of emails with the form data. Problem is, there is no notempty () function. The solution is the negation operator (!), which turns true into false, or false into true. So !empty() literally calls the empty () function and reverses its result, like this:

The NOT operator (!) turns true into false, or false into true. if (!empty(\$subject)) (. This condition asks, "Is the Subject field not empty?" Or, does it have data in it?

174 Chapter 4




Fill in the blanks in Elmer's sendemail.php code so that email only gets sent when both \$subject and \$text are not empty. Use if statements and the empty() function.

All my fields need to have values.



```
<?php
                                                             sendemail.html
 $from = 'elmer@makemeelvis.com';
 $subject = $ POST['subject'];
 $text = $ POST['elvismail'];
 if .....
   if .....
     $dbc = mysqli connect('data.makemeelvis.com', 'elmer', 'theking', 'elvis store')
       or die('Error connecting to MySQL server.');
     $query = "SELECT * FROM email list";
     $result = mysqli query($dbc, $query)
       or die('Error querying database.');
     while ($row = mysqli_fetch_array($result)) {
       $to = $row['email'];
       $first name = $row['first name'];
       $last name = $row['last name'];
       $msg = "Dear $first_name $last_name, \n$text";
       mail($to, $subject, $msg, 'From:' . $from);
       echo 'Email sent to ' . $to . '<br />';
     mysqli close ($dbc);
 ......
?>
```






See if the empty form field validation works.

Modify the code in sendemail.php to use if statements that check the form field data before sending email messages. Upload the new version of the script to your web server and open the sendemail.html page in a web browser. Make sure to leave at least one of the form fields blank, and click Submit.





Joe: I think you're right. If we want to make sure all those fields are not empty, we'll have to nest an if statement for each field.

Frank: As long as we indent each line of code for each if statement, aren't we OK?

Jill: Technically, yes. I mean, the code will certainly work no matter how many if's we nest, but I'm worried about it getting hard to understand with so much nesting. Just matching up curly braces accurately could be a problem.

Frank: That's true. I think it'd also be a pain having to indent the action code so far... let's see, that's ten form fields, giving us ten nested ifs with ten levels of indentation. Even if we just indent each if two spaces, that's 20 spaces before every line of action code. Yuck.

Joe: But if we indent with tabs, it cuts that in half—10 tabs versus 20 spaces isn't so bad.

Jill: Guys, the issue isn't really about the specific code used to indent the nested if's. It's just not a good coding practice to nest if statements so deep. Think about it like this—we're really talking about one logical test condition, "are all our form fields non-empty?" The problem is, that test condition involves ten different pieces of data, causing us to have to break it into ten separate if statements.

Frank: Ah, I see. So what we need is a way to test all ten pieces of form data in a single test condition, right?


Jill: Yup.

Joe: Then we could write one big test condition that checks all the form fields at once. Awesome!

Jill: Yeah, but we're still missing the piece of the puzzle that lets us combine multiple comparisons within a single test condition...

Test multiple conditions with AND and OR

You can build a test condition for an if statement with multiple checks by connecting them with a **logical operator**. Let's look at how it works with two familiar conditions, !empty(\$subject) and !empty(\$text). This first example involves two expressions joined by the logical AND operator, which is coded using &&.



The AND operator takes two true/false values and gives you true only if they are both true; otherwise the result is false. So in this case both form fields must be non-empty in order for the test condition to be true and the action code for the if statement to run.

The logical OR operator, coded as | |, is similar to AND except that it results in true if either of the true/false values is true. Here's an example:

So the action code for this if statement is executed if either one of the form fields is not empty. Things get even more interesting if you want to isolate one form field as being empty but the other having data, like this:

```
if (empty($subject) && (!empty($text))) {
```

Since this test condition uses AND, both expressions inside of the test condition must be true in order for the action code to be run. This means the Subject form field must be empty, but the Body field must have data. You can reverse this check by moving the negation operator (!) to the other empty () function:

```
if ((!empty($subject)) && empty($text)) ( This is true only if /subject isn't empty but /text is.
```

www.it-ebooks.info

The AND (&&) and OR (|||) logical operators make it possible to structure much more powerful test conditions that would otherwise require additional, often messy, if statements. PHP logic operators make it possible to structure more elegant if statements.

Logical AND is coded as &&, while logical OR is coded as ||.

That's not the number eleven, it's two vertical pipes II—just above backslash (V) on your keyboard.

subject must be empty and stext must be non-empty for this test condition to be true.



Rewrite the highlighted sections of the sendemail.php script so that it uses logical operators in a single if test condition instead of nested if statements.

```
<?php
 $from = 'elmer@makemeelvis.com';
 $subject = $ POST['subject'];
  $text = $ POST['elvismail'];
                                    Here are our nested if statements.
                                    Rewrite them using a single if
 if (!empty($subject)) (
                                    statement with logical operators.
    if (!empty($text)) {
  .......
      $dbc = mysqli connect('data.makemeelvis.com', 'elmer', 'theking', 'elvis store')
       or die('Error connecting to MySQL server.');
      $query = "SELECT * FROM email list";
      $result = mysqli query($dbc, $query)
       or die('Error querying database.');
     while ($row = mysqli fetch array($result)) (
       $to = $row['email'];
       $first name = $row['first name'];
       $last_name = $row['last_name'];
       $msg = "Dear $first name $last name, \n$text";
       mail($to, $subject, $msg, 'From:' . $from);
       echo 'Email sent to ' . $to . '<br />';
      mysqli close($dbc);
                     These braces close the
                     two if statements.
?>
```



Make sure the logical operators in the Send Email script do the same job as the nested if statements.

Modify the code in sendemail.php to use a single if statement that takes advantage of logical operators to check the form field data before sending email messages. Double-check the exercise solution on the following page if you aren't sure about the changes to make.

Upload the new version of the script to your web server and open the sendemail.html page in a web browser. Make sure to leave at least one of the form fields blank, and click Submit. Does the script still prevent the email messages from being sent when a form field is blank?

Dumb Questions


O: Does it matter what order you put two conditions joined by && or | | in an if statement?

A: Yes. The reason is because these two operators are **short-circuited** whenever possible. What this means is that if the first operand is enough to determine the outcome of the expression, the second operand is ignored. As an example, if the first operand in an AND expression is false, this is enough to cause the expression to be false regardless of the second operand, so the second operand is ignored. The same rule applies when the first operand in an OR expression is true.


Q: I've seen PHP code that uses and and or instead of && and | |. How do those work?

A: They're virtually the same as && and | |.

There's a slight difference in how they're evaluated relative to other operators, but if you're careful to use parentheses to make your test conditions clear, then there's essentially no difference.



Form users need feedback



We need to let Elmer know that there was a problem, ideally telling him what form fields were blank so that he can try entering the message again.

Not a problem. Just put an echo statement after the closing brace of the if statement.



That won't work because code <u>after</u> the if statement will always be executed.


Placing the echo statement after the if statement just means it runs **after** the if statement, but it always runs regardless of the outcome of the if. That's not what we need. We need the echo statement to show an error message **only** if the test condition of the if statement is false. You could express our logic as this:

IF subject contains text AND body contains text



X ELSE echo error message

The if statement offers an optional else clause that runs code in the event that the test condition is false. So our error message echo code can go in an else clause, in which case it only gets run when one of the form fields is left empty. Just place the word else after the if statement, and then stick the action code for it inside curly braces:




The else clause executes code when an if test condition is false.



Below is new code for Elmer's sendemail.php script that uses if statements and else clauses to provide feedback, but some of the code has gotten misplaced. Use the magnets to replace the missing code.

```
// We know both $subject AND $text are blank
<?php
  $from = 'elmer@makemeelvis.com';
                                            // $subject is empty
  $subject = $ POST['subject'];
                                                // Everything is fine, send email
  $text = $_POST['elvismail'];
                                                          // Stext is empty
  else (
      // We know we are missing $subject OR $text - let's find out which one
        echo 'You forgot the email subject. <br />';
      else (
        echo 'You forgot the email body text. <br />';
    else (
      while ($row = mysqli_fetch_array($result)) {
        $to = $row['email'];
        $first name = $row['first name'];
        $last name = $row['last name'];
        $msg = "Dear $first name $last name, \n$text";
                                                                empty($text)
        mail($to, $subject, $msg, 'From:' . $from);
                                                                      empty($subject)
        echo 'Email sent to ' . $to . '<br />';
                                                                 empty($text)
      mysqli_close($dbc);
                                                                    empty($subject)
                                                            empty ($subject)
?>
```





All those nested if s and else's are making the script hard to follow. I'd hate to ever have to work on that script! It needs to be simplified before someone gets hurt.

It's always a good idea to simplify code whenever possible, especially nested code that gets too deep.

Too many else clauses with nested if statements can make your code hard to follow. Maybe that wouldn't matter if we never had to look at it again, but that's unlikely. If we ever needed to change the form and add another field, validating it would be trickier than it needed to be because it would be hard to read the code and figure out where the changes need to go.

cleaner

BE the IF code

Your job is to play IF code and clean up the messy nested IF's and ELSE's. Rewrite the code to get rid of the nesting, but make sure it still works correctly.

Hint You might not even need any elses!

```
if (empty($subject) && empty($text)) {
  echo 'You forgot the email subject and body text.<br />';
) else (
                                                          Rewrite this code so
  if (empty($subject) || empty($text)) (
                                                          that it isn't nested
    if (empty($subject) (
      echo 'You forgot the email subject. <br />';
    } else {
      echo 'You forgot the email body text. <br />';
  ) else (
    // Everything is fine. send the email
```



Try out the cleaner if code to make sure it works as expected.

Modify the code in sendemail.php to use if statements similar to those you just wrote that simplify the if nesting. Flip to the solution on the following page if you aren't sure about the changes to make.

Upload the new version of the script to your web server and open the sendemail.html page in a web browser. Experiment with the script by submitting the form with form fields both blank and filled. Does the script display error messages

Dumb Questions

Q: Are a few levels of nesting really that

A: It depends. If you're writing some code that only you will ever see and you think you'll remember exactly what every next line does in six months time when you come back to it to tweak it, nest away.

If on the other hand, you'd like to keep your code as clean and logical as possible, you can use any of the several logic operators you've met so far.

Q: How does else work?

A: In an if...else statement, the else matches anything and everything that doesn't match the if part.


O: Hmm. Okay. Does that mean I could nest if and else in existing if...else statements?

A: Well, you could, but with all that nesting, things would get complex pretty fast and we're trying to avoid resting here!

cleaner BE the IF code Solution

Your job is to play IF code and clean up the messy nested IF's and ELSE's. RRewrite the code to get rid of the nesting, but make sure it still works correctly.

```
if (empty($subject) && empty($text)) {
                     echo 'You forgot the email subject and body text. <br />';
                   } else {
                     if (empty($subject) || empty($text)) (
                       if (empty($subject) (
                         echo 'You forgot the email subject. <br />';
                       ) else (
                         echo 'You forgot the email body text.<br />';
                     } else {
                       // Everything is fine. send the email
Here, we're testing
to see if both the
subject and stext
 variables are empty
                 > if (empty(fsubject) && empty(ftext)) {
                  echo 'You forgot the email subject and body text <br />';
                                                               This code checks to see if fsubject is empty and ftext is not empty.
Here we're testing
to see if stext is
empty and subject
                                                               If we didn't use the AND (&&) to isolate
is not empty.
                                          the non-empty subject/empty body text,
                                                               we could end up getting an extra feedback
                  if ((lempty(fsubject)) && empty(ftext))
                                                               message. Same thing goes for not empty
                  echo 'You forgot the email body text <br /> i subject and empty ftext
                                                            The NOT operator (1) checks for
                                                            fsubject and ftext being non-empty.
And here, we're
                  testing to see if
neither isubject nor
Hext is empty.
```





What would you do to improve the error handling of the Send Email script to make it more helpful?.

It would be cool to show the form along with the error message. Couldn't we just echo the form if the email subject and body text are empty?



Displaying the form would definitely be helpful, as it would save Elmer having to navigate back in his browser.

So in addition to echoing an error message when one of the form fields is empty, we also need to regenerate the HTML form code from PHP by echoing it to the browser. This code shows that PHP is capable of generating some fairly complex HTML code:

```
This PHP code generates the entire HTML

form, starting with the <form> tag.

echo '<form method="post" action="sendemail.php">';

echo '<label for="subject">Subject of email:</label><br/>
'<input id="subject" name="subject" type="text" '.

'size="30" /><br />';

echo '<label for="elvismail">Body of email:</label><br />';

echo '<label for="elvismail" name="elvismail" rows="8" '.

'cols="40"></textarea id="elvismail" name="elvismail" rows="8" '.

'cols="40"></textarea><br />';

echo '<input type="submit" name="submit" value="Submit" />';

echo '</form>';

Since HTML code is riddled with double quotes, it's easier to use single quotes to surround strings of HTML code in PHP.
```

This indentation isn't strictly necessary, but it helps to see _ the structure of the original HTML code.

If you're thinking this code looks a bit chaotic, that's because it is. Just because you **can** do something in PHP doesn't mean you should. In this case, the added complexity of echoing all that HTML code is a problem. This is a big enough chunk of code that generating it via PHP with echo is really not a good option...

You can close

and open blocks

of PHP code to

you are here >

193

Ease in and out of PHP as needed

It's sometimes easy to forget that a PHP script is really just an HTML web page that is capable of holding PHP code. Any code in a PHP script that isn't enclosed by the <?php and ?> tags is assumed to be HTML. This means you can close a block of PHP code and revert to HTML as needed, and then pick back up with a new block of PHP code. This is an extremely handy technique for outputting a chunk of HTML code that is unwieldy to generate through PHP echo statements... like our Send Email form code.


output chunks of HTML code in a <?php \$from = 'elmer@makemeelvis.com'; PHP script. \$subject = \$ POST['subject']; \$text = \$ POST['elvismail']; This ?> tag closes the PHP The form is coded as normal if (empty(\$subject) && empty(\$text)) { block, returning // We know both \$subject AND \$text are blank HTML since this code is us to HTML echo 'You forgot the email subject and body text.
'; outside of PHP tags. <form method="post" action="sendemail.php"> <label for="subject">Subject of email:</label>
 <input id="subject" name="subject" type="text" size="30" />
 <label for="elvismail">Body of email:</label>
 <textarea id="elvismail" name="elvismail" rows="8" cols="40"></textarea>
 <input type="submit" name="submit" value="Submit" /> </form> <?php The <?php tag starts a new PHP block. Since</p> Since we're still inside of the if we're still inside the if action, we have to - action, the HTML code is only output close the if statement before continuing. if both form fields are empty. if (empty(\$subject) && (!empty(\$text))) { echo 'You forgot the email subject.
'; if ((!empty(\$subject)) && empty(\$text)) { echo 'You forgot the email body text.
'; if ((!empty(\$subject)) && (!empty(\$text))) { // Code to send the email Write down anything you think might be limiting about this 3> code. How would you fix it?

www.it-ebooks.info

Use a flag to avoid duplicate duplicate code

The problem with the previous code is that it will have to drop out of PHP and duplicate the form code in three different places (once for each validation error). We can use a true/false variable known as a **flag** to keep track of whether or not we need to output the form. Let's call it \$output_form. Then we can check the variable later in the code and display the form if the variable is true.

So we need to start out the script with <code>Soutput_form</code> set to <code>false</code>, and then only change it to <code>true</code> if a form field is empty and we need to show the form:



By making HTML

code dependent on

Code the HTML form only once


Turning the new validation logic into PHP code involves creating and initializing the new <code>\$output_form</code> variable, and then making sure to set it throughout the validation code. Most important is the new <code>if</code> statement at the end of the code that only displays the form if <code>\$output_form</code> is set to <code>true</code>.

```
an IF statement,
<?php
                                                                       we avoid duplicate
  $from = 'elmer@makemeelvis.com';
                                          We create our new
  $subject = $ POST['subject'];
                                                                       code in our script.
                                          variable here and set
  $text = $ POST['elvismail'];
                                          it to false initially.
  Soutput_form = false; <
  if (empty($subject) && empty($text)) {
    // We know both $subject AND $text are blank
    echo 'You forgot the email subject and body text. <br />';
    Soutput form = true; <
                                                      Set the variable to true if both
                                                      fsubject and ftext are empty so
                                                      that the form is shown.
  if (empty($subject) && (!empty($text))) {
    echo 'You forgot the email subject. <br />';
    Soutput form = true;
                                                  Also set the variable to
                                                   true if subject is empty.
  if ((!empty($subject)) && empty($text)) {
    echo 'You forgot the email body text.<br />';
    Soutput form = true;
                                         And set the variable to
                                                true if stext is empty.
  if ((!empty($subject)) && (!empty($text))) {
    // Code to send the email
                                                                We've dropped out of PHP code, but
                            This if statement checks the
                                                                anything prior to the closing } is still
                            foutput_form variable and displays the form if it is true.
                                                                considered part of the if action - in this
                                                               case it's the HTML code for the form.
  <form method="post" action="sendemail.php">
    <label for="subject">Subject of email:</label><br />
    <input id="subject" name="subject" type="text" size="30" /><br />
    <label for="elvismail">Body of email:</label><br />
    <textarea id="elvismail" name="elvismail" rows="8" cols="40"></textarea><br />
    <input type="submit" name="submit" value="Submit" />
  </form>
                Don't forget to jump
back into PHP code and
                                                            The HTML code only appears once since
<?php
                                                             we've crunched all the logic for displaying
                close the if statement
                                                             it into a single variable, foutput form.
```

The new form is better, but I still have to retype the fields I had typed in correctly, which is really annoying.


HTML alone can't preserve form data.

When Elmer submits the Send Email form with an empty field, the sendemail.php script catches the error and generates a new form. But the new form is pure HTML code, which can't possibly know anything about any data Elmer might have entered earlier. So we're generating a clean new form as part of the validation, which is wiping out any data Elmer might have entered.



Ack. We can't get around the fact that a new form will have to be generated in the PHP script. But we need a way to remember any data Elmer might have already entered, and plug it back into the new form so that Elmer can focus solely on filling out the form field that he accidentally left empty...


| | Sharpen your pencil | first form field filled | orm should look like after he submits it with only the out. Then write down how you think each of the two should be altered to carry out this new functionality. |
|---|---|-------------------------|--|
| | | Sul | omit . |
| | sendemail.php | i . | sendemail.html |
| | | | ······ |
| | | | |
| | | ******** | |
| *************************************** | | | |
| | | | |
| | | ********** | |
| *************************************** | *************************************** | | |



A form that references itself

How can it be possible to remove sendemail.html from the Send Email form equation? The answer is that we're not actually eliminating any HTML code, we're just moving it to the PHP script. This is made possible by the fact that a PHP script can contain HTML code just like a normal web page. So we can structure our script so that it not only processes the form on submission but also displays the form initially, which is all sendemail.html was doing.

The key to the sendemail.php script being able to fill the role left by sendemail.html is the form action. Since the script itself now contains the HTML form, the form action leads back to the script... a **self-referencing form**.



An HTML form that is part of the PHP script that processes it is known as self-referencing.

The script initially shows the form and then processes it when it is submitted. Processing the form involves either sending emails or displaying the form again with an error message.

To understand what's going on here, think about the first time Elmer visits the page (script). An empty form is generated as HTML code and displayed. Elmer fills out a field of the form and clicks Submit. The script processes its own form, and displays an error message if any data's missing. More importantly, the script displays the form again, but this time it includes any data Elmer has already entered. When a form's smart enough to remember data entered into it in prior submissions, it's known as a **sticky form**... the data sticks to it!


Sticky forms remember the data the user has already correctly entered.



How do you think we can tweak Elmer's application to make the form fields sticky?

Point the form action at the script

As we've seen several times, the action attribute of the <form> tag is what connects a form to a PHP script that processes it. Setting the action of Elmer's form to sendemail.php works just fine in allowing it to process itself, which is the first step toward form stickiness. In fact, the form already has its action attribute set to the script:



This code works, assuming you don't ever rename the script and forget to update the code. But there's a better way that works no matter what because it doesn't rely on a specific script filename. It's the built-in PHP superglobal variable \$_SERVER['PHP_SELF'], which stores the name of the current script. You can replace the script URL in the form action to \$_SERVER['PHP_SELF'], and not ever have to worry about updating anything if you ever need to rename the script.

The only catch is that \$_SERVER['PHP_SELF'] is PHP code, which means you have to echo its value so that it is output as part of the HTML code, like this:

Instead of hardcoding the name of our script, we can tell it to reference itself by using the SERVERC'PHP_SELF'] superglobal.

<form action="<?php echo \$ SERVER['PHP SELF']; ?>" method="post">

Granted, using \$_SERVER['PHP_SELF'] instead of the script name isn't an earth shattering improvement but it's one of the many little things you can do to make your scripts easier to maintain over time.


\$_SERVER['PHP_SELF'] stores away the name of the current script.



Try out the new self-referencing script with improved form validation logic.

Modify the code in sendemail.php to use the <code>Soutput_form</code> variable to selectively display the form as shown a few pages back. Also change the action attribute of the <code><form></code> tag so that the form is self-referencing.

You no longer need the sendemail.html page on your web server, so feel free to delete it. Then upload the new version of the sendemail.php script to your web server and open the script in a web browser. How does it look?



First things first - we'll get to the sticky stuff in a moment.


| nessage the first time the form is shown: | |
|---|---|
| | , |
| | |
| | |

Write down why you think the script is displaying an error

Check to see if the form has been submitted

The problem is that the script can't distinguish between the form being displayed for the first time and it being submitted with incomplete data. So the script reports missing data the very first time the form is displayed, which is confusing. The question is, how can we check to see if the form is being submitted? If we know that, we can make sure we only validate data on a submission.

Remember how, when a form is submitted using the POST method, its data is stored away in the \$_POST array? If the form hasn't been submitted, then the \$_POST array isn't filled with any data. Or to put it another way, the \$_POST array hasn't been set. Any guess what function we could call to see if the \$_POST array's been set?



Since every form has a Submit button, an easy way to check to see if a form has been submitted is to see if there's \$_POST data for the Submit button. The data's just the label on the button, which isn't important. What's important is simply the existence of \$_POST['submit'], which tells us that the form has been submitted. Just make sure that 'submit' matches up with the id attribute of the Submit button in the form code.

The \$_POST superglobal allows us to check and see if a form has been submitted.

Dumb Questions

Q: How does knowing if the form was submitted stop us from accidentally displaying validation error messages?

A: The reason the error messages are being shown incorrectly is because the script doesn't distinguish between the form being submitted vs. being displayed for the first time. So we need a way to tell if this is the first time the form is being shown, in which case empty form fields are perfectly fine—it's not an error. We should *only* validate the form fields if the form's been submitted, so being able to detect a form submission is very important.

Q: So why don't we check to see if real form data's set, instead of the Submit button?

A: It would work perfectly fine to check \$_POST['subject'] or \$_POST['elvismail'], but only for this particular form. Since every form has a Submit button that can be consistently named submit, checking \$_POST['submit'] gives you a reliable way to check for form submission in all of our scripts.



The Send Email Script Up Close

```
We check the value of & POST"submit'J.
<?php
                                             If the form has never been submitted,
  if (isset($ POST['submit']))
    $from = 'elmer@makemeelvis.com';
                                             this will be unset
    $subject = $ POST['subject'];
    $text = $ POST['elvismail'];
    $output form = false;
    if (empty($subject) && empty($text)) [
      // We know both $subject AND $text are blank
      echo 'You forgot the email subject and body text. <br />';
      Soutput form = true;
    if (empty($subject) && (!empty($text))) {
      echo 'You forgot the email subject. <br />';
      Soutput form = true;
    if ((!empty($subject)) && empty($text)) (
      echo 'You forgot the email body text. <br />';
      $output form = true;
    if ((!empty($subject)) && (!empty($text))) (
      // Code to send the email
                              This parenthesis closes the
                              first if, which tells us if
                              the form was submitted.
  else (
    Soutput form = true;
                                 If the form's never been
                                 submitted, we definitely
                                 need to show it!
  if ($output form) {
3>
  <form method="post" action="<?php echo $ SERVER['PHP SELF']; ?>">
    <label for="subject">Subject of email:</label><br />
    <input id="subject" name="subject" type="text" size="30" /><br />
    <label for="elvismail">Body of email:</label><br />
    <textarea id="elvismail" name="elvismail" rows="8" cols="40"></textarea><br />
    <input type="submit" name="submit" value="Submit" />
  </form>
<?php
?>
```

www.it-ebooks.info

203



Cool. So we can now detect the form submission and show error messages correctly. But we still haven't made the form fields sticky, right?

That's right. Detecting the form submission is important, but we still need to plug the sticky form data back into the form.

Knowing if the form's been submitted is an important part of making it sticky, but it isn't the only part. The part we're missing is taking any form data that was submitted and plugging it back into the form as the form is being output. You can set an input form field using the value attribute of the HTML <input> tag. For example, this code presets the value of an input field using the value attribute:

This value is hardcoded - it's always the same every time the form is shown.

<input name="subject" type="text" value="Fall Clearance!">

But we don't want to hardcode a specific value. We want to insert a piece of data from a PHP variable. How is that possible? Remember that we've used echo to dynamically generate HTML code from PHP in other situations. In this case, we can use echo to generate a value for the value attribute from a PHP variable, like this:

Since we're switching to PHP to echo the variable, we have to use a <?php tag.

The variable is echoed using the familiar echo statement.

<input name="subject" type="text" value="<?php echo \$subject; ?>">

And to return back to HTML, we close up the -PHP code with the ?> tag.

For a text area input field, we echo the sticky data in between the <textarea> and </textarea> tags instead of using the value attribute.


Elmer's form can then be modified similarly to take advantage of sticky data:

```
<form method="post" action="<?php echo $ SERVER['PHP SELF']; ?>">
  <label for="subject">Subject of email:</label><br />
  <input id="subject" name="subject" type="text" size="30"</pre>
   value="<?php echo $subject; ?>"/><br />
  <label for="elvismail">Body of email:</label><br />
  <textarea id="elvismail" name="elvismail" rows="8" cols="40">
  > <?php echo $text; ?></textarea><br />
  <input type="submit" name="submit" value="Submit" />
</form>
```



Check to see how sticky Elmer's data really is.

Change the code in sendemail.php to check \$_POST for the form submission, as well as adding echo code to the form so that its fields are sticky. Upload the new version of the script to your web server and open the script in a web browser. Experiment with different form field values, including leaving one or both fields empty, and submit it a few times.




Some users are still disgruntled

Form validation has gone a long way toward dealing with Elmer's frustrated customers, particularly those who were receiving blank emails. But not everyone is happy. It seems a few people are receiving duplicate emails... remember this guy from earlier in the chapter?



Elmer knows he didn't send a message more than once, leading him to suspect that maybe some users have accidentally subscribed to his email list more than once. Not a problem, just use the Remove Email page/script from the last chapter to remove the user, right?

Unfortunately, it's not that simple. Removing Elbert using his email address will completely delete him from the email_list table, causing him to no longer receive any email messages from Elmer. We need a way to only delete Elbert's **extra** rows from the table, making sure to leave one.



206

Hmm. The problem is that there are multiple rows in the table but no way to distinguish them from each other. Without a way to isolate them individually, any DELETE we try to do will delete all of them.



Joe: Maybe our Add Email form should check for duplicate email addresses before adding new users. That would fix it, right?

Frank: Excellent idea.

Jill: Yes, that would solve the problem moving forward, but it doesn't help us deal with duplicate email addresses that are already in the database.

Frank: Right. What if we tried to use a different column in the table to delete the extra rows, like last name?

Jill: I wondered about that, but using a last name is potentially even worse than an email address. What if we wanted to delete someone named John Smith from our mailing list, and we ran the following SQL code:

DELETE FROM email_list WHERE last_name = 'Smith'

Joe: We wouldn't just delete John Smith from our table; we'd be deleting Will Smith, Maggie Smith, Emmitt Smith...

Frank: Wow, that wouldn't be good. Last names are more likely to be common across rows than email addresses, and first names would be even worse than that. We could lose dozens and dozens of rows with one simple query.

Jill: Exactly. We can't risk using a WHERE clause that will delete rows we need to keep. We need to be certain we can pinpoint just the ones we want to remove.

Joe: So what the heck do we do? We can't use email, last name, or first name in our WHERE clause.

Frank: We're out of columns in our table to use. Looks like we're out of luck.

Jill: Not necessarily. What we really need is something to make each row of the table unique—then we could pinpoint rows without any trouble. And just because we don't currently have a column that has a unique value for each row doesn't mean we can't add one.

Joe: A new column? But we've already decided on our table structure.

Frank: Yeah, but what we've got isn't meeting our needs. You're right that it would be better if we had realized this beforehand, so we could have designed our table accordingly, but it's not too late to fix what we've got.

Joe: OK, but what would we call our new column? What data would we put into it?

Jill: Well, since its purpose would be to uniquely identify each row in the table, we could call it identifier, or maybe just id for short.

Frank: Nice, and we can fill the id column with a different ID number for each row, so when we execute our DELETE, we'll be removing rows based on a unique number, instead of an email address or surname.

Joe: Exactly. It's really a great idea, isn't it? I'm so glad I thought of it.


Table rows should be uniquely identifiable

Part of the whole idea of sticking something in a database is that later on you'd like to look it up and do something with it. Knowing this, it's incredibly important for each row in a table to be **uniquely identifiable**, meaning that you can specifically access one row (and only that row!). Elmer's email_list table makes a dangerous assumption that email addresses are unique. That assumption works as long as no one accidentally subscribes to the mailing list twice, but when they do (and they will!), their email address gets stored in the table twice... no more uniqueness!

| first_name | last_name | email | | 1 |
|------------|-----------|-----------------------------|----------|--------|
| Denny | Bubbleton | denny@mightygumball.net | ~ | |
| Irma | Werlitz | iwer@aliensabductedme.com |] | And |
| Elbert | Kreslee K | elbert@kresleesprockets.biz | — | - Eimi |
| Irma | Kreslee | elbert@kresleesprockets.biz | - | can |

When you don't have a column of truly unique values in a table, you should create one. MySQL gives you a way to add a unique integer column, also called a **primary key**, for each row in your table.

What Elmer's table should contain:



Hey genius, you know if we want to make a change to the table structure, we have to do a DROP TABLE and then recreate it from scratch. Elmer's email data will be toast!

It's true that DROP TABLE would destroy Elmer's data. But SQL has a another command that lets you make changes to an existing table without losing any data.

It's called ALTER TABLE, and we can use it to create a new column without having to drop the table and destroy its data. Here's what the general format of an ALTER TABLE statement looks like for adding a new column to a table:

The name of the table to be altered.

The name of the new column to be added.

ALTER TABLE table name ADD column name column type

The data type of

We can use the ALTER TABLE command to add a new column to the email list table, which we'll name id. We'll give the id column a data type of INT, since integers work great for establishing uniqueness. Some other information is also required, as this code reveals:

The name of the table that we want to alter.

We want to ADD a new column, which we call id.

This tells the MySQL server to add I to the value stored in this column for each new row that's inserted.

ALTER TABLE email list ADD id INT NOT NULL AUTO INCREMENT FIRST,

ADD PRIMARY KEY (id)

it an INTeger.

The data type of FIRST tells MySQL to make the new column the column makes first in the table. This is optional, but it's good form to put your id column first

This little chunk of code tells MySQL that the new id column is the primary key for the table. More on that in just a sec!

This ALTER TABLE statement has a lot going on because primary keys have to be created with very specific features. For example, NOT NULL tells MySQL that there must be a value in the id column—you can never leave it blank. AUTO INCREMENT further describes the traits of the id column by causing it to automatically get set to a unique numeric value when a new row is inserted. As its name suggests, AUTO INCREMENT automatically adds one to the last id value used in a row and places this value into the id column when you INSERT a new row into your table. Finally, PRIMARY KEY tells MySQL that each value in the id column is unique, but there's more to it than just uniqueness...

you are here >

209

Primary keys enforce uniqueness

A **primary key** is a column in a table that distinguishes each row in that table as unique. Unlike normal columns, which could also be designed to be unique, only one common can be made the primary key. This provides a clear choice for what column to use in any queries that need to pinpoint specific rows.

In order to ensure this uniqueness for primary keys, MySQL imposes a bunch of restrictions on the column that has been declared as PRIMARY KEY. You can think of these restrictions as rules to be followed as you work with primary keys:

A primary key is a column in your table that makes each row unique.

The five rules of primary keys:



The data in a primary key can't be repeated.

Two rows should never have the same data in their primary keys. No exceptions—a primary key should always have unique values within a given table.



A primary key must have a value.

If a primary key was left empty (NULL), then it might not be unique because other rows could potentially also be NULL. Always set your primary keys to unique values!



The primary key must be set when a new row is inserted.

If you could insert a row without a primary key, you would run the risk of ending up with a NULL primary key and duplicate rows in your table, which would defeat the purpose.



A primary key must be as efficient as possible.

A primary key should contain only the information it needs to be unique and nothing more. That's why integers make good primary keys—they allow for uniqueness without requiring much storage.



The value of a primary key can't be changed.

If you could change the value of your key, you'd risk accidentally setting it to a value you already used. Remember, it has to remain unique at all costs.

The id column in Elmer's table doesn't have repeat data, has a value for every row, is automatically set when a new row is inserted, is compact, and doesn't change. Perfect!

| id | first_name | last_name | email | | |
|----|------------|-----------|---------------------------|--|--|
| 1 | Denny | Bubbleton | denny@mightygumball.net | | |
| 2 | Irma | Werlitz | iwer@aliensabductedme.com | | |



Alter Elmer's table and try out inserting a new row of data with a primary key.

Using a MySQL tool such as the MySQL terminal or the SQL tab of phpMyAdmin, enter the ALTER TABLE statement to add a primary key column named id:

```
ALTER TABLE email_list ADD id INT NOT NULL AUTO_INCREMENT FIRST,
ADD PRIMARY KEY (id)
```

Now insert a new customer to the database to see if the id column is automatically set for the new row. Here's an example of an INSERT statement to use (notice the primary key isn't mentioned):

```
INSERT INTO email_list (first_name, last_name, email)
VALUES ('Don', 'Draper', 'draper@sterling-cooper.com')
```

Finally, issue a SELECT statement to view the contents of the table and see the new primary key in all its glory! Just in case you've forgotten, here's the SELECT statement:


```
SELECT * FROM email list
```

The new id column is auto-incremented so that it remains unique for the new row of data.

```
mysql> SELECT * FROM email_list;


| id | first_name | last_name | email |
| 1 | Denny | Bubbleton | denny@mightygumball.net |
| 2 | Irma | Werlitz | iwer@aliensabductedme.com |
| 3 | Elbert | Kreslee | elbert@kresleesprockets.biz |
| 4 | Irma | Kreslee | elbert@kresleesprockets.biz |
| 5 | Don | Draper | draper@sterling-cooper.com |
| 5 rows in set (0.0005 sec)
```

Okay, so now every row in the table has a unique primary key. How does that help? Elmer still deletes based on email addresses.



Frank: That's right! So we just need to change the form so that the user enters the ID of a customer instead of their email address. No problemo!

Jill: Actually, big problemo. The user has no way of knowing the ID of a customer without somehow finding them in the database. In fact, the user doesn't know anything about the database structure. Maybe what we need is to rethink the form so that it lists out all the names and email addresses in a list with checkboxes next to each one. Here, I'll sketch it for you.



Frank: Nice sketch, but how does that help Elmer isolate a customer for deletion using their ID?

Joe: Hmm. What if we stored the customer ID in the value of the checkbox. That way it isn't actually visible, but the script can get to it.

Jill: That's a great idea. So we could generate the form automatically in a loop by doing a SELECT to get all the data, and then creating each checkbox input field from a row of query data.


Joe: Cool. But what happens when the Submit button is pressed? What does \$ POST have in it?

Frank: Hang on, Joe, we'll get there in a minute. Let's just start by building this part of the script, the part that displays all the data from the table and writes out those checkboxes...



PHP & MySQL Magnets


Use the magnets below to finish the missing code for the Remove Email script, which presents a series of checkboxes for the customers in Elmer's database. Note that this code just creates the form; don't worry about the code that performs the DELETE just yet.





PHP & MySQL Magnets Solution

Use the magnets below to finish the missing code for the Remove Email script, which presents a series of checkboxes for the customers in Elmer's database. Note that this code just creates the form; don't worry about the code that performs the DELETE just yet.




From checkboxes to customer IDs

The checkbox code generated by the Remove Email script is simple HTML with our primary key (id) stuffed into the value attribute of the <input> tag. There's one small, but very important change from ordinary checkbox HTML code, though. You might have noticed square brackets ([]) at the end of the checkbox name—they serve a vital purpose.

echo '<input type="checkbox" value="' . \$row['id'] . '" name="todelete[]">';


The square brackets result in the creation of an array within \$_POST that stores the contents of the value attribute of every checked checkbox in the form. Since each checkbox's value attribute contains a primary key, each value in the todelete array is the ID of the row in our table that needs to be deleted. This makes it possible for us to loop through the todelete array and issue an SQL query to delete each customer that is checked in the form.

The square brackets at the end of the checkbox name automatically put the checkbox values in an array we've named "todelete[]".




Loop through an array with foreach

The foreach loop takes an array and loops through each element in the array without the need for a test condition or loop counter. As it steps through each element in the array, it temporarily stores the value of that element in a variable. Assuming an array is stored in a variable named \$customers, this code steps through each one:




So if we want to loop through the customer IDs stored in the \$_POST array in the Remove Email script, we can use the following foreach code:



The \$delete_id variable holds the value of each array element as the loop progresses through them one at a time.

We can use this variable to access the ID of each customer and then delete them from the table.




With the foreach loop now stepping through each of the **checked** checkboxes in the Remove Email form, we just need to add code inside of the loop to issue a DELETE query and actually delete each row from the email_list table.

We constructed this array so that it only holds customers that were checked in the Remove Email form.



Finish the code for Elmer's new and improved removeemail.php script so that it deletes customers that have been checked in the form when the form is submitted.

```
$dbc = mysqli_connect('data.makemeelvis.com', 'elmer', 'theking', 'elvis_store')
   or die('Error connecting to MySQL server.');
 // Delete the customer rows (only if the form has been submitted)
 if (_____) (
   foreach ($_POST['todelete'] as $delete_id) {
     echo 'Customer(s) removed.<br />';
 // Display the customer rows with checkboxes for deleting
 $query = "SELECT * FROM email list";
 $result = mysqli query($dbc, $query);
 while ($row = mysqli fetch array($result)) {
   echo '<input type="checkbox" value="' . $row['id'] . '" name="todelete[]" />';
   echo $row['first name'];
   echo ' ' . $row['last_name'];
   echo ' ' . $row['email'];
   echo '<br />';
 mysqli close($dbc);
?>
 <input type="submit" name="submit" value="Remove" />
                                                                removeemail.php
</form>
```






Take Elmer's newly revamped Remove Email script for a spin.

Modify the code in the removeemail.php script so that it generates customer checkboxes instead of using the old email text field. Then add the code to delete customers whenever the form's submitted. Also change the action attribute of the <form> tag so that the form's self-referencing.

Now that removeemail.php uses a self-referencing form, you no longer need the removeemail.html page on your web server, so feel free to delete it. Then upload the new version of removeemail.php to your web server and open the script in a web browser. Check off a few customers and click Submit. The form immediately changes to reflect the customer removal.





if, else

The PHP if statement makes

decisions based on whether or not

something is true. Give it a true/

will let you make all kinds of cool decisions. An else clause can be

added to an if statement to give

it an alternate action.

false test condition and some action code, and an if statement

Your PHP & MySQL Toolbox

You bagged quite a few new PHP and MySQL skills while taking Elmer's web application to a whole new level...

This SQL statement changes the structure of a table, such

ALTER TABLE

as adding a new column of data. This allows you to alter a table structurally without having to drop it and start over.

==, <>, !=, <, >, ...

Comparison operators that can be used to construct test conditions that compare values to each other. These are often used to control if statements and loops.

foreach

A PHP looping construct that lets you loop through an array one element at a time without using a test condition. Inside the loop, you can access each element of the array.

isset(), empty()

The negation operator, or NOT

operator, reverses a true/false

value. So true becomes false and

false becomes true.

The built-in PHP isset() function tests to see if a variable exists, which means that it has been assigned a value. The empty() function takes things one step further and determines whether a variable contains an empty value (O, an empty string, false, or NULL).

&&, OR

These are logical operators that are used to build expressions involving true/false values. Combining two values with && (AND) results in true only if both values are true. Combining values with 11 (OR) results in true if either of the values is true.

5 working with data stored in files




Don't believe the hype...about databases, that is. Sure, they work wonders for storing all kinds of data involving text, but what about binary data? You know, stuff like JPEG images and PDF documents. Does it really make sense to store all those pictures of your rare guitar pick collection in a database table? Usually not. That kind of data is typically stored in files, and we'll leave it in files. But it's entirely possible to have your virtual cake and eat it too—this chapter reveals that you can use files and databases together to build PHP applications that are awash in binary data.

this is a new chapter

Virtual guitarists like to compete


Apparently creating art for art's sake isn't always enough because players of the hot new game Guitar Wars are quite enamored with competitive virtual guitar playing. So much so that they regularly post their high scores at the Guitar Wars web site, which you are now in charge of maintaining. Problem is, there isn't currently a good way to verify the scores.

The Guitar Wars application allows users to add their own scores to the high score list.




picture The proof is in the rockin'


Visual verification of a high score is what we need to determine who's for real and who isn't. So the Guitar Wars application needs to allow users to submit a screen shot of their high score when posting their score. This means the high score list will not only be a list of scores, names, and dates, but also a list of images (screen shots).



The application needs to store images

Currently, the Guitar Wars high score application keeps track of three pieces of information: the date and time of a new score, the name of the person submitting the score, and the score itself. This information is entered through a form as part of the application's user interface, after which it gets stored in a MySQL database table called guitarwars.





you are here > 227



The Guitar Wars high score application will have to change to accommodate uploadable image files for high score screen shots. Circle and annotate the parts of the application that must change to support user-submitted images.

```
<html xmlns="http://www.w3.org/1999/xhtml" xml:lang="en" lang="en">
 <title>Guitar Wars - High Scores</title>
  k rel="stylesheet" type="text/css" href="style.css" />
</head>
<body>
  <h2>Guitar Wars - High Scores</h2>
  Welcome, Guitar Warrior, do you have what it takes to crack the
  high score list? If so, just <a href="addscore.php">add your own
  score</a>.
   <hr />
   $dbc = mysqli_connect('www.quitarwars.net', 'admin', 'rockit', 'gwdb');
   // Retrieve the score data from MySQL
   $query = "SELECT" * FROM guitarwars";
   Sdata = mysqli_query($dbc, $query);
   // Loop through the array of score data, formatting it as HTML
   echo '';
   while ($row = mysqli_fetch_array($data)) (
     // Display the score data
     echo '';
     echo '<span class="score">' . $row['score'] . '</span><br />';
echo '<strong>Name:</strong> ' . $row['name'] . '
echo '<strong>Date:</strong> ' . $row['date'] . '
    echo '';
    mysqli_close($dbc);
  2>
  </body>
   </html>
```



This file doesn't need to change, so you don't have to worry about it



The complete source code for the Guitar Wars application is available for download from the Head First Labs web site:

www.headfirstlabs.com/books/hfphp

!......


guitarwars

index.php

| id | date | name | |
|----|---------------------|-----------------|--------|
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 |

```
<html xmlns="http://www.w3.org/1999/xhtml" xml:lang="en" lang="en">
  <head>
    <title>Guitar Wars - Add Your High Score</title>
    k rel="stylesheet" type="text/css" href="style.css" />
  </head>
  <body>
    <h2>Guitar Wars - Add Your High Score</h2>
   if (isset($_POST['submit'])) (
      // Grab the score data from the POST
      $name = $_POST['name'];
     $score = $_POST['score'];
     if (!empty($name) && !empty($score)) {
        // Connect to the database
       $dbc = mysqli_connect('www.guitarwars.net', 'admin', 'rockit', 'gwdb');
       // Write the data to the database
       Squery = "INSERT INTO guitarwars VALUES (0, NOW(), '$name', '$score')";
       mysqli_query($dbc, $query);
       // Confirm success with the user
       echo 'Thanks for adding your new high score!';
       echo '<strong>Name:</strong> ' . $name . '<br />';
echo '<strong>Score:</strong> ' . $score . '';
       echo '<a href="index.php">&It;&It; Back to high scores</a>';
       // Clear the score data to clear the form
       Sname = "";
       $score = "";
       mysqli close ($dbc);
     else (
       echo 'Please enter all of the information to add ' .
         'your high score.';
?>
  <form method="post" action="<?php echo $_SERVER['PHP_SELF']; ?>">
   <label for="name">Name:</label><input type="text" id="name" name="name"
value="<?php if (!empty($name)) echo $name; ?>" /><br />
    <label for="score">Score:</label><input type="text" id="score" name="score"</pre>
     value="<?php if (!empty($score)) echo $score; ?>" />
    <hr />
    <input type="submit" value="Add" name="submit" />
 </form>
</body>
</html>
```

addscore.php



Planning for image file uploads in Guitar Wars

Although it may not seem like a big deal to add support for uploadable screen shot images to Guitar Wars, the application must change in a variety of ways. For this reason, it's a good idea to have a plan of attack before diving into any code. Let's nail down the steps required to revamp the Guitar Wars high scores for screen shots.

screenshot

Use ALTER to add a screenshot column to the table.

First off is the database, which needs a new column for storing the name of each screen shot image file. Since we plan on putting all image files in the same folder, all we need to store in the database is the filename itself (no path).

Change the Add Score form so that it uses a file input field to allow image file uploads.

The Add Score page already has a form for adding scores, so we need to modify that form and give it a file input field. This input field works in conjunction with the web browser to present the user with a user interface for selecting a file to upload.

Screen shot: Choose File phizsscore.gif

Write a query to INSERT the screen shot image filename into the screenshot column of the table.

The Add Score script that processes the form for adding scores must also take into consideration the new file input form field, and handle inserting a screen shot image filename into the screenshot column when inserting a new high score row into the guitarwars table.

phizsscore.gif

Change the main Guitar Wars page to show screen shot images for the high scores.

Last on the laundry list of changes involves the main index.php Guitar Wars page, which must be changed to actually show the screen shot image for each high score that is displayed.



The high score database must be ALTERed

In addition to a variety of PHP scripting tweaks, the image-powered Guitar Wars application needs a new column in the guitarwars table to store screen shot image filenames. Enter SQL, which offers a statement called ALTER that is capable of modifying tables in all kinds of interesting ways, including adding new columns of data. You used the ALTER statement in the previous chapter to tweak Elmer's email_list table, but let's recap how the command works.

ALTER TABLE guitarwars DROP COLUMN score

The DROP COLUMN) statement drops an entire column from a table.

OK, maybe that's a dangerous example since it reveals how to drop an entire column from a table, data and all. Yet there certainly may be a situation where you need to remove a column of data from a table. It's more likely that you need to add a column of data, as is the case with Guitar Wars. This is made possible by ADD COLUMN, which is one of several table alterations you can carry out with ALTER.

The ALTER statement is used to change the structure of a database.

The ALTER statement is often followed by TABLE to indicate that you're going to alter a table. It's also possible to alter the structure of the entire database with ALTER DATABASE, but that's another story.

ADD COLUMN

Adds a new column to a table—just specify the name of the column and its type following ADD COLUMN.

ADD COLUMN age TINYINT

CHANGE COLUMN

Changes the name and data type of a column—just specify the name of the old column, new column, and new data type following CHANGE COLUMN.

ALTER TABLE guitarwars CHANGE COLUMN score high_score INT

DROP COLUMN

Drops a column (and any data stored in it) from a table—just specify the name of the column following DROP COLUMN.

ALTER TABLE guitarwars DROP COLUMN age

MODIFY COLUMN

Changes the data type or position of a column within a table—just specify the name of the column and its new data type following MODIFY COLUMN. To change the position of a column, specify the name of the column and its exact position (FIRST is the only option here) or a relative position (AFTER another existing column, specified by name).

ALTER TABLE guitarwars
MODIFY COLUMN date DATETIME AFTER age



Write an SQL statement that adds a new column named screenshot to the guitarwars table. Make sure to give the new column a suitable MySQL data type. Then write another SQL query to check the structure of the table and make sure the column was successfully added.

quitarwars

| | | name | store | screenshot |
|----|---------------------|-----------------|--------|------------|
| id | date | | 127650 | |
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | |
| 0 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 2 | | Eddie Vanilli | 345900 | |
| 3 | 2008-04-23 09:06:35 | | 282470 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | | |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | |
| - | | Kenny Lavitz | 64930 | |
| 6 | 2008-04-23 14:09:50 | Keility Lovinz | | |

| Write the statement that adds a column here. | |
|--|--|
| | |
| | |
| | |
| | |
| | |
| Write the other SQL statement here. | ······································ |
| 8 | |
| | |
| | |

you are here >

233

Sharpen your pencil Solution

Write an SQL statement that adds a new column named screenshot to the guitarwars table. Make sure to give the new column a suitable MySQL data type. Then write another SQL query to check the structure of the table and make sure the column was successfully added.

The ALTER statement adds a new screenshot column to the guitarwars table.

quitarwars

| 1.4 | data name | | screenshot |
|--|--|---|---|
| | THE STATE OF THE S | 127650 | |
| 2008-04-22 14:37:34 | Paco Jastorius | | |
| | Nevil Johansson | 98430 | |
| The second secon | Eddie Vanilli | 345900 | |
| | | 282470 | |
| | | | |
| 2008-04-23 09:13:34 | | | |
| 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| | date 2008-04-22 14:37:34 2008-04-22 21:27:54 2008-04-23 09:06:35 2008-04-23 09:12:53 2008-04-23 09:13:34 2008-04-23 14:09:50 | date 2008-04-22 14:37:34 Paco Jastorius 2008-04-22 21:27:54 Nevil Johansson 2008-04-23 09:06:35 Eddie Vanilli 2008-04-23 09:12:53 Belita Chevy 2008-04-23 09:13:34 Ashton Simpson | date 2008-04-22 14:37:34 Paco Jastorius 127650 2008-04-22 21:27:54 Nevil Johansson 98430 2008-04-23 09:06:35 Eddie Vanilli 345900 2008-04-23 09:12:53 Belita Chevy 282470 2008-04-23 09:13:34 Ashton Simpson 368420 |

Since the column is new, it starts out empty (NULL) for existing rows in the table.

The ALTER statement doesn't affect any of the other table data.

ALTER TABLE guitarwars

ADD COLUMN screenshot varchar (64)

ADD COLUMN indicates that we want to alter the table by adding a new column of data.

The name and data type of the new column are specified last in the SQL query - 64 characters are enough to accommodate most image filenames, although you can make the column even longer if you want to be extra safe.

The name of the table to be

DESCRIBE guitarwars

This statement displays the structure of the table, including the column names and their data types.

The first — step is done!

Use ALTER to add a screenshot column to the table.

234



Add the screenshot column to the guitarwars table.

Using a MySQL tool, execute the ALTER statement to add the screenshot column to the guitarwars table. Then issue the DESCRIBE statement to take a look at the table structure and make sure the column was added.

Issuing the DESCRIBE statement reveals the new screenshot column.

| Pield | Type | Null | Key | Default | |
|---|--|------------------------------|-----|-----------------------------------|----------------|
| id date name score icreenshot | timestamp varchar(32) int([1) varchar(64) | I NO I NO I NO I NO | PRI | NULL CURRENT_TIMESTAMP NULL | #Wto_increment |

You can construct the initial guitarwars table by downloading the example code for Guitar Wars, and then executing the SQL query found in the file guitarwars.sql.

Dumb Questions

Q: Do new columns added with ALTER have to be added to the end of a database table?

A: No, they can be added anywhere. But keep in mind that the order of the columns in a table isn't terribly important. In other words, you can structure query results so that data is organized in any order you want. But maybe you like the sense of structural order brought about by a specific ordering of columns, in which case you may want to add a column in an exact location. You can do this by tacking on the keyword FIRST to the ALTER query. Or use AFTER column to place a column relative to another column:

ALTER TABLE guitarwars ADD COLUMN age TINYINT AFTER name

If you don't specify where a new column is added, it defaults to the end of the table.

Q: What happens to the existing high score database rows of data after adding the new screenshot column?

A: Since the ALTER statement only affects the structure of a database, the new screenshot column is empty for all pre-existing rows of high scores. While it's possible to populate the screenshot column of future rows, pre-existing rows all have an empty screenshot column.

Q: Can screen shot filenames still be added to the pre-existing rows?


A: Yes, they definitely can, and you would use the UPDATE SQL statement to do so. There is nothing stopping you from manually uploading image files to the web server and then using UPDATE to fill in the screen shot filenames for existing scores. But remember that the whole idea here is user-submitted image files, so it makes sense to allow users to upload their own screen shot images. And they can do exactly this by using the improved image-powered Add Score script you're about to build...

you are here >

235

How do we get an image from the user?

With a new column added to the high score database, we're ready to focus on allowing the user to upload an image file. But how exactly is that possible? FTP? Mental telepathy? This actually leads back to the Add Score form, where we can use a form field to allow the user to select an image file to upload.





The Add Score Form Up Close

This form attribute tells the form to use a special type of encoding required for file uploading – it affects how the POST data is bundled and sent when the form is submitted.

Establishes a maximum file size for file uploads, in this case 32 KB (32,768 bytes).

This is a selfreferencing form.

<form enctype="multipart/form-data" method="post" action="<?php echo \$_SERVER['PHP_SELF']; ?>">

<input type="hidden" name="MAX_FILE_SIZE" value="32768" />

<_abel for="name">Name:</label>

<input type="text" id="name" name="name" value="<?php if (!empty(\$name)) echo \$name; ?>" />

<label for="score">Score:</label>

<input type="text" id="score" name="score" value="<?php if (!empty(\$score)) echo \$score; ?>" />

<label for="screenshot">Screen shot:</label>

<input type="file" id="screenshot" name="screenshot" />

<hr />

<input type="submit" value="Add" name="submit" />

</form>

The actual file input field, which ultimately relies on a native operating system dialog for file browsing and selection.



Change the Add Score form so that it uses a file input field to allow image file uploads.

store image filenames in the database

filename Insert the image into the database

Simply uploading an image file to the web server via a form isn't enough. We have to store the filename in the new screenshot column of the database so that the image can be accessed and displayed. As it stands, the Add Score script already inserts new high scores into the guitarwars table using the SQL INSERT statement, but this statement doesn't factor in the new screenshot column:

Image filenames are stored in the database as part of an INSERT statement.

The MySQL NOW() function is used to insert the current date/time.

INSERT INTO guitarwars VALUES (0, NOW(), '\$name', '\$score')

The id column gets set automatically via __ AUTO_INCREMENT - the O is ignored, although the query does require a value here.

Since this SQL statement is inserting values without identifying the column names for each, it must include a value for every column. But we just added a new column, which means the query no longer works—it's missing a value for the new screenshot column. So adding a screen shot image filename to the database as part of a new high score row requires us to add a new value to the INSERT statement:

Passing the screenshot image filename along in the INSERT statement adds it to the database.

INSERT INTO guitarwars VALUES (0, NOW(), '\$name', '\$score',

Rows of data inserted prior to the addition of the screenshot column don't have a screenshot filename.

guitarwars

| id | date | name | score | screenshot |
|----|---------------------|-----------------|--------|----------------|
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | - Streethallor |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 | |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| 7 | 2008-04-24 08:13:52 | Phiz Lairston | 186580 | phizsscore.gif |

The new INSERT statement results in the screenshot filename getting inserted into the screenshot column.

The order of these values matters since the INSERT statement is assuming they are in the same order as the columns in the table.

'\$screenshot'

Write a query to INSERT the screen shot image filename into the screenshot column of the table.

Find out the name of the uploaded file

The query looks good, but we still don't know what the actual filename of the image is. It's fair to assume that the file input field in the form somehow provides access to the filename, but how? The answer lies in a built-in PHP superglobal variable named \$_FILES, which is similar to the \$_POST superglobal we've used to access form data. Like \$_POST, \$_FILES is an array, and within it is not only the name of the uploaded file, but also some other information about the file that might prove useful.

ctual filename in the form answer lies in a ch is similar to

Like \$_POST, of the uploaded aight prove useful.

| S_FILES['screenshot']['name'] | The name of the uploaded file.

 The MIME type of the uploaded file,

in this case GIF.

The form passes some useful information about the file to the PHP script via the FILES superglobal variable.

phizsscore.gif

This is the image file being uploaded thanks to the file input field in the form.

The \$_FILES
built-in superglobal
variable provides
access to information
about uploaded files.

\$_FILES['screenshot']['size']

The size (in bytes)
of the uploaded file.

\$_FILES['screenshot']['tmp_name']

/tmp/phpE7qJky

The temporary
storage location of
the file on the server.


\$_FILES['screenshot']['error']

The error code for the file
upload; O indicates a success,
other values indicate failure.

\$_FILES['screenshot']['type']

The other information made available in the \$_FILES variable is certainly useful, but right this moment, we just need the name of the image, which can be stored away in a local variable (\$screenshot) and used in the SQL INSERT statement.

- \$screenshot = \$ FILES['screenshot']['name'];





The main Guitar Wars page (index.php) still isn't displaying screen shot images for the high scores. Finish the code so that it shows the images.

```
<?php
// Connect to the database
$dbc = mysqli connect('www.guitarwars.net', 'admin', 'rockit', 'gwdb');
// Retrieve the score data from MySQL
Squery = ;
$data = mysqli query($dbc, $query);
// Loop through the array of score data, formatting it as HTML
echo '';
while ($row = mysqli fetch array($data)) {
 // Display the score data
 echo '';
 echo '<span class="score">' . $row['score'] . '</span><br />';
 echo '<strong>Name:</strong> ' . $row['name'] . '<br />';
 echo '<strong>Date:</strong> ' . $row['date'] . '';
 else (
  echo '<img src="unverified.gif" alt="Unverified score" />';
echo '';
mysqli close($dbc);
```

Sharpen your pencil Solution

The main Guitar Wars page (index.php) still isn't displaying screen shot images for the high scores. Finish the code so that it shows the images.

In a move to help simplify the code, we're not using "or

```
die()" to produce error messages and exit the script
                                                                                                                  when a mysqli function fails. You may want to continue
                                                                                                                   including this code in your own applications but we're
<?php
                                                                                                                   going to skip it from here on for the sake of brevity.
  // Connect to the database
   $dbc = mysqli connect('www.quitarwars.net', 'admin', 'rockit', 'qwdb');
                                                                                                                               The SQL statement that requests
                                                                                                                           / scores doesn't change at all!
   // Retrieve the score data from MySQL
   squery = "SELECT * FROM guitarwars" #;
   $data = mysqli query ($dbc, $query);
  // Loop through the array of score data, formatting it as HTML
   echo '';
   while ($row = mysqli_fetch_array($data)) {
     // Display the score data
     echo '';
    echo '<span class="score">' . Srow['score'] . '</span><br />'; to make sure the
   echo '<strong>Name:</strong>'. $row['name']. '<br/>
screen shot image file screen shot image file isn't an empty file.

if (is_file( frow['screenshot'] ) && filesize( frow["screenshot'] ) \tau_{\text{al}} = "Score image" />

// td>

        echo '<img src="unverified.gif" alt="Unverified score" />';
                                                                                                                                                                                                    Change the main
                                                                                                                                                                                                    Guitar Wars page
   echo '';
                                                                                                                                                                                                    to show screen
                                                                                                                                                                                                    shot images for
                                                                                                                                                                                                    the high scores.
  mysqli close($dbc);
```



Add a new high score to Guitar Wars, complete with a screen shot image.

If you haven't already done so, download the Guitar Wars example code from the Head First Labs web site at www.headfirstlabs.com/books/hfphp. It's in the chapter05 folder. The code consists of the main page (index.php), the Add Score script (addscore.php), and a style sheet (style.css).

First you need to change the addscore.php script so that its Add Score form supports file uploads. This includes adding new form fields, adjusting the <form> tag, and checking to make sure the \$screenshot variable isn't empty. Then incorporate the new high score INSERT query into the script.

Now shift to the index.php script, and add the new code from the facing page so that it displays the screen shot image for each high score.

Upload all of these files to your web server and open the addscore.php page in a web browser. Enter a new high score in the form, and click Submit. Then navigate to the index.php page and take a look at the new score.

| | 4 - 4 |
|---|-------|
| 368420 Name: Ashton Simpson Date: 2008-04-23 09:13:34 | |
| 64930 Name: Kenny Lavitz Date: 2008-04-23 14:09:50 | |
| Mi . | - 1 |
| 186580 Name: Phiz Lairston Date: 2008-04-24 08:13:52 | • |
| g a | |
| | |

Something isn't right! The image doesn't appear with the new score as expected.



Why do you think the screen shot image doesn't show up for the new score? What about for the scores that were already in the database?

Where did the uploaded file go?

The problem with the uploaded image not appearing is that we made an assumption that the file would be uploaded to the same folder on the web server as our PHP scripts. As it turns out, this assumption is dead wrong. The Add Score form lets the user select a file from their own computer, but the file is actually uploaded to a **temporary folder** on the server. The temporary folder is created automatically on the server and usually has a weird name with a bunch of random letters and numbers. Web server This presents a problem for our code in index.php because it assumes the image is located in the main web folder: root This code assumes the This temporary image is stored in the folder name and www. tmp main web folder where location often the PHP files are varies with each stored ... but it isn't! PHP installation. et off phpE7qJky Client web browser addscore.php index.php 1001 1110100 The screen shot ooloto image file begins in mypics iotolli addscore.php is some folder on the phizsscore.gif where this form user's computer. originates 1001 1110100 001010 HIOIOI phizsscore.gif Gultar Wars - Add Your High Score The Add Score script takes care of uploading the image file to a temporary

244 Chapter 5

folder on the server.

This is the

of the image file, including the permanent path and filename.

The file is moved from a temporary < folder to a permanent folder.

move_uploaded_file()


destination location

tmp

phpE7qJky

1001

phizsscore.gif



www

yle.css

score.php

This folder can be any folder

you choose on the web server,

permission to write files to it.

just make sure you have

index.php

245 you are here >

1001

1110100 001010

HIDIOI

phizsscore.gif

Dumb Questions

Q: Can't I change the initial storage location of uploaded files by modifying the php.ini file?

A: Yes. The PHP initialization file (php.ini) can be used to change the initial storage location of uploaded files through the upload_tmp_dir option. But if your application is hosted on a virtual server, you may not have access to this file, which means you'll have to move the file to your own folder via PHP script code.

Q: Why is the initial upload folder called a "temporary" folder? Does it go away after a file is moved?

A: No. The folder is "temporary" in a sense that it isn't intended to serve as the final storage location for uploaded files. You can think of it as a holding area where uploaded files are stored until they are moved to their final storage location.

Q: Why can't I just leave a file in the temporary folder?

A: You can, in which case you'd need to add

\$_FILES['screenshot']['tmp_name'] to
the path of the image to make sure it is found in the temporary
folder. But keep in mind that you don't typically control the name
or location of the folder. Even more important is the fact that
temporary folders can be automatically emptied periodically on
some systems. Another potential issue is that the temporary
upload folder may not be publicly accessible, so you won't be able
to reference uploaded files from HTML code, which is the whole
point in Guitar Wars and most other PHP applications. By moving
uploaded files out of the temporary upload folder, you can carefully
control exactly where they are stored and how they are accessed.


OK, so now I know how to move uploaded files around. That's really special. But I still don't have a clue where they are supposed to go.



Every application needs an images folder.

OK, maybe "need" is a bit strong, but it's important to organize the pieces and parts of PHP applications as much as possible, and one way to do so is to create folders for different components. Since uploaded images are submitted by users, they aren't something you typically have direct control over, at least in terms of filenames and quantity. So it's a good idea to store them separately from other application files.


All this said, we need an images folder, where image files that are uploaded to the Guitar Wars application are stored. This folder can also serve as the storage location for any other images the application may use, should the need arise.



The images folder isn't actually any bigger than other folders, but it helps organize image files into one place.

Create a home for uploaded image files


The images folder is just like any other folder on the web server except that it must be placed somewhere beneath the main web folder for the application. It's usually fine to just place the folder directly beneath this web folder, but you're free to create a more complex folder hierarchy if This is the web folder for the you want. application where the PHP scripts are stored, including index.php. With the images folder created immediately beneath the main web folder on the web server, it becomes possible to reference image files from within PHP scripts like this: The image filename is concatenated to the path. Web server \$target = GW UPLOADPATH . \$screenshot; images/phizsscore.gif root The \$target path is built out of a new constant we're going to add to the script called GW UPLOADPATH, which holds the path to our images folder. Like a variable, a The images folder constant stores a piece of data. But the value of a constant is typically placed www tmp can't change once it's set. The image filename as entered just beneath the into the Add Score form is then concatenated to the web folder. images path. phpE7qJky images score.php 1001 too! h Uploaded image index.php 1110100 files are moved to 001010 the images folder, Hololl where they can If your PHP application is phizsscore.gif phizsscore.gif be displayed via hosted anywhere other HTML < img> tags than your local computer, you'll need to use FTP to create the images folder. move uploaded file (Use an FTP program to access the file \$ FILES['screenshot']['tmp name'], system of your web site and create the Starget); images folder beneath the web folder of the application.



INSERT INTO guitarwars VALUES (0, NOW(), '\$name', '\$score', '\$screenshot')

guitarwars

| id | date | nume | store | screenshot |
|----|---------------------|-----------------|--------|----------------|
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | an oursigor |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 | |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| 7 | 2008-04-24 08:13:52 | Phiz Lairston | 186580 | phizsscore.gif |






Give uploaded screen shot images a permanent home in their own image folder.

Modify the addscore.php script to use the GW_UPLOADPATH constant and store uploaded screen shot images in the path it points to. Here's a peek at the code that needs to change:

```
// Define the upload path and maximum file size constants define ('GW_UPLOADPATH', 'images/');
if (isset(5_POST['submit'])) (
   // Grab the score data from the POST
   $name = S_POST['name'];
   $score = 8 POST['score'];
   $screenshot = $ FILES['screenshot']['name'];
   if (!empty($name) && !empty($score) && !empty($screenshot)) (
     // Move the file to the target upload folder
$target - GW_UPLOADPATH . Screenshot;
if (move_uploaded_frie() FILES['screenshot']['tmp_name'], $target)) (
         // Connect to the database
         $dbc = mysqli_connect('www.guitarwars.net', 'admin', 'rockit', 'gwdb');
        // Write the data to the database 
$query = "INSERT INTO guitarwars VALUES (0, NOW(), '$name', '$score', '$screenshot')";
         mysqli query($dbc, $query);
         // Confirm success with the user
         echo 'Thanks for adding your new high score!';
        echo '<strong>Name:</strong> ' . Sname . '<br />';
echo '<strong>Score:</strong> ' . Sscore . '<br />';
echo '<img arc="' GW UPLOADPATH . Sscreenshot . '" alt="Score image" />';
echo '<a href="index.pnp">**It;**It; Back to high scores</a>';
                                                                                                                             addscore.php
```

The index.php script is also affected by the GW_UPLOADPATH constant. Don't forget to change it as well. After making these changes, upload the scripts to your server and try adding a high score again.



Q: If the php.ini file can be used to control the storage location of uploaded files, why is it necessary to move the file?

A: Because it isn't always possible to change pnp.ini. For example, if you're building a PHP application on a virtual web server, you very likely won't be able to change the settings in php.ini. And even if you are able to change php.ini, you run the risk of breaking your application if you ever need to move it to another server. In other words, the application will be dependent on a path controlled by php.ini, as opposed to a path controlled by your own PHP code.

Q: Why isn't the date something that users can enter in Guitar Wars?

A: The date is an important part of a high score in that it establishes when a score was officially posted to the site. Like any record, the first person to achieve a certain score gets all the glory. Rather than trust a user to tell us when they achieved their high score, we can just use the post date/time as the official recording of the score. This eliminates bogus dates and lends more credibility to the high score list. Users of such a competitive application will always be looking for an angle, so eliminate as many of them as you can!

It is worth pointing out that the NOW () function uses the time on the web server, which may not be the same as the user's local time. This shouldn't be a problem, however, since all users are held to that same server time.

Databases are great for storing text data, but it's usually better for them to reference binary data in external files.

Dumb Questions

O: Isn't it possible for people to overwrite each other's screen shot images by uploading image files with the same names?

A: Yes. The problem has to do with the fact that the screen shot image stored on the web server uses the exact same filename provided by the user in the file upload form field. So if two users upload image files with the same filenames, the first user's image will get overwritten by the second user's image. Not good. One solution is to add a degree of uniqueness to the image filename on the server. A simple way to do this is to add the current server time, in seconds, to the front of the filename, like this:

\$target = GW_UPLOADPATH . time()
\$screenshot;

The result of this code is a filename of 1221634560phizsscore.gif instead of phizsscore.gif, where 1221634560 is the current time on the server expressed in seconds. Q: Could we have stored the actual image data for an uploaded high score screen shot in the Guitar Wars database?

A: Yes. Databases are very flexible and allow you to store binary data within them. However, the big problem in this case is that Guitar Wars uses the uploaded images in HTML code so that they can be displayed on the main index.php page. The HTML tag is designed to reference an image file stored on the web server, not a chunk of binary image data stored in a database. So even if you altered the guitarwars table to hold binary image data, you'd be facing a significant challenge trying to get the data back into a format that can be displayed using HTML code.


There's nothing terribly special about the time returned by the time() function other than the fact that it sources unique numbers...the number it returns is always growing!



BULLET POINTS

- The ALTER statement is used to change the structure of a MySQL database table, such as adding a new column of data.
- With a little help from PHP and MySQL, an HTML
 <input> tag can be used to upload image files.
- The superglobal variable \$_FILES is where PHP stores information about an uploaded file.
- The standard PHP function move_uploaded_ file() allows you to move files around on the web server and is critical for handling uploaded files.
- Most web applications benefit from having an images folder for storing images used by the application, especially those uploaded by users.


252



Shared data has to be shared


When it comes to data that is shared across multiple scripts in an application, you need a way to store the data in one place and then pull it into the different scripts. But that still doesn't answer the question of where exactly the data should go...?

You could store the data only in index.php...



Shared script data needs to be accessible throughout an application without code duplication.

...but then other scripts wouldn't have access to it.




The solution to shared script data lies in **include files**, which are PHP source code files that are inserted into other PHP files as needed.

Shared script data is required

Include files are very powerful because you create them once but then reuse them as needed in other script files, effectively sharing the code within. The GW_UPLOADPATH constant can be placed within an include file to establish a collection of "application variables."

Include files allow you to share code across multiple scripts.



Dumb Questions

Q: Hey, aren't these application "variables" really constants?

A: Sometimes, yes. But that's OK. The point is not to split hairs over variables vs. constants. Instead, we're just trying to establish a common place to store shared script data within a given application. And that place is a script file called appvars.php.

Q: Is code in shared script files limited to data?


A: No, not at all. Any PHP code can be placed in its own script file and shared using the require_once statement. In fact, it's very common for applications to share lots of functional code across multiple script files. Not only is it common to use shared script files, but it's often a great idea in terms of code organization.

Q: Why is the PHP statement to include script code called require_once?

A: The name "include file" comes from a PHP statement called include that is very similar to require_once. The difference is that require_once results in an error if the include file cannot be found—include won't reveal an error if an include file is missing. Also, the "once" in require_once means that it keeps a file from being accidentally included more than once. You sometimes see include used instead of require_once to include code that isn't as important, such as pure HTML code that doesn't perform a critical purpose. PHP also has include_once and require statements that are variations on require_once and include.


Think of require_once as "insert"

Includes aren't limited to one shared PHP file, and they can appear anywhere you want within a script. You can think of the require_once statement as an "insert" statement that gets replaced with the contents of the script file it references. In the case of Guitar Wars, the database connection variables could also benefit from being moved into an include file. So the contents of two shared script files are inserted directly into other script files at the points where they are required.



The REQUIRE_ONCE statement inserts shared script code into other scripts.

256



Awesome! Now I have access to the shared data too.

Move the file upload path to a constant that is shared via an include file.

Oops, another new step! Some things are difficult to plan for, so you have to be ready to tweak your design "on the fly."




Create two include files for Guitar Wars, and then share them among the other scripts.

Create two new text files, appvars.php and connectvars.php, and enter the code for them shown on the facing page. Then add require_once statements to index.php and addscore.php so that both shared script files are included. Upload all of the scripts to your web server and try out the Add Score form and main page to make sure they still work with the new and improved include file organizational structure.

www.it-ebooks.info

Order Timing is everything with high scores


Guitar Wars is finally image-powered, allowing users to upload screen shot images to help verify their high scores. While this is a major improvement to the application, it hasn't solved a problem that users have actually been grumbling about for quite a while—the order of the scores on the main page.





PHP & MySQL Magnets

See if you can figure out how **ORDER BY** works by using the magnets below to create ordered **SELECT** statements that result in the output below. Also circle which query you think represents the best fix for Guitar Wars. Hint: **ASC** stands for ASCending and **DESC** stands for DESCending.




you are here > 259




PHP & MySQL Magnets Solution

See if you can figure out how **ORDER BY** works by using the magnets below to create ordered **SELECT** statements that result in the output below. Also circle which query you think represents the best fix for Guitar Wars. Hint: **ASC** stands for ASCending and **DESC** stands for DESCending.




Honoring the top Guitar Warrior

With the order of the scores fixed, it's now possible to make an unexpected improvement to the high score list by calling out the highest scorer at the top of the list. The top scoring Guitar Warrior deserves a top score header that clearly displays the highest, score, so there is no doubt who the top Guitar Warrior is... and what score to gun for.



Format the top score with HTML and CSS

The most important thing about the new high score header is that it be clearly seen above all other scores in the high score list. This requires the help of both HTML and CSS to add some visual flair. The header will be generated as a row in the HTML table with a special CSS style applied to it. This style, topscoreheader, must be added to the style.css stylesheet for Guitar Wars.



The index.php script already generates an HTML table containing the high score list. Generating a header just for the top score involves isolating the first score, which is guaranteed to be the top score since the list is now in order A while loop takes care of looping through the scores, so we need to somehow count the scores, and only generate the header for the first one...



Finish the code for the index.php Guitar Wars script so that it adds a formatted header for the top score that uses the topscoreheader CSS style. Hint: Don't forget that the top score header is part of the high score HTML table, which has two columns.

```
// Loop through the array of score data, formatting it as HTML
echo '';
$i = 0;
while ($row = mysqli_fetch_array($data)) {
 // Display the score data
 if (.....) {
 echo '';
 echo '<span class="score">' . $row['score'] . '</span><br />';
 echo '<strong>Name:</strong> ' . $row['name'] . '<br />';
 echo '<strong>Date:</strong> ' . $row['date'] . '';
 if (is_file(GW_UPLOADPATH . $row['screenshot']) &&
   filesize(GW UPLOADPATH . $row['screenshot']) > 0) (
   echo '<img src="' . GW_UPLOADPATH . $row['screenshot'] .
     '" alt="Score image" />';
 else (
   echo '<img src="' . GW_UPLOADPATH . 'unverified.gif' .
     "" alt="Unverified score" />';
 ......
echo '';
```

index.php



Finish the code for the index.php Guitar Wars script so that it adds a formatted header for the top score that uses the topscoreheader CSS style. Hint: Don't forget that the top score header is part of the high score HTML table, which has two columns.

```
fi is the variable that counts
                        through the high scores - we can
                        use it to isolate the first score
// Loop through the array of score data, formatting it as HTML
                                                               If fi equals O, we know
echo '';
                                                               it's the first (top!) score,
$i = 0;
                                                               so render the HTML
while ($row = mysqli_fetch_array($data)) {
                                                               code for the header.
 // Display the score data
 if ( fi == 0 ) (
   echo 'Top Score: '.
     frow['score'] . ';
 echo '';
                                                             The topscoreheader
 echo '<span class="score">' . $row['score'] . '</span><br />';
                                                             style class is stored
 echo '<strong>Name:</strong> ' . $row['name'] . '<br />';
                                                              in style.css.
 echo '<strong>Date:</strong> ' . $row['date'] . '';
 if (is file(GW UPLOADPATH . $row['screenshot']) &&
   filesize(GW_UPLOADPATH . $row['screenshot']) > 0) {
   echo '<img src="' . GW UPLOADPATH . $row['screenshot'] .
     '" alt="Score image" />';
 else {
   echo '<img src="' . GW UPLOADPATH . 'unverified.g:f' .
     "" alt="Unverified score" />';
                         Increment the counter at the
                       - end of the score loop - this
                        code is the same as fi = fi + 1;
echo '';
```


264

index.php



Order the high scores and showcase the highest score of all.


Modify the index.php script to use the new ordered SELECT query, and then add in the code that generates the top score header. Upload the new script to your web server and open it in your browser to see the top score prominently displayed.



It's true, the unverified scores need to be dealt with.


But one thing at a time. It seems another problem has surfaced that is preventing people from uploading their high score screen shots...


265



small Only images allowed

So how exactly do we check the Add Score form and make sure uploaded images adhere to a certain size and type? The answer lies in the built-in \$_FILES superglobal variable, which if you recall, is where we earlier obtained the temporary storage location of the uploaded file so that it could be moved to the images folder. Now we're going to use it to grab the size and MIME type of the file.







| | Write an if statement that checks to make sure a screen shot file is an image, as well as checking to make sure it is greater than |
|---|--|
| | O bytes in size and less than the constant GW_MAXFILESIZE. Assume the file size and type have already been stored in variables named \$screenshot size and \$screenshot type. |
| if (| |
| *************************************** | |
| |) (|

you are here >

267





Since we're making the script more robust, it's also a good idea to check the f_FILES superglobal to make sure there wasn't an upload error.

Display a descriptive error if the file is the wrong type or too large.

```
if (!empty($name) && !empty($score) && !empty($screenshot)) (
  if ((($screenshot_type == 'image/gif') || ($screenshot_type == 'image/jpeg') ||
   ($screenshot_type == 'image/pjpeg') || ($screenshot_type == 'image/png')) &&
    ($screenshot_size > 0) && ($screenshot_size <= GW_MAXFILESIZE)) (
    if ($_FILES['file']['error'] == 0) [
      // Move the file to the target upload folder
      $target = GW_UPLOADPATH . $screenshot;
     if (move_uploaded_file($_FILES['screenshot']['tmp_name'], $target)) (
        // Connect to the database
       $dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
        $query = "INSERT INTO guitarwars VALUES (0, NOW(), '$name', '$score', '$screenshot')";
        mysqli_query($dbc, $query);
        // Confirm success with the user
        echo 'Thanks for adding your new high score!';
        echo '<strong>Name:</strong> ' . $name . '<br />';
        echo '<strong>Score:</strong> ' . $score . '<br />';
        echo '<img src="' . GW_UPLOADPATH , $screenshot . '" alt="Score image" />';
        echo '<a href="index.php">&lt;&lt; Back to high scores</a>';
        // Clear the score data to clear the form
        $name = "";
         $score = "";
         $screenshot = "";
         mysqli_close($dbc);
        echo 'Sorry, there was a problem uploading your screen shot image. $/p>';
       else
     echo 'The screen shot must be a GIF, JPEG, or PNG image file no ' .
       'greater than ' . (GW_MAXFILESIZE / 1024) . ' KB in size.';
   // Try to delete the temporary screen shot image file
  @unlink($_FILES['screenshot']['tmp_name']);
    echo 'Please enter all of the information to add your high score.';
                                                                                       addscore.php
    The unlink() function deletes a file
                                                           The new and improved
    from the web server. We suppress its
                                                           Add Score script now
    error reporting with @ in case the
                                                           has image file validation.
    file upload didn't actually succeed.
```

you are here >

269



Add screen shot image file validation to the Add Score script.

Modify the addscore.php script to use the new image file validation code. Upload the script to your web server and try out the Add Score form with both valid images and a few invalid files (huge images and non-images).

Dumb Questions

Q: Why are there two different MIME types for JPEG images?

A: This is a question better asked of browser vendors, who, for some reason, decided to use different MIME types for JPEG images. To make sure the JPEG file validation works across as many browsers as possible, it's necessary to check for both MIME types.

Q: Why is it necessary to check for image files larger than 0 bytes? Aren't all images larger than 0 bytes?

A: In theory, yes. But it is technically possible for a 0 byte file to get created on the server if the user specifies a file that doesn't actually exist on their own computer. Just in case this happens, addscore.php plays it safe and checks for an empty file.

Q: Why is GW_MAXFILESIZE placed in appvars.php even though it is only used in addscore.php?

A: While it's true that appvars.php is intended for storing script data that is shared across multiple script files, it is also a good place to store any constant script data. In this case, placing GW_MAXFILESIZE in appvars.php makes it easier to find if you ever want to make the file upload limit larger.

Q: How does that line of code with @unlink() work?


A: The built-in PHP unlink () function deletes a file from the web server, in our case the temporary image file that was uploaded. Since it's possible that the upload failed and there is no temporary image file, we suppress any potential errors generated by unlink () by preceding it with an at symbol (@). You can stick @ in front of any PHP function to suppress its error reporting.

What about all those unverified scores? They haven't gone away, you know.

The high score list must be cleaned up.

With image file uploading tightened up thanks to validation, we can't ignore the problem of unverified scores any longer. New scores with uploaded screen shot images shouldn't play second fiddle to old scores without screen shots that may or may not be valid. Guitar Wars needs a way to remove old scores!

The current top score is not verified, which doesn't instill much confidence in other users.



ed.

guitarwars

| 70 | | | | |
|----|---------------------|-----------------|--------|----------------|
| id | date | name | score | screenshot |
| /1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 | |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| 7 | 2008-04-24 08:13:52 | Phiz Lairston | 186580 | phizsscore.gif |

Unverified scores without images need to be removed from the database, pronto!


Write down how you would go about cleaning up the unverified scores in the high score list:

Plan for an Admin page

Since we just need to remove some unverified scores from the database, it's perfectly reasonable to just fire up an SQL tool and manually remove rows from the database with a few DELETE queries. But this may not be the last time you'll need to remove a score, and it's no fun having to resort to manual SQL queries to maintain a web application. The idea here is to build an application that can be maintained with as little hassle as possible.

What we need is a page that only the web site administrator has access to and can use to remove scores... an Admin page! But we need to be very careful in making a clear distinction between what parts of Guitar Wars are for the administrator and what parts are for users. Web applications often include pages for public access, as well as admin pages that are only for site maintenance.

These pages are for users:





Write down what the Admin and Remove Score scripts need to do in order to accommodate a score removal feature for Guitar Wars. Then draw how a score removal affects a row in the guitarwars table and the screen shot image file associated with it.

| A. | |
|----------|--|
| < bub | |
| 2 | |
| | |
| dmin.php | |

Web server




| *************************************** | |
|---|-----------------|
| | php</td |
| | |
| | 7> |
| | removescore.php |

guitarwars

| id | date | name | store | screenshot |
|----|---------------------|-----------------|--------|---------------|
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 | |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| 7 | 2008-04-24 08:13:52 | Phiz Lairston | 186580 | phizsscore.gi |

273



274 Chapter 5

Generate score removal links on the Admin page


Although the Remove Score script is responsible for the actual score removal, we need an Admin script that allows us to select a score to remove. The admin.php script generates a list of high scores with Remove links for each one. These links pass along data about a given score to the removescore.php script.

```
<?php
  require once ('appvars.php');
  require once ('connectvars.php');
  // Connect to the database
                                                                         admin.php
  $dbc = mysqli connect(DB HOST, DB USER, DB PASSWORD, DB NAME);
  // Retrieve the score data from MySQL
  $query = "SELECT * FROM guitarwars ORDER BY score DESC, date ASC";
  $data = mysqli_query($dbc, $query);
  // Loop through the array of score data, formatting it as HTML
                                                             The URL to the Remove Score script
  echo '';
                                                             is doing more than just linking to the
  while ($row = mysqli_fetch_array($data)) (
                                                             script .. it's also passing data to it!
   // Display the score data
   echo '<strong>' . $row['name'] . '</strong>';
    echo '' . $row['date'] . '';
    echo '' . $row['score'] . '';
    echo '<a href="removescore.php?id=' . $row['id'] . '&amp;date=' . $row['date'] .
      '&name=' . $row['name'] . '&score=' . $row['score'] . '&screenshot=' .
     $row['screenshot'] . '">Remove</a>';
                                             This code generates an HTML link to
  echo '';
                                             the removescore php script, passing along
                                             information about the score to be removed.
  mysqli close ($dbc);
                                     <a href="removescore.php?id=5&date=2008-04-23%2009:1</pre>
                                     3:34&name=Ashton%20Simpson&score=368420&screenshot=
```

Scripts can communicate with each other

In order for the Remove Score script to remove a high score, it must know what score to remove. But that's decided in the Admin script. This begs the question, how does the Admin script tell the Remove Score script what score to remove? This communication between scripts is accomplished by packaging up the data as part of a "Remove" URL for each high score shown on the Admin page. If you closely analyze the URL for a particular score, you'll notice that all the high score data is in there.

The URL of a script can be used to pass data as a GET request.



OK, so data gets passed along through a URL, but how exactly does the Remove Score script get its hands on that data? Data passed to a script through a URL is available in the \$_GET superglobal, which is an array very similar to \$_POST. Packaging data into a linked URL is the same as using a GET request in a web form. In a traditional HTML GET request, form data is **automatically** sent along to the form processing script as part of the script's URL. We're doing the same thing by **manually** building our own GET request as a custom URL.

Similar to \$_POST, using the \$_GET array to access the high score data requires the name of each piece of data.

The URL for a script serves as a handy way to pass important data, such as the ID of a database row.

\$ GET['score']

\$_GET['rame']

The name of the piece of data is used to access it within the f_GET array.



I don't see what all the fuss is with GET. Why can't you just pass the data to the script using POST? That's how you've done it up until now.

POST requests can only be initiated through a form, while GET requests can be packaged as URLs.


Up until now we've always passed data to a script through a web form where the script was listed as the action for the form's Submit button. When the user fills out the form and presses the Submit button, the form data is packaged up and sent along to the form as a POST request.

The problem is that the Admin page doesn't use a form to initiate the Remove Score script. It just links to the script via a URL. So we need a way to send along data to a script using nothing more than a URL. This is where GET is particularly handy since it provides access to data that is packaged in a URL as parameters. Similar to POST, the data that gets passed along to the script through a GET request is available through a superglobal, but it's named \$_GET instead of \$_POST.



0

0



you are here > 277

Of GETs and POSTs

The difference between GET and POST isn't just form vs. URL since GET requests can (and often are) used to submit form data as well. The real distinction between GET and POST has to do with the **intent** of a request, GET is used primarily to retrieve data from the server **without affecting anything** on the server. POST, on the other hand, typically involves sending data to the server, after which **the state of the server usually changes** somehow in response to the data that was sent.

The two types of web requests, GET and POST, control how you shuttle data between scripts.

POST

Used to send data to the server that somehow causes a change in the state of the server, such as inserting data in a database. Data can still be returned in a response. Unlike GET, POST requests can only be made through the action of a web form. Also unlike GET, the data sent in a POST request is hidden from view.

GET

Typically used for data retrieval that doesn't change anything on the server. For small amounts of data, GET is also useful for directly sending data to the server in a URL. Unlike POST, GET is primarily suited to sending small amounts of data.

Dumb Questions

Q: I've seen web forms that use GET. How does that work?

A: Both GET and POST have their place when it comes to web forms. When creating a web form, the method attribute of the <form> tag controls how the data is sent, while the action attribute identifies the script to receive the data and process it:

<form method="post" action="addscore.php">

When the submit button is clicked to submit this form, the addscore.php script is executed, and the form data is passed along to it through the \POST array. But you could've just as easily written the \POST tag like this, in which case the data would get passed along through the \POST array:


<form method="get" action="addscore.php">

Q: Ah, so it doesn't matter which request method I use, GET or POST?

A: Wrong. It matters quite a lot. GET is generally used for getting data from the server, not changing anything on the server. So GET is perfect for forms that make informational requests on the server without altering the state of the server, such as selecting rows from a database. POST, on the other hand, is best suited for requests that affect the server's state, such as issuing an INSERT or DELETE query that changes the database. Another distinction between GET and POST is that data passed through a GET is visible in a URL, while POST data is hidden, and, therefore, is a tiny bit more secure.

Q: How does this distinction between GET and POST factor into the passing of data to a script through a URL?

A: Well, first of all, you can only pass data to a script through a URL using a GET request, so POST is eliminated immediately. Furthermore, since GET is intended purely for requests that don't alter the state of the server, this means you shouldn't be doing any INSERTs, DELETE FROMs, or anything else that will change the database in a script that receives data through its URL.



Tonight's talk: GET and POST

| GET: | POST |
|------|------|
| | |

So, word on the street is you've been saying all I'm good for is asking questions but not really doing anything with the answers. Is that true?

Sure is. Let's face it, you don't have any real power, just the ability to ask the server for something.

OK, so it's true that I'm not really intended to be causing changes on the server such as deleting files or adding database rows, but that doesn't mean I'm not important.

If you say so. All I know is not a whole lot would get done without people like me making things happen on the server. If the server was always stuck in the same state, it would be pretty boring out there.

True, but you're permanently connected to your good buddy, Form, whereas Form and I are merely casual acquaintances. I leave room for other friends, such as URL.

So you think your "circle of friends" somehow overcomes your inability to take action? I doubt it.

Well, then I have a question for you. How exactly do you take action when your little sidekick, Form, isn't around? You know sometimes Page doesn't find it necessary to go to the trouble of involving Form.

> Listen, Form is my friend, and long ago I made a commitment not to do any requesting without him. So judge my loyalty if you must, but I won't betray my friend!

Calm down. I'm just pointing out that while I'm geared toward retrieving data from the server, I'm fairly flexible in how I can be used to do it.

I'll give you that. You're alright by me.

Glad to hear it. It's been good talking to you...

you are here > 279

GET, POST, and high score removal

We've established that the removal of scores in Guitar Wars starts with a "Remove" link on the Admin page that links to the Remove Score script. We also know that score data can be passed through the link URL to the Remove Score script. But we have a problem in that a GET request really shouldn't be changing anything on the server, such as deleting a score. A possible solution is to not change anything on the server... yet. What if the Remove Score script initially displayed a confirmation page before actually removing a score from the database?




The confirmation page shows the score that is up for removal with a simple Yes/No form. Selecting Yes and clicking the Submit button results in the score being removed, while choosing No cancels the score removal.

Thinking in terms of GETs and POSTs, the Remove Score script can display the confirmation page as a response to the GET request from the Admin script. And since the confirmation itself is a form, it can issue its own POST request when submitted. If the form is a self-referencing form, the same script (removescore.php) can process the POST and carry out the score removal. Here are the steps involved in this process:

A confirmation page gives the user a chance to confirm the high score removal instead of just removing it instantly.

It's entirely possible, even helpful in some cases, for the same script to respond to both GET and POST requests.

- The Remove Score script is initiated through a GET request by the user clicking the "Remove" link on the Admin page.
- The Remove Score script uses the high score data stored in the \$_GET array to generate a removal confirmation form.
- The Remove Score script is initiated again, this time, through a POST request by the user submitting the confirmation form.
- The Remove Score script deletes the score from the database and also deletes the screen shot image file from the web server.



Dumb Questions

Q: How can the same script process both GET and POST requests?

A: It all has to do with how a script is invoked. In the case of the Remove Score script, it is invoked in two different ways. The first way is when the user clicks a "Remove" link on the Admin page, in which case a URL leads them to the script. Since data is packaged into the URL, this is considered a GET request. This GET request causes the script to generate a web form whose action refers back to the same Remove Score script. So when the user submits the form, the script is invoked a second time. But unlike the first time, there is no fancy URL with data packaged into it and, therefore, no GET request. Instead, the high score data is passed along through a POST request and is, therefore, available in the \$POST array.

Q: So the manner in which the script is invoked actually determines what it does?

A: Yes! When the script sees that data has been sent through a URL as a GET request, it knows to display a confirmation form, as opposed to deleting anything from the database. So the data sent along in the \$_GET array is used only within the confirmation page and has no lasting effect on the server.

When the script sees that data is being delivered through a POST request, the script knows that it can delete the data from the database. So it uses the \$_POST array to access the data and assemble a DELETE_FROM query that deletes the score. And since most high scores also have a screen shot image file stored on the web server, the script also deletes that file.

Isolate the high score for deletion

With the score removal process laid out, we can now focus our attention on the database side of things. The Remove Score script is responsible for removing a high score, which means deleting a row from the database of scores. If you recall, the SQL DELETE FROM statement allows us to delete rows. But in order to delete a row, we must first find it. This is accomplished by tacking a WHERE clause onto a query that uses DELETE FROM. For example, this SQL query deletes the row with the name column set to 'Ashton Simpson':

This query deletes rows with a name column matching 'Ashton Simpson'.

DELETE FROM guitarwars WHERE name = 'Ashton Simpson'

guitarwars

| id | date | name | score | screenshot |
|----|---------------------|-----------------|--------|---------------|
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 | |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | _ |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| 7 | 2008-04-24 08:13:52 | Phiz Lairston | 186580 | phizsscore.gi |

The table name is required by DELETE FROM to know which table you're deleting data from.

The name of the user is the match used to delete the high score.

There's a problem with this query, however. In a world full of millions of Guitar Warriors, odds are there will be more than one Ashton Simpson. This query doesn't just delete a single row, it deletes **all** rows matching the name 'Ashton Simpson'. The query needs more information in order to delete the right row:

By matching the score in addition to the name, the deletion gets much more exact

DELETE FROM guitarwars WHERE name = 'Ashton Simpson'

quitarwars

| id | date | name | score | screenshot |
|----|---------------------|-----------------|--------|----------------|
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 | / |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | > |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| 7 | 2008-04-24 08:13:52 | Phiz Lairston | 186580 | phizsscore.gif |

AND score = '368420'

The AND operator changes - the query so that both the name and score must match.

Now that both the name and score have to match, the odds of accidentally deleting more than one score are decreased dramatically.

you are here > 283

Control how much you delete with LIMIT

Using both the name and score columns as the basis for deleting a row is good... but not good enough. Application development is about minimizing risks at all cost, and there's still a slight risk of deleting multiple rows that match both the same name and score. The solution is to force the query to only delete **one row** no matter what. The LIMIT clause makes this happen:

For maximum safety, put a limit on the number of rows — that can be deleted.

DELETE FROM quitarwars WHERE name = 'Ashton Simpson' AND score = '368420' LIMIT 1

The number following LIMIT lets MySQL know the maximum number of rows to delete—in this case, one. So we're guaranteed to never delete more than one row with this query. But what if there were two Ashton Simpsons with the same score? Sure, this is an unlikely scenario, but it's sometimes worth considering extreme scenarios when working out the best design for an application.

guitarwars

| id | date | name | score | screenshot |
|-----|---------------------|-----------------|--------|-----------------|
| 1 | 2008-04-22 14:37:34 | Paco Jastorius | 127650 | |
| 2 | 2008-04-22 21:27:54 | Nevil Johansson | 98430 | |
| 3 | 2008-04-23 09:06:35 | Eddie Vanilli | 345900 | |
| 4 | 2008-04-23 09:12:53 | Belita Chevy | 282470 | |
| 5 | 2008-04-23 09:13:34 | Ashton Simpson | 368420 | |
| 6 | 2008-04-23 14:09:50 | Kenny Lavitz | 64930 | |
| 7 | 2008-04-24 08:13:52 | Phiz Lairston | 186580 | phizsscore.gif |
| | | - Viv | | |
| 523 | 2008-11-04 10:03:21 | Ashton Simpson | 368420 | ashtonsscore.jp |

Two high score rows with the exact same name and score present a problem for our DELETE query.

| statemen | wn wnat napp it above is ex- ton Simpson | ecuted. How | could you n | he |
|---------------|--|-------------|-------------|------|
| | | | | |
| | | | | |
| ************* | | | | |

284

Would it be any better to use the ID of the score in the WHERE clause of the DELETE FROM query? It might help make sure we delete the right score, no?

Yes, it would! The ID of a high score is the perfect way to isolate the score for deletion.

Uniqueness is one of the main advantages of creating primary keys for your tables. The id column in the guitarwars table is the primary key and is, therefore, unique for each and every high score. By using this column in the WHERE clause of the DELETE FROM query, we eliminate all doubt surrounding which score we're deleting. Here's a new query that uses the id column to help ensure uniqueness:

DELETE FROM guitarwars WHERE id = 5

Trusting that the id column is indeed a primary key results in this code safely deleting only one row. But what if **you** didn't create the database, and maybe uniqueness wasn't properly enforced? Then a LIMIT clause might still make some sense. The rationale is that if you intend for a query to only affect one row, then say it in the query.

DELETE FROM guitarwars WHERE id = 5 LIMIT 1

It's never a bad idea to be very explicit with what you expect to be done in a query, and in this case LIMIT adds an extra degree of safety to the DELETE query.



Deleting data based on a primary key helps to ensure accuracy in isolating the right row for deletion.

The LIMIT clause explicitly states that the query can't delete more than one row.

285



PHP & MySQL Magnets

The removescore.php script is almost finished, but it is missing a few important pieces of code. Use the magnets to plug in the missing code and give Guitar Wars the ability to eradicate unwanted scores.

```
<html xmlns="http://www.w3.org/1999/xhtml" xml:lang="en" lang="en">
 <meta http-equiv="Content-Type" content="text/html; charset=utf-8"/>
<head>
 <title>Guitar Wars - Remove a High Score</title>
 k rel="stylesheet" type="text/css" href="style.css" />
</head>
<body>
 <h2>Guitar Wars - Remove a High Score</h2>
<?php
                   ('appvars.php');
                  ('connectvars.php');
 if (isset($_GET['id']) && isset($_GET['date']) && isset($_GET['name']) &&
    isset($_GET['score']) && isset($_GET[ _____])) (
    // Grab the score data from the GET
    $id = $ GET['id'];
    $date = $_GET['date'];
    $name = $ GET['name'];
    $score = $ GET['score'];
                    = $_GET[ ];
   else if (isset($_POST['id']) && isset($_POST['name']) && isset($_POST['score'])) {
    // Grab the score data from the POST
    = $_POST[ ];
     $name = $_POST['name'];
     $score = $_POST['score'];
     echo 'Sorry, no high score was specified for removal.';
    if (isset($_POST['submit'])) {
     if ($_POST['confirm'] ==
        // Delete the screen shot image file from the server
        @unlink(GW_UPLOADPATH . $screenshot);
        // Connect to the database
        $dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
```

```
// Delete the score data from the database
                                guitarwars WHERE LIMIT ......
               **************
       mysqli_query($dbc, $query);
       mysqli_close($dbc);
       echo 'The high score of ' . $score . ' for ' . $name . ' was successfully removed.';
       echo 'The high score was not removed.';
      else (
     else if (isset( ) && isset( ) && isset( ) && ......
      isset($score) && isset($screenshot)) {
      echo 'Are you sure you want to delete the following high score?';
      echo '<strong>Name: </strong>' . $name , '<br /><strong>Date: </strong>' . $date .
       '<br /><strong>Score: </strong>' . $score . '';
      echo '<form method="post" action="removescore.php">';
      echo '<input type="radio" name="confirm" value="Yes" /> Yes ';
      echo '<input type="radio" name="confirm" value="No" checked="checked" /> No <br />';
      echo '<input type="submit" value="Submit" name="submit" />';
      echo '<input type="hidden" name="name" value="' , $name . '" />';
       echo '<input type="hidden" name="score" value="' , $score , '" />';
       echo '</form>';
                      ><&lt; Back to admin page</a>';
     echo '<a href=
                   **************
    </body>
    </html>
                                                                        removescore.php
                                                                FROM
   require_once
                               $id
                                                     $name
                                   "admin.php"
                     'Yes'
                                                      'screenshot'
                                                                           $screenshot
                                           $date
                 "id"
         'id'
                        DELETE
                                    'screenshot'
         id
                                                                        require once
sid
                           $id
                                                        $id
```


you are here > 287



PHP & MySQL Magnets Solution

The removescore.php script is almost finished, but it is missing a few important pieces of code. Use the magnets to plug in the missing code and give Guitar Wars the ability to eradicate unwanted scores.


```
<html xmlns="http://www.w3.org/1999/xhtml" xml:lang="en" lang="en">
  <meta http-equiv="Content-Type" content="text/html; charset=utf-8"/>
<head>
  <title>Guitar Wars - Remove a High Score</title>
  <link rel="stylesheet" type="text/css" href="style.css" />
</head>
                                                          Include the shared script
<body>
  <h2>Guitar Wars - Remove a High Score</h2>
                                                          files but use required once
                                                          since they are critical to
<?php
                                                          the score removal.
                      ('appvars.php');
     require once
                       ('connectvars.php');
     require once
   if (isset($_GET['id']) && isset($_GET['date']) && isset($_GET['name']) &&
    isset($_GET['score']) && isset($_GET[
                                             'screenshot'
     // Grab the score data from the GET
                                                            The script reacts differently
     $id = $ GET['id'];
                                                            depending on whether the incoming
     $date = $_GET['date'];
                                                            request is a GET or a POST.
     $name = $ GET['name'];
     $score = $ GET['score'];
                       = $ GET [
                                    'screenshot'
        $screenshot
   else if (isset($_POST['id']) && isset($_POST['name']) && isset($_POST['score'])) (
      // Grab the score data from the POST
                                                     The @ PHP error suppression directive prevents
                                                     errors from being displayed. This makes sense
                           'id'
               = $ POST[
                                                     for unlink() since we may be attempting to delete a file that doesn't exist In which case,
      $name = $_POST['name'];
      $score = $ POST['score'];
                                                     we don't want the user to see an error.
      echo 'Sorry, no high score was specified for removal.';
                                                                         This script can be used
    if (isset($_POST['submit'])) (
                                                                         to remove any scores,
                                                                         so the uploaded image
      if ($ POST['confirm'] ==
                                  'Yes'
                                                                         file must be deleted as
         Delete the screen shot image file from the server
                                                                         part of the removal.
         @unlink(GW_UPLOADPATH . $screenshot);
         // Connect to the database
         $dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_WAME);
```





Add Remove Score and Admin scripts to Guitar Wars so that scores can be removed.

Create two new text files, removescore.php and admin.php, and add the code to them that you've just worked through. Upload the new scripts to your web server, and then open the Admin script in your web browser. Click the "Remove" link for a score you'd like to get rid of, and then confirm its removal on the Remove Score page. Return to the Admin page to make sure the score is gone, and then go to the main Guitar Wars page (index.php) to see the change there.




290 Chapter 5



PHP&MySQLcross

Tired of uploading image files? How about uploading some knowledge into a bunch of squares laid out in a puzzle?



Across

- 1. The type attribute of the <input> tag must be set to this for a file upload form field.
- 4. It's usually a good idea to store uploaded application images in an folder.
- This SQL statement is used to change the structure of a table.This SQL statement is used to put the results of a query in a certain order.
- Information about uploaded files is stored in the \$_..... superglobal variable.
- This PHP statement is used to insert code from another script.
- It's a good idea to do this to newly uploaded files.

Down


- To prevent a DELETE FROM statement from deleting more than one row, use this SQL statement.
- 3. When a file is uploaded through a form, it is placed in a folder on the web server.
- When altering a table, this SQL command takes care of adding a new column.
- 6. This PHP statement is used to create a constant.
- Include files are very handy for data among several script files.
- This SQL statement is used as part of another statement to order query results in descending order.

you are here >

291



PHP&MySQLcross Solution



292

Your PHP & MySQL Toolbox

Feel free to take a virtual bow. Not only are you loved by virtual guitarists worldwide, but you've also added quite a few new skills to your PHP and MySQL skillset: altering the structure of tables, handling file uploads, controlling the order of data, and removing data.

ALTER TABLE table
ADD COLUMN column type

Use this SQL statement to add a
new column of data to an existing
new column of data to an existing
database table. The column is
database table and of the table
and is initially empty for rows
that are already in the database.

include, include_once,
require, require_once

These PHP statements allow you to share script code across multiple script files in an application, eliminating duplicate code and making the code easier to maintain.



This folder provides a convenient location to store images for an application, including images that were uploaded by users.

\$_FILES

This built-in PHP superglobal variable stores information about files that have been uploaded through a file input form. You can use it to determine the filename, the temporary storage location of the file, the file size, and the file type, among other things.

ORDER BY column

This SQL statement orders the results of a query based on a certain column of data. Use ASC or DESC after the statement to sort the data in ascending or descending order. ASC is the default ordering for ORDER BY, and is, therefore, optional.

DELETE FROM table
WHERE column = match
LIMIT num

Use this SQL statement to remove a row from a database table. More than one match can (and often should) be used to improve the accuracy of the deletion, not to mention limiting the deletion to a single row.

6 securing your application



A short climb, a little telephone rewiring, and this little one-horse town won't know what hit it.


Your parents were right: don't talk to strangers. Or at least don't trust them. If nothing else, don't give them the keys to your application data, assuming they'll do the right thing. It's a cruel world out there, and you can't count on everyone to be trustworthy. In fact, as a web application developer, you have to be part cynic, part conspiracy theorist. Yes, people are generally bad, and they're definitely out to get you! OK, maybe that's a little extreme, but it's very important to take security seriously and design your applications so

that they're protected against anyone who might choose to do harm.

this is a new chapter

The day the music died

Uh oh, our young virtual rock prodigy's moment in the limelight has been short-lived, as Jacob's top Guitar Wars score is somehow missing, along with all the other scores. It seems a diabolical force is at work to foil the high score application and prevent Guitar Warriors from competing online. Unhappy virtual guitarists are unhappy users, and that can only lead to unhappy application developers... you!




A SELECT query reveals that the guitarwars table

is completely empty-all

Where did the high scores go?

We know that the main Guitar Wars page is empty, but does that mean the database is empty too? A SELECT query can answer that question:



Somehow all of the high score rows of data have been deleted from the Guitar Wars database. Could it be that maybe someone out there is using our Remove Score script to do evil? We need to protect the scores!

| | h of the following techniques you could use to protect the Guita scores from bitter virtual guitar haters, and then write down why |
|--|---|
| Password protect the Admin page so that only people who know the passwor (you!) can remove scores. | d Create a user registration system, and then only give some users (you!) administrative privileges. |
| | ** |
| | ** |
| | |
| | |
| Check the IP address of the computer try to access the Admin page, and only allow certain ones (yours!). | F 1 Climate at a transport of factions |
| | |
| | |
| | |
| | **** |

you are here > 297

Sharpen your pencil Solution

Circle which of the following techniques you could use to protect the Guitar Wars high scores from bitter virtual guitar haters, and then write down why.



Password protect the Admin page so that only people who know the password (you!) can remove scores.

Password protecting the Admin page is a good quick and dirty solution because it's not too complicated and it secures the site quickly.

All of the techniques are circled because they all solve the problem, although some are more viable than others.



Create a user registration system, and then only give some users (you!) administrative privileges.

A user registration system with admin privileges is a great solution but involves a fair amount of planning and coding effort... Guitar Wars needs security now!



Check the IP address of the computer trying to access the Admin page, and only allow certain ones (yours!).

Checking the IP address works but it makes the site dependent upon your computer's IP address, which very well may change



Eliminate the score removal feature altogether.


Removing the feature certainly solves this specific problem, but if you recall, the removal feature was originally added in the previous chapter to make the site easier to maintain.

298

Securing the teeming hordes

A simple and straightforward way to quickly secure the Guitar Wars high scores is to use HTTP authentication to password protect the Admin page. This technique actually involves both a user name and a password, but the idea is to require a piece of secret information from an administrator before they have access to restricted application features, such as the score removal links.


When a page is secured using HTTP authentication, a window pops up requesting the user name and password before access is allowed to the protected page. In the case of Guitar Wars, you can limit access to the Admin page to as few people as you want, potentially just you! HTTP authentication provides a simple way to secure a page using PHP.




www.it-ebooks.info

Protecting the Guitar Wars Admin page

HTTP authentication works like this: when a user tries to access a page protected by authentication, such as our Admin page, they are presented with a window that asks them for a user name and password.





Dumb Questions

Q: Is HTTP authentication really secure?

A: Yes. And no. It all depends on what you're trying to accomplish with security. Nothing is ever truly 100% secure, so we're always talking about **degrees of security**. For the purposes of protecting high scores in Guitar Wars, HTTP authentication provides a reasonable level of security. You could add encryption to the password to ramp that up a bit further. However, it's probably not sufficient for an application involving data that is more sensitive, such as financial data.

Q: What happens if the user name and password are entered incorrectly?

A: The browser emits a small electrical shock through the mouse. No, it's nothing that harsh. Usually a message is displayed letting users know that they're attempting to access a secure page that is apparently none of their business. It's ultimately up to you how grim you want this message to read.

Q: Does HTTP authentication require both a user name and password? What if I only want to use a password?

A: You aren't required to use both a user name and password. If you just want a password, focus solely on checking the \$_SERVER['PHP_AUTH_PW'] global variable. More on how this variable is checked in just a moment...

How exactly do you protect a page with HTTP authentication? Do you call a PHP function?

A: Yes, you do. HTTP authentication involves establishing a line of communication between the browser and the server through HTTP headers. You can think of a header as a short little conversation between the browser and the server. Browsers and servers use headers quite often to communicate outside of the context of PHP, but PHP does allow you to send a header, which is how HTTP authentication works. We're about to dig a lot deeper into headers and their role in HTTP authentication with PHP.



When should the authentication of the Admin page actually take place?

you are here > 301


HTTP authentication requires headers

The idea behind HTTP authentication is that the server withholds a protected web page, and then asks the browser to prompt the user for a user name and password. If the user enters these correctly, the browser goes ahead and sends along the page. This dialog between browser and server takes place through **headers**, which are little text messages with specific instructions on what is being requested or delivered.

Headers are actually used **every time** you visit a web page, not just when authentication is required. Here's how a normal, unprotected web page is delivered from the server to the browser with the help of headers:


All web pages are delivered with the help of headers.

Web server





Headers control precisely how and what kind of information is passed back and forth between a web browser and web server. An individual header often consists of a name/value pair that identifies a piece of information, such as the content type of a web page (HTML). A certain group of headers is sent to the server as part of a web page request, and then another group is returned to the browser as part of the response. Let's take a closer look at these groups of headers to find out exactly what is sent as the client and server communicate with each other.



Headers matter to us in regard to Guitar Wars because they provide the mechanism for disrupting the delivery of a page from the server and requiring the user to enter a user name and password before it can be delivered. In other words, you have to tweak the headers returned by the server to protect a page with HTTP authentication.



Head First: You seem to be grabbing a lot of attention when it comes to authenticating web pages. Is it really justified, or are you just looking for your fifteen minutes of virtual fame?

Header: Oh, I'm justified alright. You more than likely take for granted that I play a role in delivering every single web page in existence. So I guess you could say the web wouldn't even work without me in the picture. I'll be around a lot longer than fifteen minutes, even if I do go largely underappreciated.

Head First: So what exactly is this role you play?

Header: You have to understand that web browsers and web servers aren't people, so they can't just call each other up on the phone or send a text message.

Head First: OMG!

Header: Yeah, I know, it's a little shocking but machines just don't communicate the same way people do. But browsers and servers still have to communicate, and they do so using me.

Head First: So how does that work?

Header: When someone types in a URL or clicks a link on a web page, the browser assembles a GET request that it sends to the server. This request is packaged into a series of headers, each of which contains information about the request. The headers hold information like the name and host of the page being requested, the type of browser doing the requesting, etc.

Head First: I still don't see why that's important.

Header: Well, do you think it's important when you tell the person at the coffee shop that you want a giganto vanilla espressiato with skim milk?

Head First: Of course, they need to know what I want.

Header: That's the same idea here. The browser tells the server what it wants by packaging the request up and sending it along in headers.

304 Chapter 6

Head First: Interesting. But I heard that servers can send headers as well. I thought servers just sent back web pages.

Header: Ah, good question. I am just as important on the other side of the communication because the server has to do more than just dump a bunch of content on the browser. The browser wouldn't have a clue what to do with it without knowing a bit more.

Head First: Such as what?

Header: The type of the content, for one thing. That's probably the most important thing, but the server also sends along other stuff like the size of the content, the date and time of the delivery, and so on.

Head First: When does the web page itself get sent?

Header: Right after the server sends me to the browser, it follows up with the actual content, be it HTML code, PDF data, or image data such as a GIF or JPEG image.

Head First: OK, I'm starting to see how you work in regard to normal web pages. But what about this authentication stuff?

Header: I play the same role for an authenticated web page as I do for a normal web page except that I also take care of letting the browser know that the page must be authenticated. That way the browser can prompt the user for authentication information.

Head First: You mean a user name and password?

Header: Exactly. And then it's up to PHP code on the server to decide if the user name and password match up, in which case, the server can go ahead and send along the rest of the page.

Head First: Fascinating. Thanks for the heads up.

Header: No problem. That's just part of my job.


Take control of headers with PHP

Using PHP, you can carefully control the headers sent by the server to the browser, opening up the possibilities for performing header-driven tasks such as HTTP authentication. The built-in header() function is how a header is sent from the server to the browser from within a PHP script.


header('Content-Type: text/html');

The header () function immediately sends a header from the server to the browser and must be called before any actual content is sent to the browser. This is a very strict requirement—if even a single character or space is sent ahead of a header, the browser will reject it with an error. For this reason, calls to the header () function should precede any HTML code in a PHP script: The header()
function lets you
create and send
a header from a
PHP script.





After processing the authentication headers, the browser waits for the user to take action via the authentication window. The browser takes a dramatically different action in response to what the user does...





If the user enters the **correct** user name and password, and clicks Log In, the server sends the HTML content of the admin.php page to the browser. The browser displays the Admin page, and the user can then remove scores just like the previous unprotected version.



If the user enters the **incorrect** user name and password, and clicks Log In, the server tells the browser to prompt the user again. The browser continues this process as long as the user keeps entering incorrect user name/password combinations. In other words, if they don't know the user name and password, their only way out is to click Cancel.



If the user clicks the Cancel button to bail out of the authentication, the server sends the browser a page with a denial message, and nothing else—the admin.php page is not sent. The denial message is controlled by PHP code in the admin.php script that is closely associated with the headers. This code calls the PHP exit() function to display a message and immediately exit the script:


exit('<h2>Guitar Wars</h2>Sorry, you must enter a valid ' .
'user name and password to access this page.');

you are here > 307



PHP Magnets

The Guitar Wars Admin script is missing several important pieces of PHP code that provide HTTP authentication. Use the magnets to fill in the missing code and use headers to make the Admin page secure. Hint: Some magnets may be used more than once.



I wonder if it's possible to send other kinds of headers using PHP?



Indeed it is... headers aren't just for security

Although authentication presents the immediate need for headers, they are quite flexible and can do lots of other interesting things. Just call the header () function with the appropriate name/value pair, like this:

The browser is redirected to the About page upon receiving this header.

```
header('Location: http://www.gultarwars.net/about.php');
?>
```

The header is called a **location header** and redirects the current page to a page called about.php on the same Guitar Wars site. Here we use a similar header to redirect to the about.php page after five seconds:

The browser is redirected to the About page after 5 seconds.

```
header('Refresh: 5; url=http://www.guitarwars.net/about.php');
echo 'In 5 seconds you'll be taken to the About page.';
?>
```

This header is called a **refresh header** since it refreshes a page after a period of time has elapsed. You often see the URL in such headers reference the current page so that it refreshes itself.

One last header is called a **content type header** because it controls the type of the content being delivered by the server. As an example, you can force a page to be plain text, as opposed to HTML, by using the following header when calling the header () function:

```
The content is delivered to the browser as plain text

header('Content-Type: text/plain');

echo 'This <strong>text</strong> won't actually be bold.';

?>
```

In this example, the text echoed to the browser is displayed exactly as shown with no special formatting. In other words, the server is telling the browser **not** to render the echoed content as HTML, so the HTML tags are displayed literally as text.

Watch it!

Headers must be the very first thing sent to the browser in a PHP file.


Because headers must be sent before any content, it is extremely important to not allow even a single space to appear outside of PHP code before calling the header() function in a PHP script.

you are here > 309



PHP Magnets Solution

The Guitar Wars Admin script is missing several important pieces of PHP code that provide HTTP authentication. Use the magnets to fill in the missing code and use headers to make the Admin page secure. Hint: Some magnets may be used more than once.





Add HTTP authorization to the Admin script.

Modify the admin.php script to use HTTP authentication so that only you have access to it. Upload the script to your web server and then open it in your web browser. Try entering the wrong user name and password first to see how access is restricted.



The Guitar Warriors are stoked about the high score application now being safe and secure!


Dumb Questions

When exactly does the exit () function get called in the Guitar Wars Admin script?

A: Even though the exit() function appears in the PHP code just below the two calls to the header() function, it's only called if the user cancels out of the authentication window by clicking the Cancel button. If the authentication fails, the server doesn't continue executing past the two header() calls. Instead, it resends the headers and tries again. Only if the user clicks Cancel does the server make it to the exit() function, in which case it sends along the content within the function call and nothing else. If the authentication succeeds, exit() isn't called because the script never makes it inside the if statement—the code inside the if statement is only executed if the user name and password aren't set or have been entered incorrectly.

Q: Does the "basic realm" of an HTTP authentication have any real purpose?

A: Yes It defines a security "zone" that is protected by a particular user name and password. Once the user name and password have been successfully entered for a given realm, the browser will remember it and not continue to display the authentication window for subsequent authentication headers in the same realm. In other words, realms allow a browser to remember that you've met the security requirements for a given collection of pages—just specify the same realm for the authentication headers in the pages.



We need to secure the Remove Score script, and I'm pretty sure we can just use HTTP authentication again.



Joe: That makes sense. I mean, it worked fine for the Admin page.

Frank: That's true. So all we have to do is put the same header authorization code in the Remove Score script, and we're good to go, right?

Jill: Yes, that will certainly work. But I worry about duplicating all that authorization code in two places, What happens if later on we add another page that needs to be protected? Do we duplicate the code yet again?

Joe: Code duplication is definitely a problem. Especially since there is a user name and password that all the scripts need to share. If we ever wanted to change those, we'd have to make the change in every protected script.

Frank: I've got it! How about putting the \$username and \$password variables into their own include file, and then sharing that between the protected scripts. We could even put it in an appears.php include file for application variables.

Joe: I like where you're headed but that solution only deals with a small part of the code duplication. Remember, we're talking about a decent sized little chunk of code.

```
<?php
// User name and password for authentication
$username = 'rock';
$password = 'roll';

if ('isset($ SERVER['PHP AUTH USER']) || !isset($ SERVER['PHP AUTH PW']) ||
   ($ SERVER['PHP AUTH USER'] != $username) || ($ SERVER['PHP AUTH PW'] != $password)) (
   // The user name/password are incorrect so send the authentication headers
   header('HTTP/1.1 401 Unauthorized');
   header('WWW-Authenticate: Basic realm="Guitar Wars"');
   exit('<h2>Guitar Wars</h2>Sorry, you must enter a valid user name and password to access this page.');
}

<html>
<html

<html>
<html>
<html

<html>
<html

<html>
<html

<html

<html

<html

<html

<html>
<html

<html
```

200 100

Jill: You're both right, and that's why I think we need a new include file that stores away all of the authorization code, not just the \$username and \$password variables.

Frank: Ah, and we can just include that script in any page we want to protect with HTTP authorization.

Joe: That's right! We just have to make sure we always include it first thing since it relies on headers for all the HTTP authorization stuff.

Create an Authorize script


We already have all the code we need for a new Authorize script; it's just a matter of moving the code from admin.php to a new script file (authorize.php), and replacing the original code with a require once statement.

We're pulling this code from admin.php so that we can place it in its own script file, authorize.php.

```
// User name and password for authentication
     $username = 'rock';
     $password = 'roll';
    if ([isset(5_SERVER['PHP_AUTH_USER']) || |isset($_SERVER['PHP_AUTH_PW']) ||
       ($ SERVER['PHP AUTH USER'] != $username) || ($ SERVER['PHP AUTH PW'] != $password)) (
// The user name/password are incorrect so send the authentication headers
       header('HTTP/1.1 401 Unauthorized');
       header('WWW-Authenticate: Basic realm="Guitar Wars"');
       exit('<h2>Guitar Wars</h2>Sorry, you must enter a valid user name and password to access this page.');
  <hearl>
   <meta http-equiv="Content-Type" content="text/html; charget=uff-8" />
    <title>Guitar Wars-High Scores Administrations/Eitle>
    <tink rel="styleshest" type-"text/ona" href="atyle.csa" />
  </head>
   <h2>Gustar Wars-High Scores Administration(/h2>
   cpabelow is a list of all Guitar Wars high scores. Use this page to remove scores as needed.
   require once ('appvars.php');
   require_once('commenters.php');
    // Connect to the database
    Schoo = mysqli connect(DB HOST, DE USER, DB PASSWORD, DB WAME);
    // Betrieve the score data from MySQL
    Squery - "SELECT " FROM quitarwarm CRDER BY score DEDC, date ASC";
   Sdata = mysqli query(Sdbc, Squery);
   // Loop through the array of score data, formatting it as HTML
   echo '';
   while (Stow - mysqli_fetch_array(Sdata)) (
// Display the score data
    echo '<atrong>' . Srow['name'] . '</strong>';
echo '' | Srow['date') | '';
echo ': Srow['score'] . '';')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')')

     echo '<a href-"::moves:core.php?id=' . Srow('id') . 'samp;date=' . Srow('date') . 'samp;name=' . Srow('name') . 'samp;score=' . Jrow('score*) . 'amp;screenshot*' . Srow('screenshot*) . '">Remove</a>
   scho 'c/tables':
  mysqli_close(fdbe);
</body>
```

admin.php





BULLET POINTS

- PHP scripts can use headers to control how the server delivers web content to the browser.
- The built-in PHP header () function is used to send headers to the browser, which can be used to redirect a page, control the content type of a page, or request the authentication of a page.
- When headers are sent to the browser using the header () function, calls to the header () function must come before any other content is sent.
- When a page is protected using HTTP authentication, the user name and password entered by the user are stored in the \$ SERVER superglobal.
- The 'basic realm' of an HTTP authentication is a security zone that gets associated with a specific user name and password, allowing multiple pages to be secured together.
- The built-in PHP exit() function exits a PHP script, preventing any code following it from being executed or otherwise sent to the browser.

Dumb Questions

Q: I still don't fully understand how Ethel got around the security in Guitar Wars. What did she do?

A: She capitalized on the weakness inherent in only protecting one page (Admin) when the remove score feature really relies on two pages (Admin and Remove Score). The Admin page presents a series of Remove links that link to the Remove Score page. The specifics about which score to remove are passed in the URL, allowing the Remove Score script to access them through the \$_GET\$ superglobal. If you were able to put together a legit URL for the Remove Score page, you could remove scores without even going through the Admin page. That's what Ethel did.

Q: But how did she know how to structure the URL to the Remove Score page?

A: She's pretty crafty, but this task didn't require a genius. Remember she mentioned bookmarking the Remove Score page back when the whole site was unprotected. Well, a bookmark is just a URL, and she was able to use it to construct a URL that directly accessed the Remove Score page without having to go through the Admin page.

OK, but the high scores had been re-entered since the previous attack. Doesn't that mean the old URLs wouldn't work since the dates are different?

A: Yes, that's a very good point. But remember, Ethel is pretty clever. She could easily look at the main Guitar Wars page and see the new dates, which she then plugged into the old URL to remove the new scores without any trouble. It's important to never underestimate the ability of determined people to reverse-engineer your PHP scripts and exploit weaknesses.

Alright, so protecting both the Admin and Remove Score pages stops Ethel, but don't they now make it a total hassle to remove scores legitimately?

A: No, not at all. Without the help of realms, it would definitely be a hassle removing scores legitimately because you'd have to enter the user name and password separately for the Admin and Remove Score pages. But remember that a realm was established that is the same in both pages, meaning that the pages fall under the same security zone. And once you go through the authentication window for a page in a given realm, the user name and password are remembered throughout the realm. The end result is that successfully entering the user name and password once is sufficient to unlock both pages.

316 Chapter 6




Never underestimate the ability of determined people to reverse-engineer your PHP scripts and exploit weaknesses.



Create the Authorize script and include it in the Admin and Remove Score scripts to secure them.

Create a new text file called authorize.php, and enter the code for the Authorize script into it. Then modify the admin.php script so that it includes the Authorize script instead of the actual HTTP authentication code. Add the same require_once statement to the beginning of the removescore.php script so that it is also protected by HTTP authentication.

Upload all of the scripts to your web server and then try to open the Remove Score script directly in your web browser. You may have to clear any previous HTTP authentication sessions in your browser for it to prompt you again—most browsers remember an authentication realm so that you don't have to keep re-entering the user name and password.




you are here >

317

High Score Guitar Wars Episode II : Attack of the Clones

Sadly, happiness in the Guitar Wars universe didn't last for long, as bogus scores are showing up in the application in place of legitimate scores... and still inciting rage throughout the Guitar Wars universe. Apparently it's entirely possible to disrupt the Guitar Wars high score list without removing scores. But how?



Subtraction by addition

Until now we've operated under the assumption that any high score submitted with a screen shot image is considered verified. It's now reasonably safe to say this is not the case! And it's pretty clear who the culprit is...


Oh yeah, it's me... guilty as charged! All I had to do was post my awesomely fake scores with touched-up screen shots. Ah, it's good to be the top Guitar Warrior.

Ethel realized she could wreak plenty of Guitar Wars have by simply submitting bogus scores with doctored screen shot images.

| Nrite down how you would solve the problem of people being able to post bogus high scores to the Guitar Wars application: | |
|--|----|
| | |
| | į |
| | 97 |
| | |

Security requires humans

Even in this modern world we live in, sometimes you can't beat a real live thinking, breathing human being. In this case, it's hard to beat a real person when it comes to analyzing a piece of information and assessing whether or not it is valid. We're talking about moderation, where a human is put in charge of approving content posted to a web application before it is made visible to the general public.



Human moderation

is an excellent way

320

Plan for moderation in Guitar Wars

Adding a human moderation feature to Guitar Wars is significant because it affects several parts of the application. The database must change, a new script must be created to carry out an approval, the Admin page must add an "Approve" link to each score, and finally, the main page must change to only show approved scores. With this many changes involved, it's important to map out a plan and carry out each change one step at a time.


Use ALTER to add an approved column to the table.

Let's start with the database, which needs a new column for keeping up with whether or not a score has been approved.

| 36 | date . exec | | 4005 | secondari | approved |
|------|---------------------|---------------|--------|------------------|----------|
| | | | | | |
| 21 | 2008-0578-21-14-59 | Lookly One | 500710 | Suddysteoori (dT | 0 |
| 29,1 | 20068501.31:15:17 | Titora Itylia | 334190 | thomesourt gif | 0 |
| 36 | 2000/05/02 18:02:04 | Ethal Hackel | 550000 | adultacers pl | 0 |
| 21 | 2008-05-02-20-33-34 | Mach | 314340 | Manage | 0 |
| :35 | 2008-05/02/20:36:38 | Person | 322718 | persona gil | 0 |

Modify the Admin page to include an "Approve" link for scores that have yet to be approved.

The Approve Score script is a back-end script that shouldn't normally be accessed directly. Instead, it is accessed through "Approve" links generated and displayed on the Admin page—only unapproved scores have the "Approve" link next to them.




Create an Approve Score script that handles approving a new high score (sets the approved column to 1).

With the database ready to accommodate high score approvals, you need a script to actually handle approving a score. This Approve Score script is responsible for looking up a specific score in the database and changing the approved column for it.



Change the query on the main page to only show approved scores.

The last step is to make sure all this approval stuff gets factored into the main high score view. So the main page of the application changes to only show high scores that have been approved—without this change, all the other approval modifications would be pointless.



Make room for approvals with ALTER

Adding the new approved column to the guitarwars table involves a one-time usage of the ALTER TABLE statement, which is an SQL statement we've used before.

ALTER TABLE guitarwars
ADD COLUMN approved TINYINT

The MySQL data type BOOL is an alias for TINYINT, so you can use either one

The new approved column is a TINYINT that uses 0 to indicate an unapproved score, or 1 to indicate an approved score. So all new scores should start out with a value of 0 to indicate that they are **initially unapproved**.



Wait a minute. I don't think you can just go adding a column to the database without changing the Add Score script—shouldn't it INSERT data into the new column?




It's true, a new column means a new value in the INSERT query in the Add Score script.

It's important to not lose sight of the fact that a PHP application is a careful orchestration of several pieces and parts: a database consisting of tables with rows and columns, PHP code, HTML code, and usually CSS code. It's not always immediately apparent that changing one part requires changing another. Adding the new approved column in the guitarwars table for the sake of the new Approve Score script also requires modifying the INSERT query in the Add Score script:

All newly inserted high score rows have approved set to O ... unapproved! -

INSERT INTO guitarwars
VALUES (0, NOW(), '\$name', '\$score','\$screenshot', 0)



When a new column is added, its approved column is set to 0 so that it starts out unapproved.

Sharpen your pencil

The Approve Score script is similar in structure to the Remove Score script except that its job is to approve a score. Finish the missing code for the Approve Score script, making sure to secure the page and only approve the appropriate score based on score data passed through a URL.

```
<?php
......t
?>
. . .
<?php
 require_once('appvars.php');
 require_once('connectvars.php');
 if (isset($ POST['submit'])) {
  if (______) {
    // Connect to the database
    $dbc = mysqli connect(DB HOST, DB USER, DB PASSWORD, DB NAME);
    // Approve the score by setting the approved column in the database
    $query = "UPDATE guitarwars SET
    mysqli_query($dbc, $query);
    mysqli close($dbc);
    // Confirm success with the user
       ......
  else {
       ......
 echo '<a href=" ">&lt;&lt; Back to admin page</a>';
?>
. . .
```

Sharpen your pencil Solution

The Approve Score script is similar in structure to the Remove Score script except that its job is to approve a score. Finish the missing code for the Approve Score script, making sure to secure the page and only approve the appropriate score based on score data passed through a URL.

```
<?php
                                         Including the Authorize script is all that is required
      require once (authorize.php')
                                          to secure the Approve Score page with a user name
                                          and password, but it must be done first thing in the
?>
                                          script since it relies on headers.
. . .
<?php
                                                              Create an Approve
  require_once('appvars.php');
                                                              Score script that
  require_once('connectvars.php');
                                                              handles approving
                                                              a new high score
                                                              (sets the approved
  if (isset($ POST['submit'])) {
                                                              column to 1).
              f_POST['confirm'] == 'Yes'
       // Connect to the database
                                                                                The D must match
       $dbc = mysqli connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
                                                                               in order to carry
                                                                                out the approval.
       // Approve the score by setting the approved column in the database
                                           approved = 1 WHERE id = 'fid'
       $query = "UPDATE guitarwars SET
       mysqli_query($dbc, $query);
                                         Setting the approved column
       mysqli close($dbc);
                                                                       Confirm the approval with
                                         to I approves the score.
                                                                       the user by showing the
                                                                       approved score and name
       // Confirm success with the user
               'The high score of '. Iscore . 'for '. Iname . ' was successfully approved.';
    else {
               'Sorry, there was a problem approving the high score ;
                                            It's important to reveal when a score cannot
                                            be approved, similar to how other Guitar Wars
                                            scripts report errors.
  echo '<a href=" admin.php
                                     "><&lt; Back to admin page</a>';
?>
                                  Provide a link back to the
                                  Admin page for easier navigation.
```

Dumb Questions

Q: Why isn't it necessary to pass along the screen shot filename when approving a score?

A: Because the process of approving a high score only requires enough information to look up a score row and then approve it. This means you really only need enough data to hone in on a particular row. The date, name, and score are enough to find a particular row and set its approved column to 1.

Q: It seems kind of cryptic to use 0 and 1 in the approved column. Are there other ways to represent this information?

A: Yes. The MySQLENUM data type, which stands for "enumerated," allows you to create a column with a restricted list of possible values. So instead of adding the approved column as a TINYINT that is intended to be 0 or 1, you could add it as an ENUM that can only have values of 'yes' and 'no', like this:

ALTER TABLE guitarwars
ADD COLUMN approved ENUM('yes', 'no')

Sharpen your pencil

The score data used to approve a score in the Approve Score script is passed through "Approve" links that are generated in the Admin script. Finish the missing code in the Admin script so that it generates these links.

```
// Loop through the array of score data, formatting it as HTML
echo '';
echo 'NameDateScoreAction';
while ($row = mysqli fetch array($data)) {
 // Display the score data
 echo '<strong>' . $row['name'] . '</strong>';
 echo '' . $row['date'] . '';
 echo '' . $row['score'] . '';
 echo '<a href="removescore.php?id=' . $row['id'] . '&amp;date=' . $row['date']
   '& name=' . $row['name'] . '& score=' . $row['score'] .
   '& screenshot=' . $row['screenshot'] . '">Remove</a>';
 if (______) {
 echo '';
                                                Hint: only unapproved scores
echo '';
                                                should have an "Approve" link.
```




The score data used to approve a score in the Approve Score script is passed through "Approve" links that are generated in the Admin script. Finish the missing code in the Admin script so that it generates these links.

```
missing code in the Admin script so that it generates these links.
// Loop through the array of score data, formatting it as HTML
echo '';
echo 'NameDateScoreAction';
while ($row = mysqli fetch_array($data)) {
 // Display the score data
 echo '<strong>' . $row['name'] . '</strong>';
 echo '' . $row['date'] . '';
 echo '' . $row['score'] . '';
 echo '<a href="removescore.php?id=' . $row['id'] . '&amp;date=' . $row['date']
   '& name=' . $row['name'] . '& score=' . $row['score']
                                                             Check to see if the score is
   '&screenshot=' . $row['screenshot'] . '">Remove</a>';
                                                             unapproved before generating
 if ( frow['approved'] == 'O' ) ( <
                                                             the "Approve" link.
   echo '/ <a href="approvescore.php?id=' .frow[id'] . '&amp;date=' .frow['date'] .
     '&name=' . frow['name'] . '&score=' . frow['score'] . '&screenshot=' .
     frow['screenshot'] . '>Approve</a>';
                                                          Generate the "Approve" link
 echo '';
                                                          so that the id, date, name,
                                                          score, and screen shot image
                                                          name are passed in the URL
echo '';
                                  The "Approve" link ties
                                   the Admin page to the
                                   Approve Score page
                                   Guitar Wars - Approve a High Score
                                                              Modify the Admin
                                                              page to include an
                                                              "Approve" link for
                                                              scores that have
                                                              yet to be approved.
```

Unapproved scores aren't worthy


All the infrastructure is now in place for the moderation feature in the Guitar Wars high score application. All that's missing is the final step, which is altering the main page to only show approved scores. This involves tweaking the SQL SELECT query so that it only plucks out scores whose approved column is set to 1 (approved). This is accomplished with a WHERE statement.

Use WHERE to select rows based on the value of a certain column.




The addition of the WHERE statement to this query eliminates any scores that haven't been approved, which includes all new scores. This gives the moderator a chance to look them over and decide whether they should be removed or made visible to the public (approved).

If the approved column is set to something other than I, the score won't be displayed.



Only approved
scores show up
on the main page
(index.php) now.

322710
Name 1878-CE-01 20 No.
Name 0872-NA.
Dec. 1308-CE-01 20 No.
Name 0872-NA.
Dec. 1308-CE-01 20 No.
Name 0872-NA.
Dec. 1308-CE-01 20 No.



Change the query on the main page to only show approved scores.





Create the Approve script and rework the rest of the Guitar Wars application to use it.

Using a MySQL tool, issue the ALTER query to add the new approved column to the guitarwars table. Then change the INSERT query in the addscore. php script to insert a 0 in the approved column for new rows of data.

Now create a new text file called approvescore.php, and enter the code for the Approve Score script into it. Then modify the admin.php script to include an "Approve" link for high scores that have yet to be approved. And finally, change the SELECT query in index.php to only show approved scores.

Upload all of the scripts to your web server, and open the main Guitar Wars page in your web browser. Take note of the scores that are visible, and then open the Admin page. Click one of the "Approve" links and continue along to approve the score. Then go back to the main page to see if the score appears.






329

The million-point hack


The moderated version of Guitar Wars represents a significant security improvement, but it's far from bulletproof. It seems our wily infiltrator has managed to find another weakness in the high score system and somehow sneak her high scores past the moderator. Ethel must be stopped, **permanently**, in order to restore trust throughout the Guitar Wars universe.



Everything in moderation...?

Even though the moderator knows without a doubt that he never approved Ethel's high score submission, it nevertheless is there in plain view with the approved column set to 1. We know the Add Score script sets the approved column to 0 for new high scores because we just modified the INSERT query in that script. Something just doesn't add up!

The Guitar Wars moderator can't figure out what happened.



| id | date | | - | ASO YES | | |
|-------|--|--------------------|------------------------------------|--------------------|----------|--|
| 21 | Colored Colored | name score | | screenshot | approved | |
| - 000 | 2008-05-01 20:36:07 | Belita Chevy | 282470 | belitasscore.gif | 1 | |
| 22 | 2008-05-01 20:36:45 | Jacob Scorcherson | 389740 | | | |
| 23 | 2008-05-01 20:37:02 | Nevil Johansson | T PARKETS TO | jacobsscore.gif | 1 | |
| 24 | 2008-05-01 20:37:23 | Y Trans | 98430 | nevilsscore.gif | 1 | |
| 25 | | Paco Jastorius | 127650 | pacosscore.gif | 1 | |
| 1,110 | 2008-05-01 20:37:40 | Phiz Lairston | 186580 | phizsscore.gif | | |
| 26 | 2008-05-01 20:38:00 | Kenny Lavitz 64930 | | | - 1 | |
| 27 | 2008-05-01 20:38:23 | Jean Paul Jones | 243260 | kennysscore.gif | 1 | |
| 28 | 2008-05-01 21:14:56 | | and it is a transfer of the second | jeanpaulsscore.gif | 1 | |
| 29 | | Leddy Gee | 308710 | leddysscore.gif | 1 | |
| 1100 | 2008-05-01 21:15:17 | T-Bone Taylor | 354190 | tbonesscore.gif | - | |
| 31 | 2008-05-02 20:32:54 | Biff Jeck | 314340 | | 1 | |
| 32 | 2008-05-02 20:36:38 | Liet 1 1 No. | | biffsscore.gif | 1 | |
| 22 | The state of the s | Pez Law | 322710 | pezsscore.gif | 1 | |
| 33 | 2008-05-05 14:58:59 | Ethel Heckel | 1000000 | ethelsscore2 gif | | |





How do you think Ethel's bogus post got past the moderator?


This score was never approved by the moderator yet its approved column is set to 1, resulting in it being displayed.



As it turns out, Ethel's million-point hack had nothing to do with the Approve Score form. Her mischief was completely isolated to the Add Score form. Below is the exact form data that Ethel entered into the Add Score form to carry out her hack. Enter the same form data in your own form and add the score. What do you think is going on?







Tricking MySQL with comments

The real culprit in Ethel's million-point attack is, strangely enough, SQL comments. A double-hyphen (--) is used in SQL to comment out the remainder of a line of SQL code. You **must follow the double-hyphen with a space** for it to work (--), but everything after the space is ignored. Now take a look at Ethel's full query with that little nugget of wisdom.

INSERT INTO guitarwars

VALUES (0, NOW(), 'Ethel Heckel', '1000000', 'ethelsscore2.gif', 1)

Is it making more sense? The comment effectively erased the remaining SQL code so that it wouldn't generate an error, allowing Ethel's version of the query to slip through without a snag. The end result is an instantly approved new high score that the moderator never got a chance to catch.

The -- comment causes the rest of the line of SQL code to be ignored.


Ethel tricked the query into approving her score-

| id | date | name | store | | |
|----|---------------------|--------------|---------|------------------|----------|
| | | *** | 31016 | screenshot | approved |
| 33 | 2008-05-05 14:58:59 | Ethel Heckel | 1000000 | ethelsscore2.gif | Τ. |

The Add Score form was SQL injected

Ethel's attack is known as an **SQL injection**, and involves an extremely sneaky trick where form data is used as a means to change the fundamental operation of a query. So instead of a form field just supplying a piece of information, such as a name or score, it meddles with the underlying SQL query itself. In the case of Guitar Wars, Ethel's SQL injection used the Score field as a means of not only providing the score, but also the screen shot filename, the approval value, and a comment at the end to prevent the original SQL code from generating an error.

Form fields are a security weak point for web applications because they allow users to enter data.



Dumb Questions

Q: Are there any other kinds of comments in SQL besides -?

A: Yes. Another variation on the single-line comment involves the use of # nstead of --, but still results in commenting out any SQL code to the end of the line following the comment. SQL also supports multi-line comments that are similar to PHP's multi-line comments in that you enclose commented code between /* and */.

Q: Would Ethel's SQL injection attack have still worked if the approved column wasn't at the end of the table?

A: No, and that's a really important point. This particular INSERT query relies on the default ordering of columns in the table. Tacking on 1 to the end of the query just happened to work because approved is the last column, appearing immediately after the screenshot column.

Protect your data from SQL injections

The real weakness that SQL injections capitalize on is form fields that aren't validated for dangerous characters. "Dangerous characters" are any characters that could potentially change the nature of an SQL query, such as commas, quotes, or -- comment characters. Even spaces at the end of a piece of data can prove harmful. Leading or trailing spaces are easy enough to eliminate with the built-in PHP function trim()—just run all form data through the trim() function before using it in an SQL query.

```
$name = trim($_POST['name']);
$score = trim($_POST['score']);
$screenshot = trim($_FILES['screenshot']['name']);
```

But leading and trailing spaces aren't the whole problem. You still have the commas, quotes, comment characters, and on, and on. So in addition to trimming form fields of extra spaces, we also need a way to find and render harmless other problematic characters. PHP comes to the rescue with another built-in function, mysqli_real_escape_string(), which escapes potentially dangerous characters so that they can't adversely affect how a query executes. These characters can still appear as data in form fields, they just won't interfere with queries.

Putting the trim() and mysqli_real_escape_string() functions together provide a solid line of defense against SQL injections.

The trim() function gets rid of leading and trailing spaces in this form data.

SQL injections can be prevented by properly processing form data.

The mysqli_real_escape_string() function converts dangerous characters into an escaped format that won't adversely affect SQL queries.

```
$nane = mysqli_real_escape_string($dbc, trim($_POST['name']));
$score = mysqli_real_escape_string($dbc, trim($_POST['score']));
$screenshot = mysqli_real_escape_string($dbc, trim($_FILES['screenshot']['name']));
```

Processing the three Guitar Wars form fields with the trim() and mysqli_real_escape_string() functions greatly reduces the chances of another SQL injection attack. But these two functions aren't enough—maybe there's a way to make the query itself less vulnerable...

mysqli_real_escape_string() is considered a database function, which is why it requires you to pass it a database connection variable, like the one used when submitting queries.

A safer INSERT (with parameters)

Aside from exploiting weak form field protection, Ethel's SQL injection also relied on the fact that the approved column followed the screenshot column in the database structure. That's how she was able to get away with just adding 1 onto the end of INSERT and have it go into the approved column. The problem is that the INSERT query is structured in such a way that it has to insert data into all columns, which adds unnecessary risk.

```
Ideally, we shouldn't be setting the
id and approved columns since they
could just have default values.


INSERT INTO guitarwars
VALUES (0, NOW(), '$name', '$score', '$screenshot', 0)
```

When data is inserted into a table like this, the order of the data must line up with the order of the columns in the table structure. So the fifth piece of data will go into the screenshot column because it's the fifth column in the table. But it really isn't necessary to explicitly insert the id or approved columns since id is auto-incremented and approved should always be 0. A better approach is to focus on inserting only the data explicitly required of a new high score. The id and approved columns can then be allowed to **default** to AUTO INCREMENT and 0, respectively.


We need a restructured INSERT query that expects a list of columns prior to the list of data, with each matching one-to-one. This eliminates the risk of the approved column being set—it's no longer part of the query. If this kind of query looks familiar, it's because you've used it several times in other examples. An INSERT query can be written so that it nails down exactly what values go in what columns.

INSERT INTO guitarwars (date, name, score, screenshot)
VALUES (NOW(), '\$name', '\$score', '\$screenshot')

Nothing can be inserted into the approved column because it isn't listed as part of the query.



allowing you to insert data without having to worry about the underlying table structure. In fact, it's considered better coding style to use this kind of INSERT query so that data is inserted exactly where you intend it to go, as opposed to relying on the structural layout of the table.



Hang on a second. This is the first I've heard of default values in MySQL tables. Is that really possible?



Not only is it possible, but it's a very good idea to specify DEFAULT column values whenever possible.

The SQL DEFAULT command is what allows you to specify a default value for a column. If a column has a default value, you can forego setting it in an INSERT query and relax in the confidence of knowing that it will automatically take on the default value. This is perfect for the approved column in the guitarwars table. Now we just need to modify the table one more time to set the default value for approved to 0 (unapproved).

Since the approved column already exists, in this ALTER TABLE statement we have to use MODIFY COLUMN instead of ADD COLUMN.

ALTER TABLE guitarwars
MODIFY COLUMN approved TINYINT

DEFAULT 0

DEFAULT results in the approved column being automatically assigned a value of O unless an INSERT query explicitly sets it otherwise.

You still have to specify the type of the column—just make sure it's the same as when you first added the column.

With the approved column now altered to take on a default value, the new and improved INSERT query in the Add Score script can insert high scores without even mentioning the approved column. This is good design since there's no need to explicitly insert a value that can be defaulted, and it adds a small extra degree of security by not exposing the approved column to a potential attack.


Form validation can never be too smart

One last step in minimizing the risks of SQL injection attacks involves the form validation in the Add Score script. Before checking to see if the screen shot file type or size is within the application-defined limits, the three Add Score form fields are checked to make sure they aren't empty.

```
if (!empty($name) && !empty($score) && !empty($screenshot)) {

This if statement checks to make sure all of the form fields are non-empty.
```

There is nothing wrong with this code as-is, but securing an application is often about going above and beyond the call of duty. Since the Score field expects a number, it makes sense to not just check for a non-empty value but for a numeric value. The PHP is_numeric() function does just that by returning true if a value passed to it is a number, or false otherwise. It's consistently doing the little things, like checking for a number when you're expecting a number, that will ultimately make your application as secure as possible from data attacks.



Whenever possible, insist on form data being in the format you've requested.

| Exercise | Rewrite the Add Score form validation if statement to use the isnumeric() function so that only a numeric score is allowed. |
|----------|---|
| | *************************************** |
| | *************************************** |
| | |
| | |



Rewrite the Add Score form validation if statement to use the isnumeric () function so that only a numeric score is allowed.

| if (le | mpty(fna | me) && is | numeri | (fscore) | && lemp | ty(fscree | nshot)) | £ |
|--------|----------|-------------|--------|----------|---------|-----------|---------|---|
| | | | | | | | | |
| .} | | *********** | | | | ******** | | |




Beef up the handling of form data in the Add Score script.

Tweak the assignment of form data to variables in the addscore.php script so that the trim() and mysqli_real_escape_string() functions are used to clean up the form data. Then change the INSERT query so that it specifies both the column names and values, eliminating the need to provide values for the id and approved columns. Also change the if statement that validates the form fields so that it checks to make sure the score is numeric.

Finally, use a MySQL tool to run the ALTER query that defaults the approved column to 0.

Upload the new Add Score script to your web server, navigate to it in a web browser, and then try the same SQL injection attack again.




Sure, this error message could be a bit more specific, but it gets the job done without adding extra logic to the script.

Form validation is a topic that reaches far beyond database security. Chapter 10 revisits form validation in much more detail...

340

Cease fire!

It seems Ethel's will to interfere with the Guitar Wars high scores has finally been broken thanks to the improvements to the application that render it immune to SQL injections. The reigning Guitar Wars champion has responded by posting a new top score.



Your PHP & MySQL Toolbox

In addition to taking the Guitar Wars high score application to a new level, you've acquired several new tools and techniques. Let's revisit the most important ones.

header()

This built—in PHP function is used to send a header from the server to the browser, allowing you to perform tasks such as redirecting the page, specifying a certain content type, or carrying out HTTP authentication.

\$ SERVER

Among other things, this built—in PHP superglobal stores the user name and password entered by the user when attempting to access a page requiring HTTP authentication. You can check these against expected values to protect pages that need to be secured.

is_numeric()

This built—in PHP function checks to see if a value is a number. It is useful for checking to see if a numeric form field actually holds a numeric value.

DEFAULT value

exit()

This SQL statement establishes the default value of a column in a table. If a new row is added and the column isn't set, it will take on the default value.

This built-in PHP function causes

a PHP script to stop immediately.

additional HTML code is delivered

Once a script encounters the

exit() function, no additional PHP code is executed and no

to the browser.

trim(), mysqli_real_
escape_string()

These two built-in PHP functions are handy for processing form data and preventing problematic characters from interfering with SQL queries. The first function trims leading and trailing spaces, while the latter escapes special characters.

Human Moderation

Everything in moderation! In this case, it means that a human being is often the best line of defense in identifying and eliminating unwanted content being posted by others. Automated security techniques are still important, but it's hard to beat a living, breathing person with a brain!

HTTP Authentication

A simple web security technique that limits access to a web page or script using a user name and password. Although not intended for highly sensitive security applications, HTTP authentication can be handy for quickly adding a degree of security to a web application.

Column/Value Query

A type of INSERT query where columns and their respective values are carefully matched to each other, as opposed to relying on the order of the data matching the structural order of the columns in the table.

SQL Injection

A security breach that involves an evil-doer somehow compromising a SQL query to gain unwarranted access to a database. Most SQL injections involve tricking a web form into passing along dangerous data directly to a dynamically constructed query. So form validation is often the solution.

Form Validation

The process of checking all of the data entered by a user into a form to ensure that it is in the expected format. In addition to making forms easier to use, validation can help make web applications more secure by not allowing users to enter bad data.

7 building personalized web apps



What's your name again? Johnson, right.
Well, I'm showing no record of you, Mr. Jackson.
Are you sure you signed up for a warranty on
your cryogenic storage cell? Oh, I see, so you're
calling from inside your cell right now. And what
was your name again?




No one likes to be forgotten, especially users of web

applications. If an application has any sense of "membership," meaning that users somehow interact with the application in a personal way, then the application needs to remember the users. You'd hate to have to reintroduce yourself to your family every time you walk through the door at home. You don't have to because they have this wonderful thing called **memory**. But web applications don't remember people automatically—it's up to a savvy web developer to use the tools at their disposal (PHP and MySQL, maybe?) to **build personalized web apps that can actually remember users**.

They say opposites attract

It's an age-old story: boy meets girl, girl thinks boy is completely nuts, boy thinks girl has issues, but their differences become the attraction, and they end up living happily ever after. This story drives the innovative new dating site, Mis-match.net. Mismatch takes the "opposites attract" theory to heart by mismatching people based on their differences.

Problem is, Mismatch has yet to get off the ground and is in dire need of a web developer to finish building the system. That's where you come in. Millions of lonely hearts are anxiously awaiting your completion of the application... don't let them down!




Check out

these guns!

they enter information about themselves that they can share with other Mismatch users, such as their gender, birthdate, and location.

Mismatch is all about personal data



In addition to viewing a user profile, Mismatch users can edit their own personal profiles using the Edit Profile page. But there's a problem in that the application needs to know which user's profile to edit. The Edit Profile page somehow needs to keep track of the user who is accessing the page.



How can Mismatch customize the Edit Profile page for each different user?

Mismatch needs user log-ins


The solution to the Mismatch personal data access problem involves user log-ins, meaning that users need to be able to log into the application. This gives Mismatch the ability to provide access to information that is custom-tailored to each different user. For example, a logged-in user would only have the ability to edit their own profile data, although they might also be able to view other users' profiles. User log-ins provide the key to personalization for the Mismatch application.

A user log-in typically involves two pieces of information, a username and a password.

User log-ins allow web applications to get personal with users.

Username

The job of the username is to provide each user with a unique name that can be used to identify the user within the system. Users can potentially access and otherwise communicate with each other through their usernames.



Password

The password is responsible for providing a degree of security when logging in users, which helps to safeguard their personal data. To log in, a user must enter both a username and password.

Passwords are extremely sensitive pieces of data and should never be made visible within an application, even inside the database.

A username and password allows a user to log in to the Mismatch application and access personal data, such as editing their profile. The Edit Profile page now indicates that the user is logged in. sidneyk Mismatch - Edi You are logged in as sidneyk. Mismatch - Edit Profile The user's username and When a user logs in, the application is Password are all that is able to remember the Personal Information required to let the application user and provide a know who they are. First name: Sidney personalized experience. Last name: Kelsow Gender: Female ‡ Birthdate: 1984-07-19

Come up with a user log-in gameplan

Adding user log-in support to Mismatch is no small feat, and it's important to work out exactly what is involved before writing code and running database queries. We know there is an existing table that stores users, so the first thing is to alter it to store log-in data. We'll also need a way for users to enter their log-in data, and this somehow needs to integrate with the rest of the Mismatch application so that pages such as the Edit Profile page are only accessible after a successful log-in. Here are the log-in development steps we've worked out so far:



Use ALTER to add username and password columns to the table.

The database needs new columns for storing the log-in data for each user. This consists of a username and password.





Build a new Log-In script that prompts the user to enter their username and password.

The Log In form is what will ultimately protect personalized pages in that it prompts for a valid username and password. This information must be entered properly before Mismatch can display user-specific data. So the script must limit access to personalized pages so that they can't be viewed without a valid log-in.





Connect the Log-In script to the rest of the Mismatch application.

The Edit Profile and View Profile pages of the Mismatch application should only be accessible to logged in users. So we need to make sure users log in via the Log In script before being allowed to access these pages.






Before going any further, take a moment to tinker with the Mismatch application and get a feel for how it works.

Download all of the code for the Mismatch application from the Head First Labs web site at www.headfirstlabs.com/books/hfphp. Post all of the code to your web server except for the .sql files, which contain SQL statements that build the necessary Mismatch tables. Make sure to run the statement in each of the .sql files in a MySQL tool so that you have the initial Mismatch tables to get started with.

When all that's done, navigate to the index.php page in your web browser, and check out the application. Keep in mind that the View Profile and Edit Profile pages are initially broken since they are entirely dependent upon user log-ins, which we're in the midst of building.



The main Mismatch page allows you to see the name and picture of the latest users, but not much else without being logged in.



The complete source code for the Mismatch application is available for download from the Head First Labs web site:

www.headfirstlabs.com/books/hfphp

Prepping the database for log-ins


OK, back to the construction. The mismatch_user table already does a good job of holding profile information for each user, but it's lacking when it comes to user log-in information. More specifically, the table is missing columns for storing a username and password for each user.

mismatch_user

| | | | | | dos | hirthdate | city | state | picture |
|---|---------|-----------|------------|-----------|--------|-----------|------|-------|---------|
| Ī | usor id | ioin date | first_name | last_name | genaer | pirinaaro | , | | |
| ١ | OSEI_IG | lem | | | | | | | |
| ١ | | | | | | | | | |
| ١ | | | | | | | | | |
| | | | | | | | | | 1 |
| | | | | | | 1 | | | |
| | l | 1 | | | | | • | | |

Username and password data both consist of pure text, so it's possible to use the familiar VARCHAR MySQL data type for the new username and password columns. However, unlike some other user profile data, the username and password shouldn't ever be allowed to remain empty (NULL).

The username and password columns contain simple text data but should never be allowed to go empty.



The mismatch_user table needs columns for username and password in order to store user log—in data.

Dumb Questions

Q: Why can't you just use user_id instead of username for uniquely identifying a user?

A: You can if you want. In fact, the purpose of user_id is to provide an efficient means of uniquely identifying user rows. However, numeric IDs tend to be difficult to remember, and users really like being able to make up their own usernames for accessing personalized web applications. So it's more of a usability decision to allow Johan to be able to log in as "jnettles" instead of "11". No one wants to be relegated to just being a number!

| ew people would war ry and remember a onger than 16 chara | nt to password — cters! | I | passwor isernam | ting an SQI and columns are able to here, and ne | s to the tak nold 32 cha | ole posit aracters, | i <mark>oned as</mark> : , passwo | showr ord al | n, with ole to h | old |
|---|-------------------------|----------|--------------------|--|-----------------------------|------------------------|--------------------------------------|-----------------|---------------------|---------|
| | | | | | | | | | | |
| | | | : | mismato | ch_user | : | | | | |
| | | naceword | | mismato | ch_user | gender | birthdate | city | state | picture |
| use | er_id username | password | join_date | | | | birthdate | city | state | picture |
| USE | er_id username | password | | | | | birthdate | city | state | picture |

sharpen your pencil

ALTER TABLE is used to add new columns to an existing table.

Finish writing an SQL statement to add the username and password columns to the table positioned as shown, with username able to hold 32 characters, password able to hold 16 characters, and neither of them allowing NULL data.

ALTER TABLE mismatch_user ADD username VARCHAR(32) NOT NULL AFTER user_id,

ADD password VARCHAR(16) NOT NULL AFTER username added first, so it's OK

to reference it here.

The AFTER statement controls where in the table new columns are added.

mismatch user

| user_id username | ioin date | first name | last_name | gender | birthdate | city | state | picture | |
|------------------|----------------------|------------|-----------|--------|-----------|------|-------|---------|---|
| user_id username | password join_uuio | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | l |

_ The position of columns in a table doesn't necessarily matter, although it can serve an organizational purpose in terms of positioning the most important columns first.

Use ALTER to add username and password columns to the table.

> Surely you don't just store a password in the database as-is... don't you also need to encrypt a password before storing it?

Good point... passwords require encryption.

Encryption in Mismatch involves converting a password into an unrecognizable format when stored in the database. Any application with user log-in support must encrypt passwords so that users can feel confident that their passwords are safe and secure. Exposing a user's password even within the database itself is not acceptable. So we need a means of encrypting a password before inserting it into the mismatch user table. Problem is, encryption won't help us much if we don't have a way for users to actually enter a username and password to log in...




0

An application log-

in requires a user

Constructing a log-in user interface

With the database altered to hold user log-in data, we still need a way for users to enter the data and actually log in to the application. This log-in user interface needs to consist of text edit fields for the username and password, as well as a button for carrying out the log-in.



there are no Questions

Q: So asterisks aren't actually stored in the database, right?

A: That's correct. The asterisks displayed in a password form field simply provide **visual security**, preventing someone from looking over your shoulder as you enter the password. When the form is submitted, the password itself is submitted, not the asterisks. That's why it's important for the password to be encrypted before inserting it into the database.



If you're worried about how users will be able to log in when we haven't assigned them user names and passwords yet... don't sweat it.


We'll get to creating user names and passwords for users in just a bit. For now it's important to lay the groundwork for log-ins, even if we still have more tasks ahead before it all comes together.

Encrypt passwords with SHA()


The log-in user interface is pretty straightforward, but we didn't address the need to encrypt the log-in password. MySQL offers a function called SHA() that applies an encryption algorithm to a string of text. The result is an encrypted string that is exactly 40 hexadecimal characters long, regardless of the original password length. So the function actually generates a 40-character code that uniquely represents the password.

Since SHA() is a MySQL function, not a PHP function, you call it as part of the query that inserts a password into a table. For example, this code inserts a new user into the mismatch_user table, making sure to encrypt the password with SHA() along the way.

The MySQL, SHA() function encrypts a piece of text into a unique 40-character code.



The same SHA() function works on the other end of the log-in equation by checking to see that the password entered by the user matches up with the encrypted password stored in the database.



Comparing Pecrypting passwords

Once you've encrypted a piece of information, the natural instinct is to think in terms of decrypting it at some point. But the SHA() function is a one-way encryption with no way back. This is to preserve the security of the encrypted data—even if someone hacked into your database and stole all the passwords, they wouldn't be able to decrypt them. So how is it possible to log in a user if you can't decrypt their password?

You don't need to know a user's original password to know if they've entered the password correctly at log-in. This is because SHA() generates the same 40-character code as long as you provide it with the same string of text. So you can just encrypt the log-in password entered by the user and compare it to the value in the password column of the mismatch_user table. This can be accomplished with a single SQL query that attempts to select a matching user row based on a password.

The SHA()
function provides
one-way
encryption—you
can't decrypt
data that has
been encrypted.

This is the password entered by the user in order to log in.

SELECT * FROM mismatch user

WHERE password = SHA('tatlover')

The SHA() function is called to encrypt the password so that it can appear in the WHERE clause.

This SELECT query selects all rows in the mismatch_user table whose password column matches the entered password, 'tatlover' in this case. Since we're comparing encrypted versions of the password, it isn't necessary to know the original password. A query to actually log in a user would use SHA(), but it would also need to SELECT on the user ID, as we see in just a moment.

Making room for the encrypted password

The SHA () function presents a problem for Mismatch since encrypted passwords end up being 40 characters long, but our newly created password column is only 16 characters long. An ALTER is in order to expand the password column for storing encrypted passwords.

ALTER TABLE mismatch_user
CHANGE password password VARCHAR(40) NOT NULL

The size of the password column is changed to 40 so that encrypted passwords will fit.

Dumb Questions

Q: What does SHA() stand for?

A: The SHA () function stands for Secure Hash Algorithm. A "hash" is a programming term that refers to a unique, fixed-length string that uniquely represents a string of text. In the case of SHA (), the hash is the 40-character hexadecimal encrypted string of text, which uniquely represents the original password.

Q: Are there any other ways to encrypt passwords?

A: Yes. MySQL offers another function similar to SHA() called MD5() that carries out a similar type of encryption. But the SHA() algorithm is considered a little more secure than MD5(), so it's better to use SHA() instead. PHP also offers equivalent functions (sha1() and md5()) if you need to do any encryption in PHP code, as opposed to within an SQL query.



Add the username and password columns to the mismatch user table, and then try them out.

Using a MySQL tool, execute the ALTER statement to add the username and password columns to the mismatch user table.

ALTER TABLE mismatch user ADD username VARCHAR(32) NOT NULL AFTER user id, ADD password VARCHAR(16) NOT NULL AFTER username

But our password column actually needs to be able to hold a 40character encrypted string, so ALTER the table once more to make room for the larger password data.

```
ALTER TABLE mismatch user
  CHANGE password password VARCHAR(40) NOT NULL
```

Now, to test out the new columns, let's do an INSERT for a new user.

INSERT INTO mismatch user

```
Don't forget to encrypt
the password by calling
the SHA() function.
(username, password, join date) VALUES ('jimi', SHA('heyjoe'), NOW())
```

To double-check that the password was indeed encrypted in the database, take a look at it by running a SELECT on the new user.

```
SELECT password FROM mismatch_user WHERE username = 'jimi'
```

And finally, you can simulate a log-in check by doing a SELECT on the username and using the SHA() function with the password in a WHERE clause. For a successful log-in, this must be the same password used when inserting the row.

```
SELECT username FROM mismatch user WHERE password = SHA('heyjoe')
```

```
File Edit Window Help OppositesAttract
                                          Only one user matches the encrypted password.
```

So the password is now encrypted, but we still need to build a log-in form. Could we just use HTTP authentication since it requires a username and password to access protected pages?

Yes! HTTP authentication will certainly work as a simple user log-in system.

If you recall from the Guitar Wars high score application in the last chapter, HTTP authentication was used to restrict access to certain parts of an application by prompting the user for a username and password. That's roughly the same functionality required by Mismatch, except that now we have an entire database of possible username/password combinations, as opposed to one application-wide username and password. Mismatch users could use the same HTTP authentication window; however, they'll just be entering their own personal username and password.




The standard HTTP authentication window, which is browser-specific, can serve as a simple log-in user interface.


0

Authorizing users with HTTP

As Guitar Wars illustrated, two headers must be sent in order to restrict access to a page via an HTTP authentication window. These headers result in the user being prompted for a username and password in order to gain access to the Admin page of Guitar Wars.



Sending the headers for HTTP authentication amounts to two lines of PHP code—a call to the header () function for each header being sent.





Circle the different parts of the Mismatch application that are impacted by the Log-In script (login.php) and its usage of HTTP authentication to control access. Then annotate how those application pieces are impacted.










viewprofile.php



editprofile.php



there are no **Dumb Questions**

Q: Why isn't it necessary to include the home page when requiring user log-ins?

A: Because the home page is the first place a user lands when visiting the site, and it's important to let visitors glimpse the site before requiring a log-in. So the home page serves as both a teaser and a starting point—a teaser for visitors and a starting point for existing users who must log in to go any deeper into the application.

Can logged-in users view anyone's profile?

A: Yes. The idea is that profiles are visible to all users who log in, but remain private to guests. In other words, you have to be a member of Mismatch in order to view another user's profile.

Q: How does password encryption affect HTTP authentication?

A: There are two different issues here: transmitting a password and storing a password. The SHA() MySQL function focuses on securely **storing** a password in a database in an encrypted form. The database doesn't care how you transmitted the password initially, so this form of encryption has no impact on HTTP authentication. However, an argument could be made that encryption should also take place during the **transmission** of the password when the HTTP authentication window submits it to the server. This kind of encryption is outside the scope of this chapter and, ultimately, only necessary when dealing with highly sensitive data.

Logging In Users with HTTP Authentication

The Log-In script (login.php) is responsible for requesting a username and password from the user using HTTP authentication headers, grabbing the username and password values from the \$_SERVER superglobal, and then checking them against the mismatch_user database before providing access to a restricted page.


```
require once('connectvars.php');
                                                                                    If the username and password
                                                                                    haven't been entered, send
  if (!isset($ SERVER['PHP AUTH USER']) || !isset($ SERVER['PHP AUTH PW'])) {
                                                                                    the authentication headers
    // The username/password weren't entered so send the authentication headers
   header('HTTP/1.1 401 Unauthorized');
                                                                                    to prompt the user.
   header('WWW-Authenticate: Basic realm="Mismatch"');
    exit('<h3>Mismatch</h3>Sorry, you must enter your username and password to log in and access ' .
      'this page.');
                                                                     Grab the username
                                                                     and password
  // Connect to the database
                                                                     entered by the user.
                                                                                            Perform a query to
  $dbc = mysqli connect(DB HOST, DB USER, DB PASSWORD, DB NAME);
                                                                                            see if any rows match
  // Grab the user-entered log-in data
                                                                                            the username and
  $user username = mysqli real escape string($dbc, trim($ SERVER['PHP AUTH USER']));
                                                                                            encrypted password.
  $user_password = mysqli_real_escape string($dbc, trim($ SERVER['PHP AUTH PW']));
  // Look up the username and password in the database
  $query = "SELECT user id, username FROM mismatch user WHERE username = '$user username' AND "
    "password = SHA('$user password')";
  $data = mysqli query($dbc, $query);
  if (mysqli num rows($data) == 1) {
    // The log-in is OK so set the user ID and username variables
                                              _ If a row matches, it means the
    $row = mysqli fetch array($data);
    $user id = $row['user id'];
                                                log-in is OK, and we can set the fuser id and fusername variables.
                                                                                   If no database row matches the
    $username = $row['username'];
                                                                                   username and password, send
                                                                                   the authentication headers
  else {
    // The username/password are incorrect so send the authentication headers
                                                                                   again to re-prompt the user.
   header('HTTP/1.1 401 Unauthorized');
   header('WWW-Authenticate: Basic realm="Mismatch"');
    exit('<h2>Mismatch</h2>Sorry, you must enter a valid username and password to log in and ' .
      'access this page.');
  // Confirm the successful log-in
 echo('You are logged in as ' . $username . '.');
?>
         All is well at this point, so
                                                              Build a new Log-In script that
         confirm the successful log-in.
                                                              prompts the user to enter their
                                                              username and password.
```




Create the new Log-In script, and include it in the View Profile and Edit Profile scripts.

Create a new text file named login.php, and enter the code for the Log-In script in it (or download the script from the Head First Labs site at www.headfirstlabs.com/books/hfphp). Then add PHP code to the top of the viewprofile.php and editprofile.php scripts to include the new Log-In script.

Upload all of the scripts to your web server, and then open the main Mismatch page in a web browser. Click the View Profile or Edit Profile link to log in and access the personalized pages. Of course, this will only work if you've already added a user with a username and password to the database.





Ruby loves horror movies, cube puzzles, and spicy food, but hates Mismatch at the moment for not letting her sign up and use the system.

I'd love to log in and start working on my profile, but I can't figure out how to sign up.



New Mismatch users need a way to sign up.

The new Mismatch Log-In script does a good job of using HTTP authentication to allow users to log in. Problem is, users don't have a way to sign up—logging in is a problem when you haven't even created a username or password yet. Mismatch needs a Sign-Up form that allows new users to join the site by creating a new username and password.


Username?

Password?

A form for signing up new users

What does this new Sign-Up form look like? We know it needs to allow the user to enter their desired username and password... anything else? Since the user is establishing their password with the new Sign-Up form, and passwords in web forms are typically masked with asterisks for security purposes, it's a good idea to have two password form fields. So the user enters the password twice, just to make sure there wasn't a typo.

So the job of the Sign-Up page is to retrieve the username and password from the user, make sure the username isn't already used by someone else, and then add the new user to the mismatch user database.



One potential problem with the Sign-Up script involves the user attempting to sign up for a username that already exists. The script needs to be smart enough to catch this problem and force the user to try a different username. So the job of the Sign-Up page is to retrieve the username and password from the user, make sure the username isn't already used by someone else, and then add the new user to the mismatch user database.

Since the passwords are now encrypted, they're secure even when viewing the database.



PHP & MySQL Magnets

The Mismatch Sign-Up script uses a custom form to prompt the user for their desired username and password. Problem is, the script code is incomplete. Use the magnets below to finish up the script so new users can sign up and join the Mismatch community.

Here's the
Sign-Up form.

Mismatch - Sign Up

Registration Info-

Please enter your username and desired password to sign up to Mismatch.

| | Password: |
|--|---------------------------------------|
| php</td <td>Password</td> | Password |
| require_once('appvars.php'); | (retype); |
| require_once('connectvars.php'); | Sign Up |
| | |
| // Connect to the database | |
| \$dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAM | ME); |
| | |
| if (isset(\$_POST['submit'])) { | |
| // Grab the profile data from the POST | |
| (Calle + mim (C PO) | ST[' '])); |
| = mysqli_real_escape_string(\$dbc, trim(\$_PO | |
| = mysqli_real_escape_string(\$dbc, trim(\$_l | POST[' '])); |
| = mysqli_real_escape_string(vabe, trim(v_) | |
| = mysqli_real_escape_string(\$dbc, trim(\$_ | POST[' '])); |
| = mysqli_real_escape_scling(vabe, elim(v_ | |
| | |
| if (!empty(\$username) && !empty(\$password1) && !empty(\$pa | assword2) && |
| if (!empty(\$username) && :empty(*pass.oranz, *** | |
| ()) { | |
| | |
| // Make sure someone isn't already registered using this u | sername |
| | |
| <pre>\$query = "SELECT * FROM mismatch_user WHERE username = '</pre> | |
| | |
| <pre>\$data = mysqli_query(\$dbc, \$query);</pre> | |
| if (muscali num rows (\$data) == 0) { | |
| // | abase |
| \$query = "INSERT INTO mismatch_user (username, password | , Join_date, villone . |
| "('', SHA(''), NOW())"; mysqli_query(\$dbc, \$query); | Don't forget, you have to |
| "(' ', SHA(' '), NOW()) ; | escape an apostroph of the |
| | escape an apostrophe it it |
| <pre>mysqli_query(\$dbc, \$query);</pre> | dppears inside of single quotes. |
| 1.1.1 | 4 |
| // Confirm success with the user echo 'Your new account has been successfully created. | . You\'re now ready to log in and ' . |
| echo 'Your new account has been successfully elected ' edit your profile . | >'; |
| ' | |

```
else {
       // An account already exists for this username, so display an error message
       echo 'An account already exists for this username. Please use a different ' .
         'address.';
          ....;
   }
     echo 'You must enter all of the sign-up data, including the desired password ' .
   else {
       'twice.';
   }
  }
 mysqli_close($dbc);
Please enter your username and desired password to sign up to Mismatch.
<form method="post" action="<?php echo $_SERVER['PHP_SELF']; ?>">
 <fieldset>
    <legend>Registration Info</legend>
     <label for="username">Username:</label>
     value="<?php if (!empty(______)) echo ____; ?>" /><br/>
     <label for=" ">Password:</label>
     <input type=" "id=" "name=" "/><br/>
     <label for=" ">Password (retype):</label>
     <input type=" "id=" "name=" "/><br/>" /><br/>" /><br
    </fieldset>
    <input type="submit" value="Sign Up" name="submit" />
                                                                                                                                                                                                            signup.php
                                                                                                      $password1
             password
                                                                                                                                 $password1
                                                                                             $password1
                                                                                                                                                                            $username
                      password
                                                                                                                                                                                         | $username
                                                                         username
                                                                                                                                                                           $username
                                                                                                                                                                                                        $username
                                                                                                username
                                                                                                                                                                     $username
                                                                                                                                                                                                                      $username
                                                                                     username
                           password2
  password2
                                        password2
                                                                                                password1
                                                                                                                                                                                                             $password2
              password2
                                                                                                                                        password1
                                                                                                        password1
                                                                                                                                                                                                  $password2
                                                                                                                       password1
```




PHP & MySQL Magnets Solution

The Mismatch Sign-Up script uses a custom form to prompt the user for their desired username and password. Problem is, the script code is incomplete. Use the magnets below to finish up the script so new users can sign up and join the Mismatch community.

Here's the
Sign-Up form.

Mismatch - Sign Up



```
else {
   // An account already exists for this username, so display an error message
   echo 'An account already exists for this username. Please use a different ' .
    'address.';
                                                                    The username is not
                                                                     unique, so display an
                               Clear the fusername
        Susername
                                                                     error message.
                               variable so that the
                                form field is cleared
  echo 'You must enter all of the sign-up data, including the desired password ' .
 else {
   'twice.';
                                          One or more of the form fields are empty, so display an error message.
mysqli close($dbc);
?>
Please enter your username and desired password to sign up to Mismatch.
<form method="post" action="<?php echo $_SERVER['PHP_SELF']; ?>">
 <fieldset>
  <legend>Registration Info</legend>
  <label for="username">Username:</label>
  <input type="text" id="</pre>
                            username
                                         name=
                                                   username
                                                                  ?>" /><br />
                                                     $username
                               $username
   value="<?php if (!empty
                              ">Password:</label>
                 password1
  <label for="
                                                               password1
                                                                              /><br />
                                                     " name="
                               " id="
                                        password1
                   password
  <input type='
                               >Password (retype):</label>
  <label for="
                  password2
                                                                            /><br />
                                                    "name="
                                                              password2
                                id="
                                       password2
  <input type="
                   password
  </fieldset>
  <input type="submit" value="Sign Up" name="submit" />
 </form>
                                                                                                signup.php
```

there are no Dumb Questions

Q: Why couldn't you just use HTTP authentication for signing up new users?

A: Because the purpose of the Sign-Up script isn't to restrict access to pages. The Sign-Up script's job is to allow the user to enter a unique username and password, and then add them to the user database. Sure, it's possible to use the HTTP authentication window as an input form for the username and password, but the authentication functionality is overkill for just signing up a new user. It's better to create a custom form for sign-ups—then you get the benefit of double-checking the password for data entry errors.

So does the Sign-Up script log in users after they sign up?

A: No. And the reason primarily has to do with the fact that the Log-In script already handles the task of logging in a user, and there's no need to duplicate the code in the Sign-Up script. The Sign-Up script instead presents a link to the Edit Profile page, which is presumably where the user would want to go after signing in. And since they aren't logged in yet, they are presented with the Log-In window as part of attempting to access the Edit Profile page. So the Sign-Up script leads the user to the Log-In window via the Edit Profile page, as opposed to logging them in automatically.

Give users a chance to sign up

We have a Sign-Up script, but how do users get to it? We need to let users know how to sign up. One option is to put a "Sign Up" link on the main Mismatch page. That's not a bad idea, but we would ideally need to be able to turn it on and off based on whether a user is logged in. Another possibility is to just show a "Sign Up" link as part of the Log-In script.

When a new user clicks the "View Profile" or "Edit Profile" links on the main page, for example, they'll be prompted for a username and password by the Log-In script. Since they don't yet have a username or password, they will likely click Cancel to bail out of the log-in. That's our chance to display a link to the Sign-Up script by tweaking the log-in failure message displayed by the Log-In script so that it provides a link to signup.php.

Here's the original log-in failure code:

```
This code just shows a log-in error message with no mention of how to sign up for Mismatch.

exit('<h3>Mismatch</h3>Sorry, you must enter your username and password to log in and access ' .

'this page.');
```

This code actually appears in two different places in the Log-In script: when no username or password are entered and when they are entered incorrectly. It's probably a good idea to go ahead and provide a "Sign Up" link in both places. Here's what the new code might look like:

```
This code is much more helpful since it generates a link to the Sign-Up script so that the user can sign up.

exit('<h2>Mismatch</h2>Sorry, you must enter a valid username and password to log in and '.

'access this page. If you aren't a registered member, please <a href="signup.php">sign up</a>.');


Nothing fancy here, just a normal HTML link to the signup.php script.
```



Add Sign-Up functionality to Mismatch.

Create a new text file named signup.php, and enter the code for the Sign-Up script in it (or download the script from the Head First Labs site at www.headfirstlabs.com/books/hfphp). Then modify the login.php script to add links to the Sign-Up script for users who can't log in.

Upload the scripts to your web server, and then open the Sign-Up page in a web browser. Sign up as a new user and then log in. Then edit your profile and view your profile to confirm that the sign-up and log-in worked correctly. The application now has that personalized touch that's been missing.





I share a computer with two roommates, and I'd rather they not have access to my Mismatch profile. I need to be able to log out!

Community web sites must allow users to log out so that others can't access their personal data from a shared computer.

Allowing users to log out might sound simple enough, but it presents a pretty big problem with HTTP authentication. The problem is that HTTP authentication is intended to be carried out once for a given page or collection of pages—it's only reset when the browser is shut down. In other words, a user is never "logged out" of an HTTP authenticated web page until the browser is shut down or the user manually clears the HTTP authenticated session. The latter option is easier to carry out in some browsers (Firefox, for example) than others (Safari).

| You are logged in as sidneyk. | Edit Profile | stay in until y |
|---|--|--|
| Mismatch - Edit Profile Personal Information First name: Sidney Last name: Reisow Gender: Female 2 Birthdate: 1984-07-19 City: Tempe State: AZ Picture: Choose File 2 sidne | To view this page, you need to log in to area "Mismatch" on www.mis-match.net Your password will be sent in the clear. Name: sidneyk Password: Remember this password in my keychain Cancel Log in | Once you log in stay in until y close the brow |

A log-out feature would allow Sidney to carefully control access to her personal profile.

Even though HTTP authentication presents a handy and simple way to support user log-ins in the Mismatch application, it doesn't provide any control over logging a user out. We need to be able to both remember users and also allow them to log out whenever they want.


Wouldn't it be dreamy if we could remember the user without keeping them logged in forever. Am I just a hopeless PHP romantic?



Sometimes you just need a cookie

The problem originally solved by HTTP authentication is twofold: there is the issue of limiting access to certain pages, and there is the issue of remembering that the user entered information about themselves. The second problem is the tricky one because it involves an application remembering who the user is across multiple pages (scripts). Mismatch accomplishes this feat by checking the username and password stored in the \$_SERVER superglobal. So we took advantage of the fact that PHP stores away the HTTP authentication username and password in a superglobal that persists across multiple pages.

HTTP authentication stores data persistently on the client but doesn't allow you to delete it when you're done.



Client web

browser


browser sessions. So a user closing their browser won't automatically log them out of Mismatch. This isn't a problem for us because we can delete

a cookie at any time from script code, making it possible to offer a log-out


feature. We can give users total control over when they log out.

What's in a cookie?

A cookie stores **a single piece of data** under a unique name, much like a variable in PHP. Unlike a variable, a cookie can have an expiration date. When this expiration date arrives, the cookie is destroyed. So cookies aren't exactly immortal—they just live longer than PHP variables. You can create a cookie without an expiration date, in which case it acts just like a PHP variable—it gets destroyed when the browser closes.



Cookies allow you to store a string of text under a certain name, kind of like a PHP text variable. It's the fact that cookies outlive normal script data that makes them so powerful, especially in situations where an application consists of multiple pages that need to remember a few pieces of data, such as log-in information.



So Mismatch can mimic the persistence provided by the \$_SERVER superglobal by setting two cookies—one for the username and one for the password. Although we really don't need to keep the password around, it might be more helpful to store away the user ID instead.


there are no Dumb Questions

What's the big deal about cookies being persistent? Isn't data stored in a MySQL database persistent too?

Yes, database data is most certainly persistent. In fact, it's technically much more persistent than a cookie because there is no expiration date involved—if you stick data in a database, it stays there until you explicitly remove it. The real issue in regard to cookies and persistence is convenience. We don't need to store the current user's ID or username for all eternity just to allow them to access their profile; we just need a quick way to know who they are. What we really need is **temporary persistence**, which might seem like an oxymoron until you consider the fact that we need data to hang around longer than a page (persistent), but not forever.


Use Bake cookies with PHP

PHP provides access to cookies through a function called setcookie() and a superglobal called \$_COOKIE. The setcookie() function is used to set the value and optional expiration date of a cookie, and the \$_COOKIE superglobal is used to retrieve the value of a cookie.



The power of setting a cookie is that the cookie data persists across multiple scripts, so we can remember the username without having to prompt the user to log in every time they move from one page to another within the application. But don't forget, we also need to store away the user's ID in a cookie since it serves as a primary key for database queries.

The PHP setcookie() function allows you to store data in cookies.



The setcookie() function also accepts an optional third argument that sets the expiration date of the cookie, which is the date upon which the cookie is automatically deleted. If you don't specify an expiration date, as in the above example, the cookie automatically expires when the browser is closed.



Switching Mismatch to use cookies involves more than just writing a new Log-Out script. We must first revisit the Log-In script and change it to use cookies instead of HTTP authentication. Circle and annotate the parts of the Log-In code that you think need to change to accommodate cookies.

```
<?php
 require_once('connectvars.php');
 if (!isset($_SERVER['PHP_AUTH_USER']) || !isset($_SERVER['PHP_AUTH_PW'])) {
   // The username/password weren't entered so send the authentication headers
   header('HTTP/1.1 401 Unauthorized');
   header('WWW-Authenticate: Basic realm="Mismatch"');
   \verb|exit('<h3>Mismatch</h3>Sorry, you must enter your username and password to '
     'log in and access this page. If you aren\'t a registered member, please ' .
     '<a href="signup.php">sign up</a>.');
 // Connect to the database
 $dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
 // Grab the user-entered log-in data
 $user_username = mysqli_real_escape_string($dbc, trim($_SERVER['PHP AUTH USER']));
 $user_password = mysqli_real_escape_string($dbc, trim($_SERVER['PHP_AUTH_PW']));
 // Look up the username and password in the database
 $query = "SELECT user_id, username FROM mismatch_user WHERE username = " .
  "'$user_username' AND password = SHA('$user_password')";
 $data = mysqli_query($dbc, $query);
if (mysqli num rows(\$data) == 1) {
  // The log-in is OK so set the user ID and username variables
  $row = mysqli_fetch_array($data);
  $user id = $row['user_id'];
  $username = $row['username'];
else {
  // The username/password are incorrect so send the authentication headers
  header('HTTP/1.1 401 Unauthorized');
  header('WWW-Authenticate: Basic realm="Mismatch"');
  \verb|exit('<h2>Mismatch</h2>Sorry, you must enter a valid username and password ' .
    'to log in and access this page. If you aren\'t a registered member, ' \cdot
    'please <a href="signup.php">sign up</a>.');
// Confirm the successful log-in
echo('You are logged in as ' . $username . '.');
```

login.php

Sharpen your penci

We need to check for the existence of a cookie to see if the user is logged in or not.

Switching Mismatch to use cookies involves more than just writing a new Log-Out script. We must first revisit the Log-In script and change it to use cookies instead of HTTP authentication. Circle and annotate the parts of the Log-In code that you think need to change to accommodate cookies.

Instead of getting the username and password from an authentication window, we need to use a form with POST data.

login.php

```
<?php
                   require once('connectvars.php');
                   if (isset($_SERVER['PHP_AUTH_USER']) || !isset($_SERVER['PHP_AUTH_PW']))
                     header('HTTP/1.1 401 Unauthorized');
                     header('WWW-Authenticate: Basic realm=<u>"Mis</u>match"');
                     exit('<h3>Mismatch</h3>Sorry, you must enter your username and password to '
We no longer
                       'log in and access this page. If you aren\'t a registered member, please '
need to
                       '<a href="signup.php">sign up</a>.');
send HTTP
authentication
                   // Connect to the database
headers.
                  $dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
                  // Grab the user-entered log-in data
                  $user_username = mysqli_real_escape_string($dbc, trix($\_SERVER['PHP_AUTH_USER'])
                  $user_password = mysqli_real_escape_string($dbc, trin(($_SERVER['PHP_AUTH_PW']));
                  // Look up the username and password in the database
                  $query = "SELECT user_id, username FROM mismatch_user WHERE username =
                    "'$user_username' AND password = SHA('$user_password')";
                  $data = mysqli_query($dbc, $query);
                                                                                  The query doesn't
                                                                                  have to change at all!
                  if (mysqli_num_rows($data) == 1) {
                    ^{\prime\prime} The log-in is OK so set the user ID and username variables
                    $row = mysqli fetch_array($data);
                                                                            Here we need to set
                    $user_id = $row['user_id'];
                    $username = $row['username'
                                                                            two cookies instead of
                                                                            setting script variables.
                  else {
                    ^{\prime/} The username/password are incorrect so send the authentication headers
                   header('HTTP/1.1 401 Unauthorized');
                    header('WWW-Authenticate: Basic realm="Mismatch"');
                   exit('<h2>Mismatch</h2>Sorry, you must enter a valid username and password ' .
                      'to log in and access this page. If you aren\'t a registered member, ' .
                      'please <a href="signup.php">sign up</a>.');
                 // Confirm the successful log-in
                 echo('You are logged in as ' . susername . '.');
               ?>
    Since we can't rely on the HTTP authentication window
```


for entering the username and password, we need to

create an HTML Log-In form for entering them.

A new form takes the

Rethinking the flow of log-ins

Using cookies instead of HTTP authentication for Mismatch log-ins involves more than just rethinking the storage of user data. What about the log-in user interface? The cookie-powered log-in must provide its own form since it can't rely on the authentication window for entering a username and password. Not only do we have to build this form, but we need to think through how it changes the flow of the application as users log in and access other pages.



A cookie-powered log-in

The new version of the Log-In script that relies on cookies for log-in persistence is a bit more complex than its predecessor since it must provide its own form for entering the username and password. But it's more powerful in that it provides log-out functionality.

```
(Log In
<?php
  require once ('connectvars.php'); Error messages are now stored
                                     in a variable and displayed, if
                                                                                                          login.php
  // Clear the error message
                                     necessary, later in the script.
                                                                                                Here's the new
  $error msg = "";
  // If the user isn't logged in, try to log them in Check the user_id cookie to
                                                                                                Log-In form
                                                       - see if the user is logged in.
  if (!isset($ COOKIE['user_id']))
    if (isset($_POST['submit']))
                                                                          If the user isn't logged
      // Connect to the database
                                                                          in, see if they've
      $dbc = mysqli connect(DB HOST, DB USER, DB PASSWORD, DB NAME);
                                                                          submitted log-in data.
      // Grab the user-entered log-in data
                                                                                          The user-entered data
      $user username = mysqli real escape string($dbc, trim($ POST['username']));
                                                                                          now comes from form
      $user password = mysqli real escape string($dbc, trim($ POST['password']));
                                                                                          POST data instead of
      if (!empty($user username) && !empty($user password)) {
                                                                                          an authentication window.
        // Look up the username and password in the database
        $query = "SELECT user id, username FROM mismatch user WHERE username = '$user username' AND " .
          "password = SHA('$user password')";
                                                      Log in the user by setting
        $data = mysqli query($dbc, $query);
                                                      user_id and username cookies.
        if (mysqli num rows($data) == 1) {
          // The log-in is OK so set the user ID and username cookies, and redirect to the home page
          $row = mysqli fetch array($data);
          setcookie('user id', $row['user id']);
          setcookie('username', $row['username']);
          $home url = 'http://' . $ SERVER['HTTP HOST'] . dirname($ SERVER['PHP SELF']) . '/index.php';
          header('Location: ' . $home url);
        else {
           // The username/password are incorrect so set an error message
          $error msg = 'Sorry, you must enter a valid username and password to log in.';
                                                                                               Redirect the user
                                                                                               to the Mismatch
      else {
                                                                                               home page upon a
         // The username/password weren't entered so set an error message
                                                                                               successful log-in.
        $error_msg = 'Sorry, you must enter your username and password to log in.';
                                                                                 Set the error message
2>
                                                                                  variable if anything is
                                                                                  wrong with the log-in data.
<html>
  <title>Mismatch - Log In</title>
                                                                             The Log-In script is now a full
  <link rel="stylesheet" type="text/css" href="style.css" />
</head>
                                                                              web page, so it requires all the
<body>
                                                                              standard HTML elements.
  <h3>Mismatch - Log In</h3>
                    continues on the facing page ...
```

Mismatch - Log In

Username: sidneyk
Password:

Log In

```
<?php
  // If the cookie is empty, show any error message and the log-in form; otherwise confirm the log-in
 if (empty($ COOKIE['user id'])) {
                                                                         If the user still isn't logged
    echo '' . $error msg .
                                                                          in at this point, go ahead
                                                                          and show the error message.
  <form method="post" action="<?php echo $ SERVER['PHP SELF']; ?>">
    <fieldset>
      <legend>Log In</legend>
      <label for="username">Username:</label>
      <input type="text" id="username" name="username"</pre>
       value="<?php if (!empty($user username)) echo $user username; ?>" /><br />
      <label for="password">Password:</label>
                                                                               These two form fields are
      <input type="password" id="password" name="password" />
                                                                               used to enter the username
    </fieldset>
    <input type="submit" value="Log In" name="submit" />
                                                                              and password for logging in
  </form>
              Everything prior to this curly brace is still part of the first if clause.
<?php
                                                                                           If the user is logged in at
  14
                                                                                           this point, just tell them so.
 else {
    // Confirm the successful log in
    echo('You are logged in as ' . $ COOKIE['username'] . '.');
?>
</body>
              Finish the HTML code to complete the Log-In web page.
</html>
```

there are no Dumb Questions

Q: Why is it necessary to store both the user ID and username in cookies?

A: Since both pieces of information uniquely identify a user within the Mismatch user database, you could use either one for the purpose of keeping up with the current user. However, user id is a better (more efficient) user reference with respect to the database because it is a numeric primary key. On the other hand, user id is fairly cryptic and doesn't have any meaning to the user, so username comes in handy for letting the user know they are logged in, such as displaying their name on the page. Since multiple people sometimes share the same computer, it is important to not just let the user know they are logged in, but also who they are logged in as.

Then why not also store the password in a cookie as part of the log-in data?

The password is only important for initially verifying that a user is who they claim to be. Once the password is verified as part of the log-in process, there is no reason to keep it around. Besides, passwords are very sensitive data, so it's a good idea to avoid storing them temporarily if at all possible.

Log-In script is actually inside the if statement? Is that possible?

A: Yes. In fact it's quite common for PHP code to be "broken up" around HTML code, as is the case with the Log-In script. Just because you close a section of PHP code with ?>, doesn't mean the logic of the code is closed. When you open another section of PHP code with <?php, the logic continues right where it left off. In the Log-In script, the HTML form is contained within the first if branch, while the else branch picks up after the form code. Breaking out of PHP code into HTML code like this keeps you from having to generate the form with a bunch of messy echo statements.


Navigating the Mismatch application


The new Log-In script changes the flow of the Mismatch application, requiring a simple menu that appears on the home page (index.php). This menu is important because it provides access to the different major parts of the application, currently the View Profile and Edit Profile pages, as well as the ability for users to log in, sign up, and log out depending on their current log-in state. The fact that the menu changes based on the user's log-in state is significant and is ultimately what gives the menu its power and usefulness.

depending on whether the username cookie is set. This menu appears when a user is not logged in, giving them an opportunity to either log in or sign up. Misma ch - Where opposites attract! Log In Sign Up Latest members: username Dierdre The index php script Jason knows to show the limited menu when it can't find the username cookie.

A different menu is shown

The menu is generated by PHP code within the index.php script, and this code uses the \$_COOKIE superglobal to look up the username cookie and see if the user is logged in or not. The user ID cookie could have also been used, but the username is actually displayed in the menu, so it makes more sense to check for it instead.





Logging out means deleting cookies

Logging out a user involves deleting the two cookies that keep track of the user. This is done by calling the setcookie() function, and passing an expiration date that causes the cookies to get deleted at that time.

```
setcookie('username', 'sidneyk', time() + (60 * 60 * 8));

Together, this expression sets an expiration date that is 8 hours from the current time.
```

This code sets an expiration date 8 hours into the future, which means the cookie will be automatically deleted in 8 hours. But we want to delete a cookie immediately, which requires setting the expiration date to a time in the past. The amount of time into the past isn't terribly important—just pick an arbitrary amount of time, such as an hour, and subtract it from the current time.

```
bO seconds * bO minutes = 3bOO seconds, which is I hour into the past.
```

To delete a cookie, just set its expiration date to a time in the past.



The Log-Out script for Mismatch is missing a few pieces of code. Write the missing code, making sure that the log-in cookies get deleted before the Log-Out page is redirected to the home page.



The Log-Out script for Mismatch is missing a few pieces of code. Write the missing code, making sure that the log-in cookies get deleted before the Log-Out page is redirected to the home page.


```
<?php
                                                                       Only log out a user if they
  // If the user is logged in, delete the cookie to log them out
                                                                     are already logged in.
  if ( isset(f_COOK|E['user_id']) ) {
    // Delete the user ID and username cookies by setting their expirations to an hour ago (3600)
     setcookie('user_id', ', time() - 3600);
                                                   Set each cookie to an hour
                                                                                 Redirect to the
     setcookie ('username', ", time() - 3600);
                                                    in the past so that they
                                                                                 Mismatch home page,
                                                     are deleted by the system.
                                                                                 which is constructed as
                                                                                 an absolute URL.
  // Redirect to the home page
  $home url = 'http://' . $ SERVER['HTTP HOST'] . dirname($ SERVER['PHP SELF']) . ' /index.php
  header('Location: ' . $home url);
                                   A location header results in the browser redirecting to another page.
?>
```




Use cookies to add Log-Out functionality to Mismatch.

Modify the Mismatch scripts so that they use cookies to allows users to log in and out (or download the scripts from the Head First Labs site at www.headfirstlabs.com/books/hfphp. The cookie modifications involve changes to the index.php, login.php, logout.php, editprofile.php, and viewprofile.php scripts. The changes to the latter two scripts are fairly minor, and primarily involve changing \$user_id and \$username global variable references so that they use the \$ COOKIE superglobal instead.

Upload the scripts to your web server, and then open the main Mismatch page (index.php) in a web browser. Take note of the navigation menu, and then click the "Log In" link and log in. Notice how the Log-In script leads you back to the main page, while the menu changes to reflect your logged in status. Now click "Log Out" to blitz the cookies and log out.





Sessions aren't dependent on the client

Cookies are powerful little guys, but they do have their limitations, such as being subject to limitations beyond your control. But what if we didn't have to depend on the browser? What if we could store data directly on the server? **Sessions** do just that, and they allow you to store away individual pieces of information just like with cookies, but the data gets stored on the server instead of the client. This puts session data outside of the browser limitations of cookies.

Store session data

Unlike cookies,
sessions store their
data on the server.

Retrieve session data

Sessions allow you to persistently store small pieces of data on the server, independently of the client.

The browser doesn't factor directly into the storage of session data since everything is stored on the server.



Client web browser

Sessions store data in **session variables**, which are logically equivalent to cookies on the server. When you place data in a session variable using PHP code, it is stored on the server. You can then access the data in the session variable from PHP code, and it remains persistent across multiple pages (scripts). Like with cookies, you can delete a session variable at any time, making it possible to continue to offer a log-out feature with session-based code.



Surely there's a catch, right? Sort of. Unlike cookies, sessions don't offer as much control over how long a session variable stores data. Session variables are **automatically destroyed as soon as a session ends**, which usually coincides with the user shutting down the browser. So even though session variables aren't stored on the browser, they are indirectly affected by the browser since they get deleted when a browser session ends.

Since session data is stored on the server, it is more secure and more reliable than data stored in cookies.

A user can't manually delete session data using their browser, which can be a problem with cookies.

There isn't an expiration date associated with session variables because they are automatically deleted when a session ends.


The life and times of sessions

Sessions are called sessions for a reason—they have a very clear start and finish. Data associated with a session lives and dies according to the lifespan of the session, which you control through PHP code. The only situation where you don't have control of the session life cycle is when the user closes the browser, which results in a session ending, whether you like it or not.

You must tell a session when you're ready to start it up by calling the session start() PHP function.

session_start(); This PHP function starts a session.

The PHP session_start() function starts a session and allows you to begin storing data in session variables.



The session ID isn't destroyed until the session is closed, which happens either when the browser is closed or when you call the session destroy() function.

editprofile.php

This PHP function session_destroy(); ends a session.

The session_destroy() function closes a session.

identifies the session

If you close a session yourself with this function, it doesn't automatically destroy any session variables you've stored. Let's take a closer look at how sessions store data to uncover why this is so.

Keeping up with session data

The cool thing about sessions is that they're very similar to cookies in terms of how you use them. Once you've started a session with a call to session_start(), you can begin setting session variables, such as Mismatch log-in data, with the \$_SESSION superglobal.

\$_SESSION['username'] = 'sidneyk';

The name of the session) variable is used as an index into the \$\frac{1}{2}SESSION superglobal.

The value to be stored is just assigned to the \$\frac{1}{2}SESSION superglobal.

echo('You are logged in as '

Unlike cookies, session variables don't require any kind of special function to set them—you just assign a value to the \$_SESSION superglobal, making sure to use the session variable name as the array index.

What about deleting session variables? Destroying a session via session_destroy() doesn't actually destroy session variables, so you must manually delete your session variables if you want them to be killed prior to the user shutting down the browser (log-outs!). A quick and effective way to destroy all of the variables for a session is to set the \$ SESSION superglobal to an empty array.

\$_SESSION = array();

This code kills all of the session variables in the current session.

But we're not quite done. Sessions can actually use cookies behind the scenes. If the browser allows cookies, a session may possibly set a cookie that temporarily stores the session ID. So to fully close a session via PHP code, you must also delete any cookie that might have been automatically created to store the session ID on the browser. Like any other cookie, you destroy this cookie by setting its expiration to some time in the past. All you need to know is the name of the cookie, which can be found using the session name() function.

if (isset(\$_COOKIE[session_name()])) {
 setcookie(session_name(), '', time() - 3600);
}

First check to see if a session cookie actually exists.

is created and stored on the server.


username = sidneyk


\(\)

\$ SESSION['username'] . '.');

To access the session variable, just use the f_SESSION superglobal and the session variable name.

Session variables are <u>not</u> automatically deleted when a session is destroyed.






Log out with sessions

Logging a user out of Mismatch requires a little more work with sessions than the previous version with its pure usage of cookies. These steps must be taken to successfully log a user out of Mismatch using sessions.

- Delete the session variables.
- Check to see if a session cookie exists, and if so, delete it.
- **3** Destroy the session.
- Redirect the user to the home page.

You don't know for certain if a session cookie is being used without checking.

OK, so this is a bonus step that isn't strictly required to log the user out, but is helpful nonetheless.



The Log-Out script for Mismatch is undergoing an overhaul to use sessions instead of pure cookies for log-in persistence. Write the missing code to "sessionize" the Log-Out script, and then annotate which step of the log-out process it corresponds to.

Sharpen your pencil Solution

The Log-Out script for Mismatch is undergoing an overhaul to use sessions instead of pure cookies for log-in persistence. Write the missing code to "sessionize" the Log-Out script, and then annotate which step of the log-out process it corresponds to.


- Delete the session variables.
- Check to see if a session cookie exists, and if so, delete it.
- (3) Destroy the session.
- (4) Redirect the user to the home page.

```
Even when logging out, you have
                to first start the session in order
                to access the session variables.
 // If the user is logged in, delete the session vars to log them out
                                               Now a session variable is used to check
 session start();
                                               the log-in status instead of a cookie.
 if ( isset($ SESS|ON['user id']) ) {
   // Delete the session vars by clearing the $ SESSION array
                                             To clear out the session variables, assign the
                                             SESSION superglobal an empty array.
   // Delete the session cookie by setting its expiration to an hour ago (3600)
  if (isset($ COOKIE[session name()])) {
      setcookie(session name(), ", time() - 3600);
                                                              , If a session cookie exists, delete it by setting its expiration to an hour ago.
   // Destroy the session
                                   Destroy the session with
    session destroy()
                                   a call to the built-in
                                   session_destroy() function.
 // Redirect to the home page
 $home url = 'http://' . $ SERVER['HTTP HOST'] . dirname($ SERVER['PHP SELF']) . '/index.php';
 header('Location: ' . $home_url);
?>
```



The move from cookies to sessions impacts more than just the Log-Out script. Match the other pieces of the Mismatch application with how they need to change to accommodate sessions.






editprofile.php

No change since the script has no direct dependence on log-in persistence.

Sessions are required to remember who the user is. Call the session_start() function to start the session, and then change \$_COOKIE references to \$_SESSION.

Sessions are required to control the navigation menu. Call the session_start() function to start the session, and then change \$_COOKIE references to \$ SESSION.





BULLET POINTS

- HTTP authentication is handy for restricting access to individual pages, but it doesn't offer a good way to "log out" a user when they're finished accessing a page.
- Cookies let you store small pieces of data on the client (web browser), such as the log-in data for a user.
- All cookies have an expiration date, which can be far into the future or as near as the end of the browser session.
- To delete a cookie, you just set its expiration to a time in the past.
- Sessions offer similar storage as cookies but are stored on the server and, therefore, aren't subject to the same browser limitations, such as cookies being disabled.
- Session variables have a limited lifespan and are always destroyed once a session is over (for example, when the browser is closed).

there are no Dumb Questions

C: The session_start() function gets called in a lot of different places, even after a session has been started. Are multiple sessions being created with each call to session_start()?

A: No. The session_start() function doesn't just start a new session—it also taps into an existing session. So when a script calls session_start(), the function first checks to see if a session already exists by looking for the presence of a session ID. If no session exists, it generates a new session ID and creates the new session. Future calls to session_start() from within the same application will recognize the existing session and use it instead of creating another one.

Q: So how does the session ID get stored? Is that where sessions sometimes use cookies?

A: Yes. Even though session data gets stored on the server and, therefore, gains the benefit of being more secure and outside of the browser's control, there still has to be a mechanism for a script to know about the session data.

This is what the session ID is for—it uniquely identifies a session and the data associated with it. This ID must somehow persist on the client in order for multiple pages to be part of the same session. One way this session ID persistence is carried out is through a cookie, meaning that the ID is stored in a cookie, which is then used to associate a script with a given session.

O: If sessions are dependent on cookies anyway, then what's the big deal about using them instead of cookies?

A: Sessions are not entirely dependent on cookies. It's important to understand that cookies serve as an optimization for preserving the session ID across multiple scripts, not as a necessity. If cookies are disabled, the session ID gets passed from script to script through a URL, similar to how you've seen data passed in a GET request. So sessions can work perfectly fine without cookies. The specifics of how sessions react in response to cookies being disabled are controlled in the php.ini configuration file on the web server via the session. use cookies, session.use only cookies, and session. use trans sid settings.

It still seems strange that sessions could use cookies when the whole point is that sessions are supposed to be better than cookies. What gives?

A: While sessions do offer some clear benefits over cookies in certain scenarios, they don't necessarily have an either/or relationship with cookies. Sessions certainly have the benefit of being stored on the server instead of the client, which makes them more secure and dependable. So if you ever need to store sensitive data persistently, then a session variable would provide more security than a cookie. Sessions are also capable of storing larger amounts of data than cookies. So there are clear advantages to using sessions regardless of whether cookies are available.

For the purposes of Mismatch, sessions offer a convenient server-side solution for storing log-in data. For users who have cookies enabled, sessions provide improved security and reliability while still using cookies as an optimization. And in the case of users who don't have cookies enabled, sessions can still work by passing the session ID through a URL, foregoing cookies altogether.

Complete the session transformation

Even though the different parts of Mismatch affected by sessions use them to accomplish different things, the scripts ultimately require similar changes in making the migration from cookies to sessions. For one, they all must call the session_start() function to get rolling with sessions initially. Beyond that, all of the changes involve moving from the \$_COOKIE superglobal to the \$_SESSION superglobal, which is responsible for storing session variables.



All of the session—powered scripts start out with a call to session_start() to get the session up and running.

```
// If the vs--isn't logged in, try to log them in if (!isset($_SESSION['user_id')) {
  if (isset($ POST['SUDMIL'])) {
    // Connect to the database
    $dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
    // Grab the user-entered log-in data
    $user_username = mysqli_real_escape_string($dbc, trim($_POST['username']));
    $user_password = mysqli_real_escape_string($dbc, trim($_POST['password']));
     if (!empty($user_username) && !empty($user_password)) {
       // Look up the username and password in the database
       $query = "SELECT user_id, username FROM mismatch_user WHERE username = '$user_username' AND " .
          "password = SHA('$user_password')";
        $data = mysqli_query($dbc, $query);
          // The log-in is OK so set the user ID and username session vars, and redirect to the home page
       if (mysqli_num_rows($data) == 1) {
         $row = mysqli fetch array($data);
$ SESSION['user_id'] = $row['user_id'];
         SESSION('USETHAME');
$nome_uff = netp., . $SERVER['HTTP_HOST'] . dirname($_SERVER['PHP_SELF']) . '/index.php';
header('Location: ' . $home_url);
          // The username/password are incorrect so set an error message
          $error_msg = 'Sorry, you must enter a valid username and password to log in.';
```

login.php

The Log-In script uses sessions to remember the user ID and username for log-in persistence, and it does so by relying on the 5_SESSION superglobal instead of 7 COOKIE.

```
// Generate the newigation menu
 if (isset SESSION['username']))
   echo '&#luuu4; <a href="vienprofile.php">View Profile</a><br />';
   echo '❤ <a href="editprofile.php">Edit Profile/
  echo '❤ <a href="logout.php">Log Out (' ($_SESSION['username']
                                                                 ')</a>';
 else (
  echo '❤ <a href="login.php">Log In</a><br />';
  echo '❤ <a href="signup.php">Sign Up</a>';
 \ensuremath{//} Loop through the array of user data, formatting it as \ensuremath{\mathtt{HTML}}
 echo '<h4>Latest members:</h4>';
echo '';
while ($row = mysqli_fetch_array($data)) {
  if (isse ($ SESSION['user_id'])) {
   $row['first_name'] . '</a>';
 else {
   echo '' . $row['first_name'] . '';
echo '';
```

The Mismatch home page uses the f_SESSION superglobal instead of f_COOKIE to access log-in data while generating the menu and choosing whether or not to provide a link to the "latest members" profiles.

Similar to the Log-In and home pages, the Edit Profile script now uses f_SESSION to access log-in data instead of f_COOKIE.

index.php

```
Although not shown,
the View Profile
script uses sessions
in much the same
way as Edit Profile.
```



viewprofile.php

```
sure the user is logged in before going any further.
exit();
else {
 echo('You are logged in as ' . ($_SESSION['username'
    '. <a href="logout.php">Log out</a>.');
    if (!empty($first_name) && !empty($last_name) && !empty($gender) && !empty($birthdate) &&
      !empty($city) && !empty($state)) {
      \ensuremath{//} Only set the picture column if there is a new picture
        $query = "UPDATE mismatch_user SET first_name = '$first_name', last_name = '$last_name', " .
      if (!empty($new_picture)) {
           "gender = '$gender', birthdate = '$birthdate', city = '$city' state = '$state', ".

"picture = '$new_picture' WHERE user_id = '" ($_SESSION['user_id']) "'";
        $query = "UPDATE mismatch_user SET first_name = '$first_name', last_name = '$last_name', "
      else {
           "gender = '$gender', birthate - 'Shirthdate', city = '$city', state = '$state' " .
"WHERE user_id = '" . ($_SESSION['user_id']). "'";
       mysqli_query($dbc, $query);
```

editprofile.php

Fireside Chats

Tonight's talk: Cookie and session variable get down and dirty about who has the best memory



Cookie

There's been a lot of talk around here among us cookies about what exactly goes on over there on the server. Rumor is you're trying to move in on our territory and steal data storage jobs. What gives?

That doesn't make any sense to me. The browser is a perfectly good place to store data, and I'm just the guy to do it.

Uh, well, that's a completely different issue. And if the user decides to disable me, then clearly they don't have any need to store data.

So I suppose your answer is to store the data on the server? How convenient.

Alright, Einstein. Since you seem to have it all figured out, why is it that you still sometimes use me to store your precious little ID on the browser?

Come on now, steal is a strong word. The truth is sometimes it just makes more sense to store data on the server.

What about when the user disables you?

Not true. The user often doesn't even know a web application is storing data because in many cases, it is behind-the-scenes data, like a username. So if you're not available, they're left with nothing.

Exactly. And the cool thing is that the user doesn't have the ability to disable anything on the server, so you don't have to worry about whether or not the data is really able to be stored.

Er, well, most people really don't know about that, so there's no need to get into it here. We can talk about that off the record. The important thing is that I'm always around, ready to store data on the server.

Cookie:

Come on, tell me how much you need me!

Oh I know you can, but the truth is you'd rather not. And maybe deep down you really kinda like me.

Ah, so you're going to resort to picking on the little guy. Sure, I may not be able to store quite as much as you, and I'll admit that living on the client makes me a little less secure. But it sure is more exciting! And I have something you can only dream about.

Well, all that storage space and security you're so proud of comes at a cost... a short lifespan! I didn't want to be the one to have to tell you, but your entire existence is hinging on a single browser session. I think that's how you got your name.

It's simple. I don't die with a session, I just expire. So I can be set to live a long, full life, far beyond the whim of some click-happy web surfer who thinks it's cute to open and close the browser every chance he gets.

Problem is, those same scripters often set my expiration to such a short period that I don't really get to experience the long life I truly deserve. I mean, I...

Session variable:

Alright, I will admit that from time to time I do lean on you a little to help me keep up with things across multiple pages. But I can get by without you if I need to.

Look, I don't have any problem with you. I just wish you were a little more secure. And you have that size limitation. You know, not every piece of persistent data is bite-sized.

Is that so? Do tell.

You mean you can go on living beyond a single session? How is that possible?!

Wow. What a feeling that must be to experience immortality. My only hope is that some slacker scripter accidentally forgets to destroy me when he closes a session... but the browser will still do me in whenever it gets shut down.


Hello? Are you there? Geez, expiration is harsh.



Change Mismatch to use sessions instead of cookies.

Modify the Mismatch scripts so that they use sessions instead of cookies to support log-in persistence (or download the scripts from the Head First Labs site at www.headfirstlabs.com/books/hfphp). The session modifications involve changes to the index.php, login.php, logout.php, editprofile.php, and viewprofile.php scripts, and primarily involve starting the session with a call to the session_start() function and changing \$ COOKIE superglobal references to use \$ SESSION instead.

Upload the scripts to your web server, and then open the main Mismatch page (index.php) in a web browser. Try logging in and out to make sure everything works the same as before. Unless you had cookies disabled earlier, you shouldn't notice any difference—that's a good thing!





Sessions without cookies may not work if your PHP settings in php.ini aren't configured properly on the server.


In order for sessions to work with cookies disabled, there needs to be another mechanism for passing the session ID among different pages. This mechanism involves appending the session ID to the URL of each page, which takes place automatically if the session.use_trans_id setting is set to 1 (true) in the php.ini file on the server. If you don't have the ability to alter this file on your web server, you'll have to manually append the session ID to the URL of session pages if cookies are disabled with code like this:

<a href="viewprofile.php?<?php echo SID; ?>">view your profile

The SID superglobal holds the session ID, which is being passed along through the URL so that the View Profile page knows about the session.

Users aren't feeling welcome

Despite serving as a nice little improvement over cookies, something about the new session-powered Mismatch application isn't quite right. Several users have reported getting logged out of the application despite never clicking the "Log Out" link. The application doesn't exactly feel personal anymore... this is a big problem.





What do you think is causing users to be automatically logged out of Mismatch? Is it something they've done inadvertently?

Sessions are short-lived...

Whether sessions or cookies are The problem with the automatic log-outs in Mismatch has to do with used, logging in is what sets the limited lifespan of sessions. If you recall, sessions only last as long as the persistent wheels in motion. the current browser instance, meaning that all session variables are killed when the user closes the browser application. In other words, closing the browser results in a user being logged out whether they like it or not. This is not only inconvenient, but it's also a bit confusing because we already have a log-out feature. Users assume they aren't logged out unless they've clicked the Log Out link. Logging in with sessions results in the creation of two session variables. user id = 1 Once the session variables are username = sidneyk destroyed, the user is logged out ... whether they like it or not! The session variables are used The session variables to remember the are destroyed along identity of the user. with the session when the browser is closed. The user closes the browser but may not

Even though you can destroy a session when you're finished with it, you can't prolong it beyond a browser instance. So sessions are more of a short-term storage solution than cookies, since cookies have an expiration date that can be set hours, days, months, or even years into the future. Does that mean sessions are inferior to cookies? No, not at all. But it does mean that sessions present a problem if you're trying to remember information beyond a single browser instance... such as log-in data!


Session variables are destroyed when the user ends a session by closing the browser.

realize that they just logged themselves out.

... but cookies can last forever!

Unlike session variables, the lifespan of a cookie isn't tied to a browser instance, so cookies can live on and on, at least until their expiration date arrives. Problem is, users have the ability to destroy all of the cookies stored on their machine with a simple browser setting, so don't get too infatuated with the permanence of cookies—they're still ultimately only intended to store temporary data.

Maybe not forever, but plenty long enough to outlast a session.



Cookies are only destroyed when they expire.

Cookies are destroyed when they expire, giving them a longer lifespan than session variables.

expiration date/time.

So would it make sense to use both sessions and cookies, where cookies help keep users logged in for longer periods of time? It would work for users who have cookies enabled.

As long as you're not dealing with highly sensitive data, in which case, the weak security of cookies would argue for using sessions by themselves.

Yes, it's not wrong to take advantage of the unique assets of both sessions and cookies to make Mismatch log-ins more flexible.

In fact, it can be downright handy. Sessions are better suited for short-term persistence since they share wider support and aren't limited by the browser, while cookies allow you to remember log-in data for a longer period of time. Sure, not everyone will be able to benefit from the cookie improvement, but enough people will that it matters. Any time you can improve the user experience of a significant portion of your user base without detracting from others, it's a win.



Sessions + Cookies = Superior log-in persistence

For the ultimate in log-in persistence, you have to get more creative and combine all of what you've learned in this chapter to take advantage of the benefits of both sessions and cookies. In doing so, you can restructure the Mismatch application so that it excels When a user logs in, both at both short-term and long-term user log-in persistence. session variables and cookies are set to store Start here! the user ID and username. user_id = 1 user_id = 1 time() + 30 days username = sidneyk username = sidneyk time() + 30 days Closing the browser results in the session variables being destroyed, The next time the user but not the cookies. The user opens Mismatch, the cookies closes the are used to recreate the web browser, session variables...voilal killing the session in the process. Poof! The expiration for the cookies is set to 30 days after the initial log-in. user_id = 1 time() + 30 days user id = 1 username = sidneyk username = sidneyk time() + 30 days The log-in data stored in the cookies is used to Rather than keeping users reset the session variable logged in forever, the cookies are destroyed 30 days later.

Dumb Questions

Q: So is short-term vs. long-term persistence the reason to choose between sessions and cookies?

A: No. This happened to be the strategy that helped guide the design of the Mismatch application, but every application is different, and there are other aspects of sessions and cookies that often must be weighed. For example, the data stored in a session is more secure than the data stored in a cookie. So even if cookies are enabled and a cookie is being used solely to keep track of the session ID, the actual data stored in the session is more secure than if it was being stored directly in a cookie. The reason is because session data is stored on the server, making it very difficult for unprivileged users to access it. So if you're dealing with data that must be secure, sessions get the nod over cookies.

Q: What about the size of data? Does that play a role?

A: Yes. The size of the data matters as well. Sessions are capable of storing larger pieces of data than cookies, so that's another reason to lean toward sessions if you have the need to store data beyond a few simple text strings. Of course, a MySQL database is even better for storing large pieces of data, so make sure you don't get carried away even when working with sessions.

Q: So why would I choose a session or cookie over a MySQL database?

A: Convenience. It takes much more effort to store data in a database, and don't forget that databases are ideally suited for holding **permanent** data. Log-in data really isn't all that permanent in the grand scheme of things. That's where cookies and sessions enter the picture—they're better for data that you need to remember for a little while and then throw away.



. . .

The Mismatch application has been redesigned to PHP Magnets use both sessions and cookies for the ultimate in user log-in persistence. Problem is, some of the code is missing. Use the session and cookie magnets to add back the missing code.



```
if (mysqli num rows($data) == 1) {
                     ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} ^{-} 
                      // and redirect to the home page
                      $row = mysqli fetch array($data);
                                              ['user_id'] = $row['user_id'];
                    ['username'] = $row['username'];
                      setcookie('user_id', $row['user_id'], time() + (60 * 60 * 24 * 30)); // expires in 30 days
                      setcookie('username', $row['username'], time() + (60 * 60 * 24 * 30)); // expires in 30 days
                    $home_url = 'http://' . $_SERVER['HTTP_HOST'] . dirname($_SERVER['PHP_SELF']) . '/index.php';
header('Location: ' . $home_url);
                    }
<?php
 ^{-}// If the user is logged in, delete the session vars to log them out
                                                                                                                                                                                      login.php
 session start();
if (isset(____['user_id'])) {
   // Delete the session vars by clearing the \ SESSION array
   ..... = array();
   // Delete the session cookie by setting its expiration to an hour ago (3600)
   setcookie(session name(), '', time() - 3600);
                                                                                                                                                                    logout.php
  // Destroy the session
  session destroy();
// Delete the user ID and username cookies by setting their expirations to an hour ago (3600)
setcookie('user id', '', time() - 3600);
                                                                                                                                                                                     $ SESSION
setcookie('username', '', time() - 3600);
                                                                                                                                                                                 $ SESSION
   <?php
      session start();
                                                                                                                                                                                     $ SESSION
     // If the session vars aren't set, try to set them with a cookie
                                                                                                                                                                              $ SESSION
                                                   ['user_id'])) {
                                                                                                                                                                                     $ SESSION
      if (!isset(
                                                     $ SESSION
        if (isset(
                                                                                                                                                                                    $ SESSION
                                                                                        ['user id'];
                                      ['user id'] =
                                                                                                                                                           index.php
                                                                                           ['username'];
                                  ['username'] =
         } .....
      }
                                                                                                                                                                                       411
                                                                                                                                                                      ere )
     ?>
```



PHP Magnets Solution

The Mismatch application has been redesigned to use both sessions and cookies for the ultimate in user log-in persistence. Problem is, some of the code is missing. Use the session and cookie magnets to add back the missing code.

```
if (mysqli_num_rows($data) == 1) {
             ^{\prime\prime} The log-in is OK so set the user ID and username session vars (and cookies),
             // and redirect to the home page
             $row = mysqli_fetch_array($data);
                                                                      The new cookies are
                                                                      set in addition to
                          ['user_id'] = $row['user_id'];
             $ SESSION
                                                                     the session variables.
                           ['username'] = $row['username'];
              $ SESSION
             setcookie('user_id', $row['user_id'], time() + (60 * 60 * 24 * 30)); // expires in 30 days
             setcookie('username', $row['username'], time() + (60 * 60 * 24 * 30)); // expires in 30 days
             $home_url = 'http://' . $_SERVER['HTTP_HOST'] . dirname($_SERVER['PHP_SELF']) . '/index.php';
             header('Location: ' . $home url);
<?php
 // If the user is logged in, delete the session vars to log them out
                                                                                                         login.php
 session start();
             $ SESSION
 if (isset.(
                            'user id'])) {
  // Delete the session vars by clearing the _{ssssssss}
     $ SESSION
                  = array();
  // Delete the session cookie by setting its expiration to an hour ago (3600)
               $ COOKIE
  if (isset(
                            [session name()])) {
                                                           Logging out now
   setcookie(session name(), '', time() - 3600);
                                                           requires deleting both
                                                                                               logout.php
                                                           the session cookie and
  // Destroy the session
                                                           the new log-in cookies.
 session destroy();
// Delete the user ID and username cookies by setting their expirations to an hour ago (3600)
setcookie('user id', '', time() - 3600);
setcookie('username', '', time() - 3600);
                                                                                    If the user isn't logged in
                  <?php
                                                                                    via the session, check to
                   session start();
                   // If the session wars aren't set, try to set them with a cookie see if the cookies are set.
                                                user id']))
                   if (!isset(
                                 $ SESSION
                                                                                         'username']))
                                                ['user_id']) && isset(
                                                                           $ COOKIE
                     if (isset(
                                   $ COOKIE
                                                                     'user_id'];
                                                        $ COOKIE
                          S SESSION
                                                                                                          index.php
                                                                      ['username'];
                                        'username']
                                                         $ COOKIE
                                                                                  This same cookie/session code
                          $ SESSION
                                                                                  must also go in editprofile.php
                                            Set the session variables
      Chapter 7
                                                                                  and viewprofile.php.
                   ?>
                                            using the cookies.
```



Change Mismatch to use both sessions and cookies.

Modify the Mismatch scripts so that they use both sessions and cookies to support log-in persistence (or download the scripts from the Head First Labs site at www.headfirstlabs.com/books/hfphp. This requires changes to the index.php, login.php, logout.php, editprofile.php, and viewprofile.php scripts.

Upload the scripts to your web server, and then open the main Mismatch page (index. php) in a web browser. Try logging in and then closing the web browser, which will cause the session variables to get destroyed. Re-open the main page and check to see if you're still logged in—cookies make this possible since they persist beyond a given browser session.



Your PHP & MySQL Toolbox

You've covered quite a bit of new territory in building a user management system as part of the Mismatch application. Let's recap some of the highlights.

setcookie()

This built—in PHP function is used to set a cookie on the browser, including an optional expiration date, after which the cookie is destroyed. If no expiration is provided, the cookie is deleted when the browser is closed.

\$_COOKIE

This built—in PHP superglobal is used to access cookie data. It is an array, and each cookie is stored as an entry in the array. So accessing a cookie value involves specifying the name of the cookie as the array index.

SHA (value)

This MySQL function encrypts a piece of text, resulting in a string of 40 hexadecimal characters. This function provides a great way to encrypt data that needs to remain unrecognizable within the database. It is a one-way encryption, however, meaning that there is no "decrypt" function.

session_destroy()

This built—in PHP function closes a session, and should be called when you're finished with a particular session. This function does not destroy session variables; however, so it's important to manually clean those up by clearing out the f_SESSION superglobal.

session_start()

This built—in PHP function starts a new session or re-starts a pre-existing session. You must call this function prior to accessing any session variables.

\$ SESSION

This built—in PHP superglobal is used to access session data. It is an array, and each session variable is stored as an entry in the array. So accessing the value of a session variable involves specifying the name of the variable as the array index.



Several pieces of code from the Mismatch application have been pulled out, and we can't remember what they do. Draw lines connecting each piece of code with what it does.

PHP/MySQL Code

Description


| empty(\$_COOKIE['user_id']) | Use a session variable to determine if a user is logged in or not. |
|--|--|
| <pre>setcookie(session_name(), '', time() - 3600);</pre> | Use a cookie to determine if a user is logged in or not. |
| SHA('\$user_password') | Destroy a session cookie by setting its expiration to an hour in the past. |
| session_destroy() | Encrypt a user's password into an unrecognizable format. |
| setcookie('user_id', \$row['user_id']) | Store a user's unique ID in a cookie. |
| <pre>\$_SESSION = array()</pre> | Start a new session. |
| session_start() | Close the current session. |
| isset(\$_SESSION['user_id']) | Destroy all session variables. |



Several pieces of code from the Mismatch application have been pulled out, and we can't remember what they do. Draw lines connecting each piece of code with what it does.

PHP/MySQL Code

Description



7 1/2 eliminate duplicate code





Sharing is caring

It's really quite simple, darling. By sharing one umbrella, we eliminate the need for two umbrellas, we both still stay dry... and you get to latch on to one handsome fella.




Umbrellas aren't the only thing that can be shared. In any web application you're bound to run into situations where the same code is duplicated in more than one place. Not only is this wasteful, but it leads to maintenance headaches since you will inevitably have to make changes, and these changes will have to be carried out in multiple places. The solution is to eliminate duplicate code by sharing it. In other words, you stick the duplicate code in one place, and then just reference that single copy wherever you need it. Eliminating duplicate code results in applications that are more efficient, easier to maintain, and ultimately more robust.


this is a new chapter

417



The Mismatch application has evolved since you last saw it, with improved navigation and a more consistent look and feel. But these improvements have come at a cost... duplicate code. Just by looking at the pages themselves, see if you can figure out what parts of Mismatch might represent a duplicate code problem. Circle and annotate these application parts, and also write down anything not visible that you think might also have code duplication issues.





Mismatch - Edit Profile

Home View Profile Edit Profile Log Out (inceles)

Personal Information

First Johan
name: Last Nertins
name: Gender: Male 12


Birthdate: 1981-11-03

City: Athers
State: GA
Picture: Choose #Ne Johange 1898

Save Profile

Copyright © 2009 Mismatch Baterprises, Inc.

editprofile.php




Mismatch is in pieces

So the Mismatch application has some common elements that are duplicated in the main script files at the moment. Why is this a big deal? Because it makes the application difficult to maintain. What happens if you decide to add a new page that requires a new menu item? You have to go through and change the menu code in every script file to show the new menu item. The same thing applies to the copyright notice.

The solution to the problem is to only store any given piece of information once. Then if that code ever needs to change, you only change it in one place. With that in mind, it's possible to rethink the organization of Mismatch in terms of reusable script components.

The page header



The header.php script contains the title of the page, which references a variable to present a different title on each page. The header also includes standard HTML boilerplate code and takes care of chores such as linking in the CSS style sheet.

This component doesn't result in visible HTML code, but it plays a vital role in managing user log-ins throughout the Mismatch application.

The navigation menu



navmenu.php

The navmenu.php script generates a navigation menu for the application based on whether the user is logged in or not. The navigation menu presents "Log In" or "Log Out" links as needed.

The session starter



The startsession.php script is responsible for starting the session and checking to see if the user is logged in.

startsession.php

The page footer



footer.php


The footer.php script displays a copyright notice for the application and closes the HTML tags opened in the header. So the header and footer work as a pair that must always be used together.

Rebuilding Mismatch from a template

OK, so we break apart Mismatch into multiple scripts, but how do we put them back together? You're already familiar with how include files work, and those are part of the solution. But you have to think larger than include files... you have to think in terms of **templates**, which allow you to build a single page as a combination of multiple include files. A template is like a blueprint for a page within an application where everything but what is truly unique to that page comes from include files.

The template version of Mismatch involves breaking apart common code into scripts that each play a very specific role, some responsible for generating visual HTML code, some not. The idea is to distill as much common functionality as possible into template include files, and then only leave code in each application page that is completely unique to that page. Templates allow a PHP application to be built out of reusable script components.

The header appears at the top of every Mismatch page, and displays the application title as well as a page-specific title.



Dumb Questions

Q: What is a template exactly? Isn't it just a bunch of include files?

A: Yes. A template is a collection of include files, but it's a collection designed specifically to separate an application into functional components. The goal is to reduce a page down to what is truly unique about that page, and only that page. So headers, footers, navigation menus, and any other application pieces and parts that are the same or similar among more than one page are ideal for inclusion in an application template. The end result is that you place template code in PHP include files that are referenced by other scripts that need them.

You can think of a template as a group of include files that go a step or two beyond just reducing duplicate code—they actually help organize the functionality of an application. Mismatch is a fairly simple example of how to employ templates—larger, more complex PHP applications often employ very sophisticated template systems.

Q: Doesn't template code have to be exactly the same in order to be shared across multiple scripts?

A: No It's perfectly acceptable for template code to just be similar, not exact. The reason is because you can use variables to allow for some degree of customization as a template is applied to different pages. The page title in Mismatch is a perfect example of this. The page header template is similar in every page in that it has a title that always begins with "Mismatch - ." But the specific title is different, which is why a variable is needed to provide a means of varying the title slightly among different pages.

424

Chapter 7 1/2

Rebuild Mismatch with templates

The design work involved in breaking an application into template scripts is usually worth the effort. You end up with a collection of tightly focused, Try to reset the bite-size scripts, as well as dramatically simplified code in the main session variables application script files that are now dependent on the template scripts. with cookies if they aren't set <?php session_start(); // If the session wars aren't set, try to set them with a cookie Start the if (!isset(\$_SESSION['user_id'])) (if (isset(\$_COOKIE['user_id']) && isset(\$_COOKIE['username'])) { session. \$_SESSION['user_id'] = \$_COOKIE['user_id']; \$ SESSION['username'] = \$ COOKIE['username']; Link in the application ?> style sheet. startsession.php <!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN" Start the official HTML "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd"> code with a DOCTYPE <html xmlns="http://www.w3.org/1999/xhtml" xml:lang="en" lang="en"> and an <html> tag. <meta http-equiv="Content-Type" content="text/html; charset=uti-8" /> <?php echo '<title>Mismatch - ' . Spage_title . '</title>'; Build a custom page title using the spage title k rel="stylesheet" type="text/css" href="style.css" /> variable, which is provided by </head> <body> the script including this file. <?php echo '<h3>Mismatch - ' . \$page title . '</h3>'; // Generate the navigation menu echo '<hr />'; header.php if (isset(\$_SESSION('username'])) { echo 'Home ❤ '; echo 'View Profile ❤ '; echo 'Edit Profile ❤ '; echo 'Log Out (' . \$_SESSION['username'] . ')'; else (echo 'Log In ❤ '; echo 'Sign Up'; Display a copyright echo '<hr />'; notice and wrap up the HTML code. navmenu.php See if the user is logged in, and then Copyright ©2008 Mismatch Enterprises, Inc. generate the appropriate </body> </html> navigation menu.


footer.php

The startsession.php script must be The spage_title variable included first so that the session is determines the title of started and the remainder of the the page that is displayed script has access to session data. within the page header. 7 Start the session require once ('startsession.php'); The connection variables and application variables are / Insert the page header still included from separate \$page title = 'Where opposites attract!', sequire once ('header.php'); script files like before require_once('appvars.php'); < The navigation menu is generated require once ('connectvars.php'); after the header but before the // Show the navigation menu body of the page. require once ('navmenu.php' / Connect to the database \$dbc = mysqli connect (DB HOST, DB USER, DB PASSWORD, DB NAME); // Retrieve the user data from MySQL Squery = "SELECT user_id, first_name, picture FROM mismatch user WHERE first name IS NOT NULL" "ORDER BY join date DESC LIMIT 5"; \$data = mysqli query(\$dbc, \$query); // Loop through the array of user data, formatting it as HTML echo '<h4>Latest members:</h4>'; echo ''; while (\$row = mysqli fetch array(\$data)) [if (is_file(MM_UPLOADPATH.\$row['picture']) && filesize(MM_UPLOADPATH.\$row['picture']) > 0) (echo ''; else (echo '"; if (isset(\$ SESSION['user id'])) (echo '' . \$row['first name'] ''; else { echo''.\$row['first name'].''; The non-template code is now echo '': truly unique to the page, so there's much less of it. mysqli close (\$dbc); The footer finishes up the page, and must appear last since it closes up the HTML tags. // Insert the page footer require once ('footer.php');

index.php

425

much Mismatch is whole again... and better organized



426 Chapter 7 1/2

8 control your data, control your world






There's nothing like a good fall data harvest. An abundance of information ready to be examined, sorted, compared, combined, and generally made to do whatever it is your killer web app needs it to do. Fulfilling? Yes. But like real harvesting, taking control of data in a MySQL database requires some hard work and a fair amount of expertise. Web users demand more than tired old wilted data that's dull and unengaging. They want data that enriches... data that fulfills... data that's relevant. So what are you waiting for? Fire up your MySQL tractor and get to work!

this is a new chapter

427


Making the perfect mismatch

The Mismatch application has a growing database of registered users but they're ready to see some results. We need to allow users to find their ideal opposite by comparing their loves and hates against other users and looking for mismatches. For every love mismatched against a hate, a couple is that much closer to being the perfect mismatch.




Mismatching is all about the data

In order to carry out Mismatches between users, we must first figure out how to organize the data that keeps up with what they love and hate. Knowing that it's going to be stored in a MySQL database isn't enough. We need to organize these love/hate topics so that they are more manageable, allowing users to respond to related topics, indicating whether they love or hate each one.




Break down the Mismatch data

Coming up with a data model for an application such as Mismatch is an extremely important step, as it controls an awful lot about how the application is constructed. In the case of Mismatch, we can break down its data needs into three interrelated pieces of data.



How exactly does this data lead to a mismatch between two users? We compare responses that users have made on each topic. For example, since Sidney and Johan have opposite responses to the topic "Horror movies," we have a successful mismatch on that particular topic. Figuring the best overall mismatch for a given user involves finding the user who has the most mismatched topics with them.



A description of the


data (the tables and

database, along with

columns) in your


Model a database with a schema


In order to translate the data requirements of the Mismatch application into an actual database design, we need a schema. A **schema** is a representation of all the structures, such as tables and columns, in your database, along with how they connect. Creating a visual depiction of your database can help you see how things connect when you're writing your queries, not to mention which specific columns are responsible for doing the connecting. As an example, let's take a look at the schema for the original Mismatch database from the previous chapter, which consists of only a single table, mismatch user.



This way of looking at the structure of a table is a bit different than what you've seen up until now. Tables have normally been depicted with the column names across the top and the data below. That's a great way to look at individual tables and tables populated with data, but it's not very practical when we want to create a structural diagram of multiple tables and how they relate to one another. And Mismatch is already in need of multiple tables...

Creating a diagram of a table lets you keep the design of the table separate from the data that's inside of it.







433



The Mismatch database is in need of storage for user responses to love/hate topics, as well as the topic names and their respective categories. Here are three different database designs for incorporating categories, topics, and responses into the Mismatch database. Circle the schema that you think makes the most sense, and annotate why.



434 Chapter 8




Wire together multiple tables

Connecting tables together to form a cohesive system of data involves the use of **keys**. We've used **primary keys** to provide a unique identifier for data within a table, but we now need **foreign keys** to link a row in one table to a row in another table. A foreign key in a table references the primary key of another table, establishing a connection between the two tables that can be used in queries.

The Mismatch schema from the previous exercise relies on a pair of foreign keys in the mismatch_response table to connect response rows to user and topic rows in other tables.

A foreign key is a column in a table that references the primary key of another table.





Without foreign keys, it would be very difficult to associate data from one table with data in another table. And spreading data out across multiple tables is how we're able to eliminate duplicate data and arrive at an efficient database. So foreign keys play an important role in all but the most simplistic of database schemas. Large arrows show †______ primary keys connecting to foreign keys to wire together tables.

436 Chapter 8

Foreign keys in action

It often helps to visualize data flowing into tables and connecting tables to one another through primary and foreign keys. Taking a closer look at the Mismatch tables with some actual data in them helps to reveal how primary keys and foreign keys relate to one another.





I understand that primary keys and foreign keys connect multiple tables together, but does the direction of the arrows between keys in those diagrams mean anything?


Yes, the direction of the arrows tells us how rows in each table relate to each other.


More specifically, they tell us how many rows in one table can have matching rows in another table, and vice-versa. This is a critical aspect of database schema design, and involves three different possible patterns of data: one-to-one, one-to-many, and many-to-many.

Tables can match row for row

The first pattern, **one-to-one**, states that a row in Table A can have at most ONE matching row in Table B, and vice-versa. So there is only one match in each table for each row.

As an example, let's say the Mismatch user table was separated into two tables, one for just the log-in information (Table A) and one with profile data (Table B). Both tables contain a user ID to keep users connected to their profiles. The user_id column in the log-in table is a primary key that ensures user log-in uniqueness. user_id in the profile table is a foreign key, and plays a different role since its job is just to connect a profile with a log-in.





With respect to the two user_id columns, the log-in table is considered a **parent** table, while the profile table is considered a **child** table—a table with a primary key has a parent-child relationship to the table with the corresponding foreign key.


438 Chapter 8

Table A Table B Many of these rows Table B MANY of these rows

One row leads to many

One-to-many means that a row in Table A can have **many** matching rows in Table B, but a row in Table B can only match **one** row in Table A. The direction of the arrow in the table diagram always points **from** the table with one row **to** the table with many rows.


Using the Mismatch database again, the current schema already takes advantage of a one-to-many data pattern. Since a user is capable of having many topic responses (love tattoos, hate hiking, etc.), there is a one-to-many relationship between user rows and response rows. The user_id column connects these two tables, as a primary key in mismatch user and a foreign key in mismatch response.



One-to-One:
exactly one
row of a
parent table
is related to
one row of
a child table.

How do I know whether rows in two tables should have a one-to-one or one-to-many relationship?

A: There will be a tendency to use one-to-many patterns much more often than one-to-one, and rightly so. It's common to have a main (parent) table containing primary data, such as users in Mismatch, that connects to a secondary (child) table in a one-to-many arrangement. This happens twice in the Mismatch schema, where both users and topics have a one-to-many relationship to responses. In many cases, rows with a one-to-one relationship in two tables can be combined into the same table However, there are certainly situations where it makes sense to go with a one-to-one pattern, such as the hypothetical user profile example on the facing page, where there is a security motivation in moving a portion of the data into its own table.




One-to-Many:
exactly one row
of a parent
table is related
to multiple
rows of a
child table.


you are here >

439

Matching rows many-to-many

The third and final table row relationship data pattern is the **many-to-many** relationship, which has multiple rows of data in Table A matching up with multiple rows in Table B... it's kinda like data overload! Not really. There are plenty of situations where a many-to-many pattern is warranted. Mismatch, perhaps? Let's have a look.






The many-to-many pattern in Mismatch is indirect, meaning that it takes place through the mismatch_response table. But the pattern still exists. Just look at how many of the same user_ids and topic_ids appear in mismatch_response.

In addition to holding the response data, the mismatch_response table is acting as what's known as a **junction table** by serving as a convenient go-between for the users and topics. Without the junction table, we would have lots of duplicate data, which is a bad thing. If you aren't convinced, turn back to the schema exercise near the beginning of the chapter and take a closer look at Design 2. In that design, the mismatch_topic table is folded into the mismatch_response table, resulting in lots of duplicate data.

Many-to-Many: Multiple rows of a parent table are related to multiple rows of a child table.

440 Chapter 8

MANUE THAT RELATION In each of the tables below, there are circled columns that could be moved out into their own tables. Write down if each of the columns is best represented by a one-to-one, one-to-many, or many-to-many relationship with its original table, and then draw the relationship as a line connecting the two tables with appropriate arrowheads. RISLATTIONSHIP address user mismatch_user user_id O address employer user employer friends friend USER category topic mismatch_topic topic_id O name category *************






Hold it right there! Take a second to get the Mismatch database in order so that we can make mismatches.

Download the .sql files for the Mismatch application from the Head First Labs web site at www.headfirstlabs.com/books/hfphp. These files contain SQL statements that build the necessary Mismatch tables: mismatch_user, mismatch_topic, and mismatch_response. Make sure to run the statement in each of the .sql files in a MySQL tool so that you have the initial Mismatch tables to get started with.

When all that's done, run a DESCRIBE statement on each of the new tables (mismatch_topic and mismatch_response) to double-check their structures. These tables factor heavily into the Mismatch PHP scripts we're about to put together.



OK, so we have this wonderfully designed database of users, categories, topics, and responses. How is that going to actually help us make a mismatch?

05



mismatch topic

| topic_id O | name | category |
|------------|--------------------------------------|---------------|
| 1 | Tattoos | Appearance |
| 2 | Gold chains | Appearance |
| 3 | Body piercings | Appearance |
| 4 | Cowboy boots | Appearance |
| 5 | Long hair | Appearance |
| 6 | Reality TV | Entertainment |
| 7 | Professional wrestling | Entertainment |
| 8 | Horror movies | Entertainment |
| 9 | Easy listening music | Entertinment |
| 10 | The opera | Entertainmen |
| 11 | Sushi | Food |
| 12 | Spam | Food |
| 13 | Spicy food | Food |
| 14 | Peanut butter & banana sandwiches | Food |
| 15 | Martinis | Food |
| 16 | Howard Stern | People |
| 17 | Bill Gates | Peopel |
| 18 | Barbara Streisand | People |
| 19 | Hugh Hefner | People |
| 20 | Martha Stewart | People |
| 21 | Yoga | Activities |
| 22 | Weightlifting | Activities |
| 23 | Cube puzzles | Activities |
| 24 | Karaoke | Activities |
| 25 | Hiking | Activities |

If you start with a well-designed database, every other piece of the application puzzle becomes that much easier to build and assemble.

Getting the database right when initially designing an application is perhaps the best thing you can do to make the development process run smoothly. It may seem like a lot of work up front plotting and scheming about how best to store the data, but it will pay off in the long run. Think about how much more difficult it would be to rework the Mismatch database schema with it full of data.

That's the big picture benefit of a good database design. Looking at the Mismatch database specifically, we have a user table that is populated by the users themselves through sign-ups and profile edits, and we have a new topic table that contains enough categories and topics to give some decent insight into a person. What we're still missing to make mismatches is a way to allow the user to enter responses, and then store them away in the response table.



The full mismatch_topic table contains 25 topics broken up across 5 categories...it's our "5 dimensions of opposability!"




How would you turn this list of categories and topics into a set of questions that users can provide love/hate responses to?

444

Build a Mismatch questionnaire

So how exactly do we get love/hate responses from users for each Mismatch topic? The answer is a questionnaire form that allows the user to choose "Love" or "Hate" for each topic in the mismatch_topic table. This form can be generated directly from the responses in the database, with its results getting stored back in the database. In fact, the design of the questionnaire form involves reading and writing responses from and to the mismatch_response table. Here's a peek at the questionnaire, along with the steps involved in building it.





Use INSERT to add empty response rows to the database the first time the user accesses the form.

We're going to generate the questionnaire form from data in the mismatch_response table, even when the user has never entered any responses. This means we need to "seed" the mismatch_response table with empty responses the first time a user accesses the questionnaire. Since the response column for these rows is empty, neither the "Love" or "Hate" radio buttons are checked when the form is first presented to the user.



Use UPDATE to change response rows based on user responses on the form.

When users submit the questionnaire form, we must commit their personal responses to the database. Even then, only responses with checked radio buttons should be updated. In other words, the database only needs to know about the responses that **have** been answered.



Use SELECT to retrieve the response data required to generate the questionnaire form.

In order to generate the questionnaire form, we need all of the responses for the logged-in user. Not only that, but we need to look up the topic and category name for each response so that they can be displayed in the form—these names are stored in the mismatch_topic table, not mismatch_response.




Generate the HTML questionnaire form from response data.

With the response data in hand, we can generate the HTML questionnaire form as a bunch of input fields, making sure to check the appropriate "Love" or "Hate" radio buttons based on the user responses.


445

Get responses into the database

Although it might seem as if we should start out by generating the questionnaire form, the form's dependent on response data existing in the mismatch_response table. So first things first: we need to "seed" the mismatch_response table with rows of unanswered responses the first time a user accesses the questionnaire. This will allow us to generate the questionnaire form from the mismatch_response table without having to worry about whether the user has actually made any responses.



So from the perspective of the questionnaire form, there's always a row of data in the mismatch_response table for each question in the form. This means that when the user submits the questionnaire form, we just update the rows of data for each response in the form.





PHP & MySQL Magnets

The following code takes care of inserting empty responses into the mismatch_response table the first time a user visits the questionnaire form. It also updates the responses when the user makes changes and submits the form. Unfortunately, some of the code has fallen off and needs to be replaced. Use the magnets to fix the missing code.

```
// If this user has never answered the questionnaire, insert empty responses into the database
$query = "SELECT * FROM mismatch_response WHERE user_id = '" . $_SESSION['user_id'] . "'";
$data = mysqli_query($dbc, $query);
if (_____($data) == 0) (
 // First grab the list of topic IDs from the topic table
  $data = mysqli_query($dbc, $query);
  StopicIDs = array();
  while ($row = mysqli_fetch_array($data)) {
   array push ($topicIDs, $row['topic_id']);
  // Insert empty response rows into the response table, one per topic
  foreach ($topicIDs as $topic_id) {
    $query = ".....mismatch_response ".
     "( _____, VALUES ('" , $_SESSION['user_id']. "', '$topic_id')";
    mysqli_query($dbc, $query);
 // If the questionnaire form has been submitted, write the form responses to the database
 if (isset($_POST['submit'])) (
  // Write the questionnaire response rows to the response table
  foreach ($_POST as $response_id => $response) {
    "WHERE _____ = '$response_id'";
    mysqli_query($dbc, $query);
   echo 'Your responses have been saved.';
```

```
user id INSERT INTO mysqli_num_rows SET response_id topic_id
```



PHP & MySQL Magnets


The following code takes care of inserting empty responses into the mismatch_response table the first time a user visits the questionnaire form. It also updates the responses when the user makes changes and submits the form. Unfortunately, some of the code has fallen off and needs to be replaced. Use the magnets to fix the missing code.

```
// If this user has never answered the questionnaire, insert empty responses into the database
Squery = "SELECT * FROM mismatch_response WHERE user_id = '" , $_SESSION['user_id'] . "'";
$data = mysqli_query($dbc, $query);
                                                            Check to see if the query returned O rows of data... no data!
                            ($data) == 0) (
        mysqli num rows
  // First grab the list of topic IDs from the topic table
                                   FROM mismatch_topic ORDER BY category_id, topic_id";
  Squery = "SELECT
                        topic id
                                                        In order to generate an empty array of responses, we first need to grab all of
  $data = mysqli_query($dbc, $query);
  StopicIDs = array();
  while ($row = mysqli_fetch_array($data)) {
                                                          the topics in the topic table.
    array_push($topicIDs, $row['topic_id']);
                                                                                The response row is
                                                                                "unanswered" at this point
   // Insert empty response rows into the response table, one per topic
                                                                                since the user hasn't
   foreach ($topicIDs as $topic_id) {
                                                                                actually chosen "love" or
                                                                               "hate" on the form yet
                                    mismatch_response "
                    INSERT INTO
     Squery =
                                         ) VALUES ('" . $_SESSION['user_id']. "', '$topic_id')";
                             topic id
             user id
     mysqli_query($dbc, $query)
 // If the questionnaire form has been submitted, write the form responses to the database
 if (isset($_POST['submit'])) (
   // Write the questionnaire response rows to the response table
   foreach ($_POST as $response_id => $response) (
                                                               response = '$response' " .
                                 mismatch response
     $query = "
                     UPDATE
                                    '$response_id'";
                                                                      All that changes when
        "WHERE
                  response id
                                                                       the user submits the form
     mysqli_query($dbc, $query);
                                                                       is the response column
   echo 'Your responses have been saved.';
                                                                       of the response table, so
                                                                       that's all we update.
```

Dumb Questions

Q: What's the deal with the array_push () function? I don't think we've used that one before.


A: We haven't. And that's because we haven't needed to build an array dynamically one element at a time. The array_push() function tacks a new element onto the end of an array, causing the array to grow by one. In the Mismatch code on the facing page, we're using array_push() to build an array of topic IDs from the mismatch_topic table. This array is then used to insert blank responses into the mismatch response table... one for each topic.



We can drive a form with data


It's nothing new that web forms are used to retrieve data from users via text fields, selection lists, radio buttons, etc., but it may not be all that obvious that you can generate HTML forms from database data using PHP. The idea with Mismatch is to dynamically generate an HTML questionnaire form from response data. The Mismatch questionnaire script makes the assumption that response data already exists, which allows it to generate the form from data in the mismatch_response table. We know this assumption is a safe one because we just wrote the code to add empty responses the first time a user visits the form.

Data-driven forms rely on data in a MySQL database to generate HTML form fields.






The Mismatch response questionnaire is generated from user responses that are stored in the mismatch_response table. In order to generate the code for the HTML form, it's necessary to read these responses, making sure to look up the name of the topic and category for each response from the mismatch_topic table. The following code builds an array of responses with topics and categories by performing two queries: the first query grabs the responses for a user, while the second query looks up the topic and category name for each response. Problem is, some of the code is missing... fill in the blanks to get it working!



```
// Grab the response data from the database to generate the form
           Squery = "SELECT response id, topic id, response FROM mismatch response " .
             "WHERE user id = '" . $ SESSION['user id'] . "'";
           $data = mysqli query($dbc, $query);
           $responses = array();
           while ($row = mysqli fetch array($data)) {
             // Look up the topic name for the response from the topic table
             This PHP -
            $\data2 = mysqli_query($dbc, ____);
function tells
             if (mysqli_num_rows(_____) == 1) {
you how many
               $row2 = mysqli_fetch_array($data2);
rows of data
              $row['topic_name'] =
$row['category_name'] =
array_push($responses, $row);
were returned as
query results.
```



Is the user response actually stored as text in the database, as in "Love" and "Hate"? If so, isn't that inefficient?



No and Yes, which is why it is important to use the most efficient data type possible to store data in a MySQL database.

When you think about it, a Mismatch response is more like a true/false answer because it's always either one value (love) or another one (hate). Actually, a third value (unknown) can be useful in letting the application know when the user has yet to respond to a particular topic. So we really need to keep track of three possible values for any given response. This kind of storage problem is ideal for a number, such as a TINYINT. Then you just use different numeric values to represent each possible response.

Minimizing the storage requirements of data is an important part of database design, and in this case a subtle but important part of the Mismatch application. These numeric responses play a direct role in the generation of form fields for the Mismatch questionnaire.



Don't worry about the "Hate" radio buttons for now - they're-generated exactly the same way.

The following code loops through the Mismatch response array that you just created, generating an HTML form field for each "Love" radio button. Fill in the missing code so that the form field is initially checked if the response is set to love (1). Also, make sure the value of the <input> tag is set accordingly.

Sharpen your pencil Solution

The following code loops through the Mismatch response array that you just created, generating an HTML form field for each "Love" radio button. Fill in the missing code so that the form field is initially checked if the response is set to love (1). Also, make sure the value of the <input> tag is set accordingly.

```
The "Love" radio button is checked
based on the value of the response
(I represents love in the database)
                                                                   If this response is set to love
                                                                  (1), check the radio button by
                                                                  setting its checked attribute
         foreach ($responses as $response) {
                                                                   to "checked".
           if (fresponse['response'] == 1
              echo '<input type="radio" name="'. $response['response_id'] .
'" value= "/" checked= "checked" />Love ';
              echo '<input type="radio" name="' . $response['response_id'] . '" value= "\" />Love ';
                                ... />Love ';
                                                        Leaving off checked="checked"
                                                        results in the radio button
            The value of the <input> tag is set
                                                        being unchecked if the response
            to "I" so that it will be easier to
                                                         isn't set to love (1).
            store the response in the database
            when the form is submitted.
```

In case you're curious, the code to generate the "Hate" radio buttons works exactly the same way - it just looks for a slightly different response... but there's actually a cleaner way to generate both the "Love" and "Hate" radio buttons with less code...

The ternary

operator can be


statements in a

used to code if-else


more compact form.

Speaking of efficiency...

Database efficiency isn't the only kind of efficiency worth considering. There's also **coding efficiency**, which comes in many forms. One form is taking advantage of the PHP language to simplify if-else statements. The **ternary operator** is a handy way to code simple if-else statements so that they are more compact.



The ternary operator is really just a shorthand way to write an if-else statement. It can be helpful for simplifying if-else statements, especially when you're making a variable assignment or generating HTML code in response to the if condition. Here's the same "Love" radio button code rewritten to use the ternary operator:



On the other hand, a response value of anything other than 1 will prevent the checked attribute from being generated, resulting in an <input> tag for the "Love" radio button that is unchecked.

Generate the Mismatch questionnaire form

We now have enough pieces of the Mismatch questionnaire form puzzle to use the response array (\$responses) we created earlier to generate the entire HTML form. If you recall, this array was built by pulling out the current user's responses from the mismatch_response table. Let's go ahead and see the questionnaire generation code in the context of the full questionnaire.php script.

```
// Start the session
                                           Include the template files
require once ('startsession.php');
                                           that start the session and
                                                                            questionnaire.php
                                          display the page header.
// Insert the page header
$page title = 'Questionnaire';
require once ('header.php');
                                                                         Restrict the page to
require_once('appvars.php');
                                                                         users who are logged in
require once ('connectvars.php');
// Make sure the user is logged in before going any further.
if (!isset($ SESSION['user id'])) {
 echo 'Please <a href="login.php">log in</a> to access this page.';
 exit();
// Show the navigation menu
require_once('navmenu.php');
// Connect to the database
$dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
// If this user has never answered the questionnaire, insert empty responses into the database
$query = "SELECT * FROM mismatch response WHERE user id = '" . $ SESSION['user id'] . "'";
$data = mysqli query($dbc, $query);
if (mysqli num rows($data) == 0) (
 // First grab the list of topic IDs from the topic table
 Squery = "SELECT topic id FROM mismatch topic ORDER BY category id, topic id";
 $data = mysqli_query($dbc, $query);
 StopicIDs = array();
 while ($row = mysqli_fetch_array($data)) (
   array_push($topicIDs, $row['topic_id']);
 // Insert empty response rows into the response table, one per topic
  foreach ($topicIDs as $topic id) {
   $query = "INSERT INTO mismatch response (user id, topic id) VALUES ('" . $ SESSION['user id'] .
      "', '$topic id')";
   mysqli_query($dbc, $query);
// If the questionnaire form has been submitted, write the form responses to the database
if (isset($ POST['submit'])) {
  // Write the questionnaire response rows to the response table
 foreach ($ POST as $response id => $response) (
    $query = "UPDATE mismatch response SET response = '$response' " .
```

456 Chapter 8


```
"WHERE response id = '$response id'";
      mysqli_query($dbc, $query);
    echo 'Your responses have been saved.';
  // Grab the response data from the database to generate the form
  $query = "SELECT response_id, topic_id, response FROM mismatch_response WHERE user_id = '" .
    $ SESSION['user id'] . "'";
  $data = mysqli query($dbc, $query);
  $responses = array();
  while ($row = mysqli_fetch_array($data)) (
    // Look up the topic name for the response from the topic table
    Squery2 = "SELECT name, category FROM mismatch_topic WHERE topic_id = '" . Srow['topic_id'] .
    $data2 = mysqli_query($dbc, $query2);
    if (mysqli_num_rows($data2) == 1) (
      $row2 = mysqli_fetch_array($data2);
      $row['topic_name'] = $row2['name'];
      $row['category_name'] = $row2['category'];
                                                        Grab the category of the
      array push ($responses, $row);
                                                        first response to get started
                                                        before entering the loop.
  mysqli_close($dbc);
  // Generate the questionnaire form by looping through the response array
  echo '<form method="post" action="' . $ SERVER['PHP SELF'] /
                                                                                              Each category is
  echo 'How do you feel about each topic?';
                                                                                              created as a fieldset
  $category = $responses[0]['category name'];
                                                                                              to help organize
  echo '<fieldset><legend>' . $responses[0]['category_name'] . '</legend>';
                                                                                              topics together.
  foreach ($responses as $response) [
   // Only start a new fieldset if the category has changed
   if ($category != $response['category name']) (
      $category = $response['category name'];
                                                                                              Here the ternary
      echo '</fieldset><fieldset><legend>' . $response['category name'] . '</legend>';
                                                                                              operator is used to
                                                                                              change the style
                                                                                              of the label for
    // Display the topic form field
    echo '<label ' . ($response['response'] == NULL ? 'class='error"' : '') . ' for="' .
                                                                                              unanswered topics
   $response['response_id'] . '">' . $response['topic_name'] . ':</label>';
echo '<input type="radio" id="' . $response['response_id'] . '" name="' .</pre>
      $response['response_id'] . '" value="1" ' .
      ($response['response'] == 1 ? 'checked="checked" ! '') . ' />Love ';
                                                                                              Each topic is
    echo '<input type="radio" id="' . $response['response_ld'] . '" name="' .
                                                                                              created as a
   > $response['response id'] . "" value="2" ' .<
                                                                                              label followed by
      ($response['response'] == 2 ? 'checked="checked"' :
                                                                                              "Love" and "Hate"
  echo '</fieldset>';
                                                                                               radio buttons
  echo '<input type="submit" value="Save Questionnaire" name='submit" />';
  echo '</form>';
  // Insert the page footer
                                              Remember,
  require_once('footer.php');
                                              = love,
?>
                                              2 = hate.
           Each of these echo statements
                                                                  Generate the HTML questionnaire
           generates a radio button - one
                                                                  form from response data.
           for "Love" and one for "Hate".
```



Try out the new Mismatch questionnaire.

Modify Mismatch to use the new Questionnaire script (or download the application from the Head First Labs site at www.headfirstlabs.com/books/hfphp). This requires creating a new questionnaire.php script, as well as adding a "Questionnaire" menu item to the navmenu.php script so that users can access the questionnaire.

Upload the scripts to your web server, and then open the main Mismatch page (index.php) in a web browser. Make sure you log in, and then click the "Questionnaire" menu item to access the questionnaire. Notice that none of the topics have answers since this is your first visit to the questionnaire. Answer the responses and submit the form. Return to the main page, and then go back to the questionnaire once more to make sure your responses are properly loaded from the database.



The topic questions in the form are dynamically generated from the database — if you add new topics, the form changes.



The complete source code for the Mismatch application is available for download from the Head First Labs web site:

.

www.headfirstlabs.com/books/hfphp

458

Dumb Questions

Q: How does the "Love" radio button code know that the ternary operator result is a string?

A: The ternary operator always evaluates to one of the two statements on each side of the colon based on the value (true or false) of the test expression. If these statements are strings, then the result of the ternary operator will be a string. That's what makes the operator so handy-you can insert it right into the middle of an assignment or concatenation.

Q: Does the ternary operator make my script run faster?

A: No, probably not. The ternary operator is more about adding stylistic efficiency to your code than performance efficiency, meaning that it literally requires less script code. Sometimes it's more concise to use the ternary operator rather than a full-blown if-else statement, even though the two are logically equivalent. Even so, don't get too carried away with the ternary operator because it can make some code more difficult to understand if you're attempting to recast a complex if-else statement. The idea is to use the ternary operator in places where eliminating an if-else can actually help simplify the code, as opposed to making it more complicated. This usually involves using the ternary operator to selectively control a value being assigned to a variable or inserted into an expression. In the case of the Mismatch radio buttons, the latter approach was used to selectively control the insertion of an HTML attribute (checked).

Q: How is it possible to generate the Mismatch questionnaire form from the mismatch response table when the user has yet to respond to anything?

A: Excellent question. The questionnaire form has to deal with two possible scenarios the user is answering the questionnaire for the first time or the user has already answered it and is revising answers. In the first scenario, no responses have been made, so the mismatch response table has no data for this user yet. But we still need to dynamically generate the form. We could use the mismatch topic table for this one-time form generation. This won't work for the second scenario, however, because this time the form must be generated based on the user's specific love/hate responses; remember, the radio buttons for "Love" and "Hate" are generated as part of the form. So we have a problem in that the code to generate the form is completely different depending on whether the users have answered the questionnaire. Not only that, but what if they only answered a few questions? This gets messy in a hurry. The solution taken by Mismatch is to pre-populate the mismatch response table with unanswered responses the first time the user accesses the questionnaire. This allows us to always generate the questionnaire form from the mismatch response table, and not worry about the complication of generating the form differently based on whether the users have responded before, or which specific topics they've responded to. Sure, the form generation code still isn't exactly trivial, but it's simpler than if we had not taken this approach.



To simplify the code, Mismatch doesn't adjust to new topics automatically, at least not when it comes to users who've already answered the questionnaire. So you'll have to empty the mismatch_response table after adding a new topic.

Add a new topic to your own mismatch_topic table with this SQL statement:

INSERT INTO mismatch topic (name, category) VALUES ('Virtual guitars', 'Activities')

Empty all the data from the mismatch_response table with this SQL statement:

DELETE FROM mismatch response


View the questionnaire in the Mismatch application to see the new topic.

Respond to the new topic, submit the form, and check out your saved response.


www.it-ebooks.info

459

The data is now driving the form



The data is driving the form's fine, but something's amiss. It appears that one of the categories has been misspelled in the database, causing the PHP code to generate a separate fieldset for it. This is a big problem because it ruins the effect of using fieldsets to help organize the form and make it easier to respond to topics.



Frank: That's easy. Just change the name of the category in the mismatch topic table to the correct spelling.

Joe: But there's more than one category misspelled. And now that I think about it, I'm not really understanding why the category names have to be stored more than once.

Jill: I agree. We went to the trouble of eliminating duplicate data in designing the database schema, yet here we are with a bunch of duplicate category names. Not only that, but we have a couple that aren't even correct.

Frank: OK, what about just getting rid of category names and maybe referring to categories by number? Then you wouldn't run the risk of typos.

Joe: True, but we still need the category names as headings in the questionnaire form.

Jill: Maybe we can refer to categories by number without throwing out the names. That's sort of what we're doing with topics already with the mismatch topic table, right?

Joe: That's right! We didn't want to store a bunch of duplicate topic names in the mismatch_response table, so we put the topic names into the mismatch_topic table, and tied topics to responses with numeric keys.

Frank: Are you saying we could solve the duplicate category name problem by creating a new category table?

Jill: That's exactly what he's saying. We can create a new mismatch_category table where each category name is stored exactly one time. And then connect categories with topics using primary and foreign keys between mismatch topic and mismatch category. Brilliant!

Strive for a bit of normalcy

The process of redesigning the Mismatch database to eliminate duplicate data and break apart and connect tables in a logical and consistent manner is known as **normalization**. Normalization is a fairly deep database design topic that can be intimidating. But it doesn't have to be. There are enough simple database design techniques we can graft from the basics of normalization to make our MySQL databases much better than if we had just guessed at how data should be laid out.

Here are some very broad steps you can take to begin the database design process that will naturally lead to a more "normal" database: Normalization means designing a database to reduce duplicate data and improve the relationships between data.

Pick your thing, the one thing you want a
 table to describe.

What's the main thing you want your table to be about?

Make a list of the information you need to know about your one thing when you're using the table.

How will you use this table?

Using the list, break down the information about your thing into pieces you can use for organizing the table.

How can you most easily query this table?

One fundamental concept in normalization is the idea of **atomic** data, which is data broken down into the smallest form that makes sense given the usage of a database. For example, the first_name and last_name columns in the Mismatch database are atomic in a sense that they break the user's name down further than a single name column would have. This is necessary in Mismatch because we want to be able to refer to a user by first name alone.

It might not always be necessary for an application to break a full name down into separate first and last columns, however, in which case name by itself might be atomic enough. So as you're breaking down the "one thing" of a table into pieces, think about **how** the data is going to be used, not just what it represents. Atomic data is data that has been broken down into the smallest form needed for a given database.

When normalizing, think in atoms

To help turn your database design brainstorms into actions, it's helpful to ask targeted questions of your data. This will help determine how the data fits into a table, and if it has truly been broken down into its appropriate atomic representation. No one ever said splitting the atom was easy, but this list of questions can help.

Making your data atomic is the first step in creating a normal table.



1. What is the **One thing** your table describes?

Does your table describe alien sightings, email list subscriptions, video game high scores, hopeless romanties?



2. How will you USE the table to get at the one thing?

Design your table to be easy to query!



3. Do your **COlumns** contain **atomic data** to make your queries short and to the point?

Make sure data is only as small as it needs to be.

bumb Questions

Q: Should I try to break my data down into the tiniest pieces possible?

A: Not necessarily. Making your data atomic means breaking it down into the smallest pieces that you need to create an efficient table, not just the smallest possible pieces you can.

Don't break down your data any more than you have to. if you don't need extra columns, don't add them just for the sake of it.

Q: How does atomic data help me?

A: It helps you ensure that the data in your table is accurate. For example, if you have a column for the street address of an alien sighting, you might want to break the street address into two columns: the number and the street. Then you can make sure that only numbers end up in the number column.

Atomic data also lets you perform queries more efficiently because the queries are easier to write, and take a shorter amount of time to run, which adds up when you have a massive amount of data stored.

Why be normal, really?

If all this talk about nuclear data and normalcy seems a bit overkill for your modest database, consider what might happen if your web application explodes and becomes the next "big thing." What if your database grows in size by leaps and bounds in a very short period of time, stressing any weaknesses that might be present in the design? You'd rather be out shopping for your new dot-com trophy car than trying to come up with a retroactive Band-aid fix for your data, which is increasingly spiraling out of control. You yearn for some normalcy.

If you still aren't convinced, or if you're stuck daydreaming of that canary yellow McLaren, here are two proven reasons to normalize your databases: Normalization has its benefits, namely improvements in database <u>size</u> and <u>speed</u>.

1. Normal tables won't have duplicate data, which will reduce the size of your database.

Huge bloated database bad...



2. With less data to search through, your queries will be faster.



464

Three steps to a normal database

You've pondered your data for a while and now have a keen appreciation for why it should be normalized, but general ideas only get you so far. What you really need is a concise list of rules that can be applied to any database to ensure normalcy... kinda like a checklist you can work through and use to make sure a database is sufficiently normal. Here goes:

Make sure your columns are atomic.

For a column to truly be atomic, there can't be several values of the same type of data in that column. Similarly, there can't be multiple columns with the same type of data.



Normalizing a database involves strictly adhering to a series of design steps.

| love | hate |
|---|--|
| cowboy boots, long hair, reality TV, easy listening music, the opera | tattoos, gold chains, body piercings, professional wrestling, horror movies |
| tattoos, gold chains, body piercings, cowboy boots, long hair, professional wrestling, horror movies | reality TV, easy listening music, the opera |
| 1 | - |

Several values of the same type of data are in the same column, and there are also multiple columns with the same data... big problem!

@ Give each table its own primary key.

A primary key is critical for assuring that data in a table can be accessed uniquely. A primary key should be a single column, and ideally be a numeric data type so that queries are as efficient as possible.




| username | password | |
|----------|----------|-------|
| dierdre | 08447b | 111 |
| baldpaul | 230dc> | 444 |
| inettles | e511d7 | 11400 |
| rubyr | 062e4a | 44 |
| theking | b4f283 | 100 |

Without a primary key, there's no way to ensure uniqueness between the rows in this table.

Make sure non-key columns aren't dependent on each other.

This is the most challenging requirement of normal databases, and one that isn't always worth adhering to strictly. It requires you to look a bit closer at how columns of data within a given table relate to each other. The idea is that changing the value of one column shouldn't necessitate a change in another column.


| | | | | | - | |
|----------|----------|-------|------------|-------|-------|----------------|
| username | password | *** | dty | state | zip | picture |
| | | | | | 02138 | dierdrepic.jpg |
| dierdre | 08447b | | Cambridge | MA | | |
| baldpaul | 230dcb | 5,990 | Charleston | SC | 29401 | paulpic.jpg |
| inettles | e511d7 | 4465 | Athens | GA | 30601 | johanpic.jpg |
| rubyr | 062e4o | | Conundrum | AZ | 85399 | rubypic.jpg |
| theking | b4f283 | | Tupelo | MS | 38801 | elmerpic.jpg |



The hypothetical ZIP code column is dependent on the city and state columns, meaning that changing one requires changing the others. To resolve the problem, we'll need to break out the user's location into its own table with the ZIP code as the primary key.



The Mismatch database is in need of a normalization overhaul to solve the problem of duplicate category names. Given the existing database structure, sketch a modified design that solves the duplicate category problem, eliminating the risk of data entry errors. Make sure to annotate the design to explain how it works.



Dumb Questions

Q: How do I go about applying the third normalization step to Mismatch to fix the hypothetical city/state/ZIP problem?

A: The solution is to break out the location of a user into its own table, and then connect the mismatch_user table to the new table via a foreign key. So you might create a table called mismatch_location that has a primary key named location_id, along with columns to store the city and state for a user, for example. Then the city and state columns are removed from mismatch_user and replaced with a location_id foreign key. Problem solved! What makes this design work is that the location_id column actually uses the ZIP code as the primary key, alleviating the non-key dependency problem.


Q: Geez, that seems like a lot of work just to meet a picky database design requirement. Is that really necessary?

A: Yes and no. The first two normalization steps really are non-negotiable because atomic data and primary keys are critical to any good database design. It's the third step where you enter the realm of weighing the allure of an impeccable database design against the practical realities of what an application really needs. In the case of the Mismatch city/state/ZIP problem, it's probably worth accepting for the sake of simplicity. This isn't a decision that should be taken lightly, and many database purists would argue that you should rigidly adhere to all three normalization steps. The good news is that the ZIP code column is purely hypothetical, and not actually part of the mismatch_user table, so we don't really have to worry about it.

Q: Even without the ZIP code column, wouldn't city and state need to be moved into their own tables to meet the third normalization step?

A: Possibly. It's certainly true that you will end up with duplicate city/state data in the mismatch_user table. The problem with breaking out the city and state without a ZIP code is that you would have to somehow populate those tables with every city and state in existence. Otherwise users would no doubt misspell some cities and you'd still end up with problematic data. This is a good example of where you have to seriously weigh the benefits of strict normalization against the realities of a practical application.

An interesting possible solution that solves all of the problems is to use a ZIP code in the mismatch_user table instead of a city and state, and then look up the city and state from a static table or some other web service as needed. That's more complexity than we need at the moment, so let's just stick with the city and state columns.



Dumb Questions

Q: How exactly does the new mismatch_category table solve the duplicate data problem?


A: The new table separates category names from the mismatch_topic table, allowing them to be stored by themselves. With categories stored in their own table, it's no longer necessary to duplicate their names—you just have a row for each category, and these rows are then referenced by rows in the mismatch_topic table. This means that category rows in the mismatch_category table have a one-to-many relationship with topic rows in the mismatch_topic table.

Q: So does that mean the mismatch_category table only has five rows, one for each category?

| | category_id O | name |
|---|---------------|---------------|
| Each category name is only — stored once! | 1 | Appearance |
| | 2 > | Entertainment |
| | 3 | Food |
| | 4- | People |
| | 5 | Activities |

Altering the Mismatch database

In order to take advantage of the new schema, the Mismatch database requires some structural changes. More specifically, we need to create a new mismatch_category table, and then connect it to a new foreign key in the mismatch_topic table. And since the old category column in the mismatch_topic table with all the duplicate category data is no longer needed, we can drop it.



mismatch_topic

| topic_id O | name | category_id |
|------------|-----------------------------------|-------------|
| | 1771 | |
| 8 | Horror movies | 2 |
| 9 | Easy listening music | 2 |
| 10 | The opera | 2 |
| 11 | Sushi | 3 |
| 12 | Spam | 3 |
| 13 | Spicy food | 3 |
| 14 | Peanut butter & banana sandwiches | 3 |
| 15 | Martinis | (3) |
| 16 | Howard Stern | 4 |
| 17 | Bill Gates | 4 |
| 18 | Barbara Streisand | 4 |
| | *** | T |

The new mismatch_category table must be populated with category data, which is accomplished with a handful of INSERT statements.

```
INSERT INTO mismatch_category (name) VALUES ('Appearance')
INSERT INTO mismatch_category (name) VALUES ('Entertainment')
INSERT INTO mismatch_category (name) VALUES ('Food')
INSERT INTO mismatch_category (name) VALUES ('People')
INSERT INTO mismatch_category (name) VALUES ('Activities')
```

The new category_id column must then be populated with data to correctly wire the category of each topic to its appropriate category in the mismatch_category table.

```
WHERE name = 'Martinis' This |D should match the auto-
incremented |D for the category
from the mismatch_category table.
```



Create and populate the new mismatch_category database table.


Using a MySQL tool, execute the CREATE TABLE SQL command on the previous page to add a new table named mismatch_category to the Mismatch database. Then issue the INSERT statements to populate the table with category data. Now run the two ALTER statements to modify the mismatch_topic table so that it has a category_id column. Finally, UPDATE each row in the mismatch_topic table so that its category_id column points to the correct category in the mismatch_category table.


Now run a SELECT on each of the tables just to make sure everything checks out.

So is Mismatch really normal?

Yes, it is. If you apply the three main rules of normalcy to each of the Mismatch tables, you'll find that it passes with flying colors. But even if it didn't, all would not be lost. Just like people, there are **degrees** of normalcy when it comes to databases. The important thing is to attempt to design databases that are completely normal, only accepting something less when there is a very good reason for skirting the rules.

- Make sure your columns are atomic.
- Give each table its own primary key.
- Make sure non-key columns aren't dependent on each other.





Yes. In fact, most structural database changes require us to tweak any queries involving affected tables.


In this case, changing the database design to add the new mismatch_category table affects any query involving the mismatch_topic table. This is because the previous database design had categories stored directly in the mismatch_topic table. With categories broken out into their own table, which we now know is a great idea thanks to normalization, it becomes necessary to revisit the queries and code them to work with an additional table (mismatch_category).

questionnaire.php

A query within a query within a query...

One problem brought on by normalizing a database is that queries often require subqueries since you're having to reach for data in multiple tables. This can get messy. Consider the new version of the query that builds the response array to generate the Mismatch questionnaire form:

More tables usually lead to messier queries.




472 Chapter 8

Let's all join hands

Yikes! Can anything be done about all those nested queries? The solution lies in an SQL feature known as a **join**, which lets us retrieve results from more than one table in a single query. There are lots of different kinds of joins, but the most popular join, an **inner join**, selects rows from two tables based on a condition. In an inner join, query results only include rows where this condition is matched.


A join grabs results from multiple tables in a single query.



with Connect the dots

Since joins involve more than one table, it's important to be clear about each column referenced in a join. More specifically, you must identify the table for each column so that there isn't any confusion—tables often have columns with the same names, especially when it comes to keys. Just preface the column name with the table name, and a dot. For example, here's the previous INNER JOIN query that builds a result set of topic IDs and category names:

Dot notation allows you to reference the table a column belongs to within a join.



474 Chapter 8

Surely we can do more with inner joins

Inner joins don't stop at just combining data from two tables. Since an inner join is ultimately just a query, you can still use normal query constructs to further control the results. For example, if you want to grab a specific row from the set of joined results, you can hang a WHERE statement on the INNER JOIN query to isolate just that row.

FROM mismatch_topic.topic_id, mismatch_category.name

FROM mismatch_topic


INNER JOIN mismatch_category

ON (mismatch_topic.category_id = mismatch_category.category_id)


WHERE mismatch_topic.name = 'Horror movies'


An INNER JOIN combines rows from two tables using comparison operators in a condition.

So what exactly does this query return? First remember that the WHERE clause serves as a refinement of the previous query. In other words, it **further constrains** the rows returned by the original INNER JOIN query. As a recap, here are the results of the inner join **without** the WHERE clause:



The WHERE clause has the effect of whittling down this result set to a single row, the row whose topic name equals 'Horror movies'. We have to look back at the mismatch_topic table to see which row this is





topic_id name category_id 7
Professional wrestling 2

8 Horror movies 2

9 Easy listening music 2

matches the WHERE clause:

there are no Dumb Questions

Q: So a WHERE clause lets you constrain the results of a JOIN query based on rows in one of the joined tables?

A: That's correct. Keep in mind that the actual comparison taking place inside a WHERE clause applies to the original tables, not the query results. So in the case of the Mismatch example, the query is retrieving data from two different tables that match on a certain column that appears in both tables (category_id), and then only selecting the row where the name column in mismatch_topic is a certain value ('Horror movies'). So the INNER JOIN takes place with respect to the category_id column in, both tables but the WHERE clause refines the results using only the name column in the mismatch_topic table.

Q: Could the WHERE clause in the Mismatch JOIN query be based on the mismatch category table instead?

A: Absolutely. The WHERE clause can restrict query results based on either of the tables involved in the join. As an example, the WHERE clause could be changed to look only for a specific category, like this:

... WHERE mismatch category.name = 'Entertainment'

This WHERE clause limits the result set to only include topics that fall under the Entertainment category. So the WHERE clause doesn't affect the manner in which the tables are joined, but it does affect the specific rows returned by the query.

Simplifying ON with USING

Remember that our goal is to simplify the messy Mismatch queries with INNER JOIN. When an inner join involves **matching columns with the same name**, we can further simplify the query with the help of the USING statement. The USING statement takes the place of ON in an INNER JOIN query, and requires the name of the column to be used in the match. Just make sure the column is named exactly the same in both tables. As an example, here's the Mismatch query again:

Rewrite ON with USING for more concise inner join queries that match on a common column.

```
SELECT mismatch topic.topic id, mismatch category.name

FROM mismatch_topic

INNER JOIN mismatch_category

ON (mismatch_topic.category_id = mismatch_category.category_id)

WHERE mismatch_topic.name = 'Horror movies'
```

Since the ON part of the query relies on columns with the same name (category_id), it can be simplified with a USING statement:

```
FROM mismatch_topic

INNER JOIN mismatch_category

USING (category_id)


WHERE mismatch_topic.name = 'Horror movies'

All that is required is the name of the column... no need to specify equality with =.
```

The column names must be the same in order to use the USING statement in an inner join.


Nicknames for tables and columns

Our INNER JOIN query just keeps getting tighter! Let's take it one step further. When it comes to SQL queries, it's standard to refer to table and columns by their names as they appear in the database. But this can be cumbersome in larger queries that involve joins with multiple tables—the names can actually make a query tough to read. It's sometimes worthwhile to employ an **alias**, which is a temporary name used to refer to a table or column in a query. Let's rewrite the Mismatch query using aliases.



An alias allows you to rename a table or column within a query to help simplify the query in some way.

Are aliases only good for writing more compact queries? No, there are some situations where they're downright essential! A join that would be quite handy in the Mismatch application is retrieving both the topic name and category name for a given topic ID. But the mismatch_topic and mismatch_category tables use the same column name (name) for this data. This is a problem because the result of combining these two columns would leave us with ambiguous column names. But we can rename the result columns to be more descriptive with aliases.



When a column is renamed with an alias, the alias is what appears in the query results.

topic_id 0=

categor

name

-mismatch_categ

category_id O

name

Selecting these two columns

in a join yields result columns

with the same name ... not good!

Joins to the rescue

So joins make it possible to involve more than one table in a query, effectively pulling data from more than one place and sticking it in a single result table. The Mismatch query that builds a response array is a perfect candidate for joins since it contains no less than three nested queries for dealing with multiple tables. Let's start with the original code:

Joins are more efficient and require less code than nested queries.

```
// Grab the response data from the database to generate the form
Squery = "SELECT response id, topic id, response FROM mismatch response " .
  "WHERE user id = '" . $ SESSION['user id'] . "'";
                                                                             The last two queries in the code
$data = mysqli query($dbc, $query);
$responses = array();
                                                                             are responsible for obtaining
while ($row = mysqli_fetch_array($data)) {
                                                                             the topic name and category
  // Look up the topic name for the response from the topic table
                                                                             name from their respective
  $query2 = "SELECT name, category id FROM mismatch topic " .
    "WHERE topic id = '" . $row['topic id'] . "'";
                                                                             tables - one query per table
  $data2 = mysqli_query($dbc, $query2);
  if (mysqli num rows($data2) == 1) {
    $row2 = mysqli_fetch_array($data2);
    $row['topic name'] = $row2['name'];
    // Look up the category name for the topic from the category table
    $query3 = "SELECT name FROM mismatch_category" .
      "WHERE category_id = '" . $row2['category_id'] .
    $data3 = mysqli query($dbc, $query3);
    if (mysqli num rows($data3) == 1) {
      $row3 = mysqli fetch array($data3);
      $row['category name'] = $row3['name'];
      array push ($responses, $row);
                                                                              With a join, it's possible to
                                                                              grab both the topic name and
                                                                              category name in a single query.
And here's the new version of the code that uses a join:
        // Grab the response data from the database to generate the form
        Squery = "SELECT response id, topic id, response FROM mismatch response " .
          "WHERE user id = '" . $ SESSION['user id'] . "'";
        $data = mysqli query($dbc, $query);
        $responses = array();
        while ($row = mysqli fetch array($data)) (
           // Look up the topic and category names for the response from the topic and category tables
          $query2 = "SELECT mt.name AS topic name, mc.name AS category name " .
            "FROM mismatch_topic AS mt " .
            "INNER JOIN mismatch_category AS mc USING (category_id) "
            "WHERE mt.topic_id = '" . $row['topic_id'] . "'";
                                                                                      Aliases are used to help
          $data2 = mysqli_query($dbc, $query2);
                                                                                      simplify the code.
          if (mysqli num rows($data2) == 1) {
            $row2 = mysqli fetch array($data2);
                                                                    The topic ID is used as
            $row['topic_name'] = $row2['topic_name'];
                                                                    the basis for the main
            $row['category name'] = $row2['category name'];
            array push ($responses, $row);
                                                                    query, but the category ID
                                                                    controls the join itself.
```

I don't get it, you still have an extra query that looks up the category name. If joins are so great, why do you still need two queries?

0




We don't still need two queries, at least not if we use joins to their full potential.

It is possible to join more than two tables, which is what is truly required of the Mismatch response array code. We need a single query that accomplishes the following three things: retrieve all of the responses for the user, get the topic name for each response, and then get the category name for each response. The new and improved code on the facing page accomplishes the last two steps in a single query involving a join between the mismatch_topic and mismatch_category tables. Ideally, a single query with two joins would kill all three birds with one big join-shaped stone.



Following is code that is capable of retrieving response data from the database with one query, thanks to the clever usage of joins. Be clever and write the SQL query that does the joining between the mismatch response, mismatch topic, and mismatch category tables.

| // Grab | the | respor | se dat | a from | the | datab | ase | to | gener | ate | the | form |
|------------|-------|----------|----------|---------|---------------|--------|-----------|-------|-------|-------|-----|------|
| query = | 22 | | | | | | | | | | | |
| query | •••• | ******** | | | | | | | | ••••• | | |
| ••••• | | | | | | | ••••• | | | | | |
| ••••• | | | ••••• | | | | | ••••• | | ••••• | | |
| ********** | | | | | • • • • • • • | | | •••• | | | | |
| | | | | | | | ••••• | | | | | |
| | | | | | | | | | | | | |
| \$data = | mysc | qli_que | ery(\$db | c, \$qu | ery) | ; | | | | | | |
| respon: | ses = | = array | ((); | | | | | | | | | |
| while (| Srow | = mys | gli fet | ch arr | av(\$ | data)) | 1 | | | | | |
| array | | | | | | | A. 1. 2.1 | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |



Dumb Questions

Q: What other kinds of joins are there?

A: Other types of inner joins include equijoins, non-equijoins, and natural joins. Equijoins and non-equijoins perform an inner join based on an equality or inequality comparison, respectively. You've already seen several examples of equijoins in the Mismatch queries that check for matching topic_id and category_id columns. Since the matching involves looking for "equal" columns (the same ID), these queries are considered equijoins.

Another kind of inner join is a natural join, which involves comparing all columns that have the same name between two tables. So a natural join is really just an equijoin, in which the columns used to determine the join are automatically chosen. This automatic aspect of natural joins makes them a little less desirable than normal inner joins because it isn't obvious by looking at them what is going on—you have to look at the database structure to know what columns are being used in the join.

Q: So all SQL joins are really just variations of inner joins?


A: No, there are lots of other joins at your disposal. The other major classification of joins is collectively called **outer joins**, but there are several different kinds of joins that are considered outer joins. There are **left** outer joins, **right** outer joins, **full** outer joins, and the seldom used but awe-inspiring triple helix ambidextrous join. OK, that last one isn't a real join, but it should be! The basic idea behind an outer join is that rows in the joined tables don't have to match in order to make it not the join. So it's possible to construct outer joins that always result in rows from a table being selected regardless of any matching conditions.

Outer joins can be just as handy as inner joins, depending on the specific needs of a database application. To learn more about the different kinds of joins and how they are used, take a look at Head First SQL.



Revamp the Questionnaire script to grab the user's response data with a single query.

Modify the questionnaire.php script to use inner joins so that the queries that grab the user's response data are handled in a single query. Upload the new script to your web server, and then navigate to the questionnaire in a web browser. If all goes well, you shouldn't notice any difference... but deep down you know the script code is much better built!





Mismatch now remembers user responses but it doesn't yet do anything with them...like finding a mismatch!

The collection of user response data only gets us halfway to a successful mismatch. The Mismatch application is still missing a mechanism for firing Cupid's arrow into the database to find a love connection. This involves somehow examining the responses for all the users in the database to see who matches up as an ideal mismatch.

Figuring out an ideal mismatch sounds pretty complicated given all those categories, topics, and responses. Are you sure that's really doable?




It's definitely doable; we just need a consistent means of calculating how many mismatched topics any two users share.

If we come up with a reasonably simple way to calculate how many mismatched topics any two users share, then it becomes possible to loop through the user database comparing users. The person with the highest number of mismatches for any given user is that user's ideal mismatch!



| Write down how you would go about calculating the "mismatchab of two users using data stored in the Mismatch database: | ility" |
|---|--------|
| | |
| | |
| | |

Love is a numbers game



We're still missing a handy way in PHP code to determine when a mismatch takes place between two responses. Certainly a couple of ifelse statements could be hacked together to check for a 1 and a 2, and then a 2 and a 1, but the solution can be more elegant than that. In either scenario, adding together the two responses results in a value of 3. So we can use a simple equation to detect a mismatch between two responses.

If ResponseA + ResponseB = 3, we have a mismatch!

So finding a love connection really does boil down to simple math. That solves the specifics of comparing individual matches, but it doesn't address the larger problem of how to actually build the My Mismatch script.

Five steps to a successful mismatch

Finding that perfectly mismatched someone isn't just a matter of comparing response rows. The My Mismatch script has to follow a set of carefully orchestrated steps in order to successfully make a mismatch. These steps hold the key to finally satisfying users and bringing meaning to their questionnaire responses.



Grab the user's responses from the mismatch_response table, making sure to join the topic names with the results.



Initialize the mismatch search results, including the variables that keep up with the "best mismatch."



Loop through the user table comparing other people's responses to the user's responses. This involves comparing responses for every person in the database to the user's corresponding responses. A "score" keeps up with how many opposite responses the user shares with each person.



After each cycle through the loop, see if the current mismatch is better than the best mismatch so far. If so, store this one as the new "best mismatch," making sure to store away the mismatched topics as well.



Make sure a "best mismatch" was found, then query to get more information about the mismatched user, and show the results.

Prepare for the mismatch search

Step 1 falls under familiar territory since we've already written some queries that perform a join like this. But we need to store away the user's responses so that we can compare them to the responses of other users later in the script (Step 3). The following code builds an array, \$user responses, that contains the responses for the logged in user.

This query uses a JOIN to select all of the responses for the user.

```
$query = "SELECT mr.response id, mr.topic id, mr.response, mt.name
AS topic name " .
  "FROM mismatch response AS mr "
  "INNER JOIN mismatch topic AS mt " .
  "USING (topic id) " .
  "WHERE mr.user id = '" . $ SESSION['user id'] . "'";
                                                             A while loop is used to go
$data = mysqli query($dbc, $query);
                                                             through each row of the query
                                                             results, building an array of
$user responses = array();
                                                             user responses in the process.
while ($row = mysqli fetch array($data))
  array push ($user responses, $row);
                                                Grab the user's responses from the
                                                mismatch_response table, making sure
   When this loop finishes, the
                                                to join the topic names with the results.
   fuser_responses array will hold
   all of the user's responses.
```

Step 2 of the My Mismatch script construction process involves setting up some variables that will hold the results of the mismatch search. These variables will be used throughout the My Mismatch script as the search for the best mismatch is carried out:

\$mismatch score = 0; € \$ \$mismatch user id = -1; \$mismatch topics = array(); This is the user ID of the person who is being checked This array holds the topics that as a potential mismatch ... are mismatched between two users.

This variable holds the mismatch score between two users - the highest score ultimately results in a mismatch.

> If this variable is still set to - l after the search, we know there wasn't a mismatch - this can only happen when no other users have answered the questionnaire, which is very unlikely.

Initialize the mismatch search results, including the variables that keep up with the "best mismatch."

486

Chapter 8

when the search is complete,


this variable holds the ID of

the best mismatch.

Compare users for "mismatchiness"

The next mismatching step requires looping through every user, and comparing their responses to the responses of the logged in user. In other words, we're taking the logged in user, or **mismatcher** (Sidney, for example), and going through the entire user table comparing her responses to those of each mismatchee. We're looking for the mismatchee with the most responses that are opposite of the mismatcher.

Where to begin? How about a loop that steps through the \$user responses array (mismatcher responses)? Inside the loop we compare the value of each element with comparable elements in another array that holds the mismatchee responses. Let's call the second array \$mismatch responses.



This array changes as the mismatcher is compared to different mismatchees.

The challenge here is that we need a loop that essentially loops through two arrays at the same time, comparing respective elements one-to-one. A foreach loop won't work because it can only loop through a single array, and we need to loop through two arrays simultaneously. A while loop could work, but we'd have to create a counter variable and manually increment it each time through the loop. Ideally, we need a loop that automatically takes care of managing a counter variable so that we can use it to access elements in each array.

foreach (...) [
Won't work!


exactly ideal.

you are here >

487

All we need is a FOR loop

PHP offers another type of loop that offers exactly the functionality we need for the My Mismatch response comparisons. It's called a for loop, and it's great for repeating something a certain amount of **known** times. For example, for loops are great for counting tasks, such as counting down to zero or counting up to some value. Here's the structure of a for loop, which reveals how a loop can be structured to step through an array using a loop counter variable (\$i).



Exercise

Step 3 of the My Mismatch script involves comparing two users by looping through each of their responses, and calculating a "score" based on how many responses are mismatched. Given the following pieces of data, finish writing the for loop that calculates this score.

Dumb Questions

Q: Why not just use a foreach loop to calculate the score instead of a for loop?

A: Although a foreach loop would work perfectly fine for looping through all of the different responses, it wouldn't provide you with an index (\$i) at any given iteration through the loop. This index is important because the code is using it to access both the array of user responses and the array of mismatch responses. A foreach loop would eliminate the need for an index for one of the two arrays, but not both. So we need a regular for loop with an index that can be used to access similar elements of each array.

Q: What's the purpose of storing the mismatched responses in their own array?

A: The array of mismatched responses is important in letting the users know exactly how they compared topically with their ideal mismatch. It's not enough to just share the identity of the ideal mismatch person—what is even better is also sharing the specific topics the user mismatched against that person. This helps give the mismatch result a little more context, and lets the users know a bit more about why this particular person is truly such a great mismatch for them.

Q: In Step 5 of the Mismatch script, how would there ever not be a best mismatch for any given user?

A: Although unlikely, you have to consider the scenario where there is only one user in the entire system, in which case there would be no one else to mismatch that user against.



Step 3 of the My Mismatch script involves comparing two users by looping through each of their responses, and calculating a "score" based on how many responses are mismatched. Given the following pieces of data, finish writing the for loop that calculates this score.

\$user_responses

| 2 | Hate | Gold chains | | | |
|---|------|------------------------|--|--|--|
| 3 | | | | | |
| | Hate | Body piercings | | | |
| 4 | Love | Cowboy boots | | | |
| 5 | Love | Long hair | | | |
| 6 | Love | Reality TV | | | |
| 7 | Hate | Professional wrestling | | | |
| 8 | Hate | Horror movies | | | |
| | 8 | | | | |

\$mismatch_responses

| | 76 | 1 | Love | Tattoos |
|-----|----|---|------|------------------------|
| | 77 | 2 | Love | Gold chains |
| 5 | 78 | | Love | Body piercings |
| 6 | 79 | 4 | Love | Cowboy boots |
| u. | 80 | 5 | Love | Long hair |
| Ε. | 81 | 6 | Hate | Reality TV |
| ~ | 82 | 7 | Love | Professional wrestling |
| - 1 | 83 | 8 | Love | Horror movies |



The score is incremented for each mismatched response found.

Remember, the number of user responses is the same as the number of total topics since the responses come straight from the questionnaire.

The sscore variable ends up being in the range O (no mismatches) to the total number of topics (complete mismatch).

for (\$i = 0; \$i < count(Suser_responses); \$i++) {

if (fuser responses[fi]['response'] + fmismatch responses[fi]['response'] == 3) {

fscore += 1;

array push(\$topics, Suser_responses[\$i]['topic_name']);

The loop counter is used to step through each user response.

Each mismatched topic is added to an array so that it can be displayed to the user when revealing the mismatch.

A mismatch consists of a love (1) matched with a hate (2), so adding them together always results in a 3 if there is a mismatch.

Loop through the user table comparing other people's responses to the user's responses.

490

Finishing the mismatching

The shiny new loop that calculates a mismatch score is part of a larger script (mymismatch.php) that takes care of finding a user's ideal mismatch in the Mismatch database, and then displaying the information.



491

```
// Only look for a mismatch if the user has questionnaire responses stored
  $query = "SELECT * FROM mismatch_response WHERE user_id = '" . $_SESSION['user_id'] . "'";
 $data = mysqli_query($dbc, $query); It's only possible to find a mismatch for a user if (mysqli_num_rows($data) != 0) 1 who has responded to the questionnaire.
    // First grab the user's responses from the response table (JOIN to get the topic name)
    $query = "SELECT mr.response id, mr.topic id, mr.response, mt.name AS topic name " .
      "FROM mismatch response AS mr " .
      "INNER JOIN mismatch_topic As mt " . _____ retrieve the topic name
                                                                 when SELECTing the user's
      "USING (topic id) " .
                                                                  questionnaire responses.
      "WHERE mr.user id = '" . $ SESSION['user id'] . "'";
    $data = mysqli query($dbc, $query);
    $user responses = array();
    while ($row = mysqli fetch array($data)) (
      array_push($user_responses, $row);
                                    — The fuser_responses array holds all of the responses for the user.
    // Initialize the mismatch search results
    $mismatch score = 0;
                                          These variables keep track of the mismatch search as
$ $mismatch_user_id = -1;
                                           it progresses.
    $mismatch_topics = array();
```

```
// Loop through the user table comparing other people's responses to the user's responses
          $query = "SELECT user id FROM mismatch user WHERE user id != '" . $ SESSION['user id'] . "'";
          $data = mysqli query($dbc, $query);
                                                                                            his query grabs all of
          while ($row = mysqli_fetch_array($data)) {
                                                                                            the users except the
                                                                                            user being mismatched.
            // Grab the response data for the user (a potential mismatch)
            $query2 = "SELECT response id, topic id, response FROM mismatch response " .
               "WHERE user id = '" . $row['user id'] .
                                                                      For each user, this query
            $data2 = mysqli query($dbc, $query2);
                                                                      grabs the questionnaire
            $mismatch responses = array();
                                                                      responses for comparing
            while ($row2 = mysqli_fetch_array($data2)) {
                                                                      as a potential mismatch.
              array push ($mismatch responses, $row2);
This curly
brace
                                                                               Here's the for loop that
marks the
                                                                               calculates the mismatch score
end of the
            // Compare each response and calculate a mismatch total
main while
                                                                               for a potential mismatch.
            $score = 0;
loop.
            $topics = array();
            for ($i = 0; $i < count($user responses); $i++) {
               if (((int) Suser responses[Si]['response']) + ((int) Smismatch responses[Si]['response']) == 3)
                 $score += 1;
                                                                              The text response ('2', for example)
                 array push ($topics, $user responses [$i] ['topic name']);
                                                                               is cast to an integer (2) so that it
                                                                               can be added and compared
            // Check to see if this person is better than the best mismatch so far
            if ($score > $mismatch_score) {
               // We found a better mismatch, so update the mismatch search results
                                                                 If this user is a better
               $mismatch score = $score;
                                                                 mismatch than the best
               $mismatch_user_id = $row['user_id'];
                                                                 mismatch so far, then set
               $mismatch topics = array slice($topics, 0);
                                                                him as the best mismatch.
                   This function extracts a "slice" of an array.
                    In this case we're just using it to copy the
                    ftopics array into imismatch topics.
                          We're still inside that first if
                         statement from the previous page,
                          and there's still more code ...
```


```
Before displaying the
                                                                 control your data, control your world
                                            mismatch results, make
  // Make sure a mismatch was found
                                            sure a "best mismatch"
  if ($mismatch user id != -1) ( &
                                            was actually found.
    $query = "SELECT username, first name, last name, city, state, picture FROM mismatch user " .
      "WHERE user id = '$mismatch user id'";
                                                                Query for the mismatched
    $data = mysqli query($dbc, $query);
    if (mysqli num rows($data) == 1) {
      // The user row for the mismatch was found, so display the user data
      $row = mysqli_fetch_array($data);
                                                                                 Display the
      echo '';
                                                                                 user's name
      if (!empty($row['first_name']) && !empty($row['last_name'])) (
        echo $row['first name'] . ' ' . $row['last name'] . '<br />';
      if (!empty($row['city']) && !empty($row['state'])) {
        echo $row['city'] . ', ' . $row['state'] . '<br />'; Show the user's
      echo '';
      if (!empty($row['picture'])) (
        echo '<img src="' . MM UPLOADPATH . $row['picture'] . '" alt="Profile Picture" /><br />';
                                                         Don't forget to
generate an <img> tag
      echo '';
                                                          with the user's picture!
      // Display the mismatched topics
      echo '<h4>You are mismatched on the following ' . count($mismatch_topics) . ' topics:</h4>';
      foreach ($mismatch topics as $topic) (
                                            It's important to show what topics actually resulted in the mismatch.
        echo $topic . '<br />';
      // Display a link to the mismatch user's profile
      echo '<h4>View <a href=viewprofile.php?user_id=' . $mismatch_user_id . '>' .
        $row['first name'] . '\'s profile</a>.</h4>';
                                                Finally, we provide a link to
the mismatched user's profile
                                                 so that the logged in user can
                                                 find out more about him
else (
 echo 'You must first <a href="questionnaire.php">answer the questionnaire</a> before you can
    'be mismatched.';
```



Find your perfect Mismatch!

Modify Mismatch to use the new My Mismatch script (or download the application from the Head First Labs site at www.headfirstlabs.com/books/hfphp). This requires creating a new mymismatch.php script, as well as adding a "My Mismatch" menu item to the navmenu.php script so that users can access the script.

Upload the scripts to your web server, and then open the main Mismatch page (index.php) in a web browser. Make sure you log in and have filled out the questionnaire, and then click the "My Mismatch" menu item to view your mismatch.




494 Chapter 8



Database Schema Magnets

Remember the Guitar Wars application from eons ago? Your job is to study the Guitar Wars database, which could use some normalization help, and come up with a better schema. Use all of the magnets below to flesh out the table and column names, and also identify the primary and foreign keys.

The database drives the display of scores on the main Guitar Wars page.




you are here > 495



Database Schema Magnets Solution

Remember the Guitar Wars application from eons ago? Your job is to study the Guitar Wars database, which could use some normalization help, and come up with a better schema. Use all of the magnets below to flesh out the table and column names, and also identify the primary and foreign keys.

The database drives the display of scores on the main Guitar Wars page.




496 Chapter 8

dependent on each other.



PHP&MySQLcross

Concerned that your own perfect mismatch is still out there waiting to be found? Take your mind off it by completing this crossword puzzle.



Across


- A representation of all the structures, such as tables and columns, in your database, along with how they connect.
- This happens when multiple rows of a table are related to multiple rows of another table.
- This allows you to convert between different PHP data types.
- Use this to combine results from one table with the results of another table in a query.
- The process of eliminating redundancies and other design problems in a database.
- You can shorten some if-else statements with this handy little operator.
- When one row of a table is related to multiple rows in another table.

Down

- 1. A join makes it possible to get rid of these.
- 2. A column in a table that references the primary key of another table.
- 3. When a form is generated from a database, it is considered
- It's not nuclear, it's just data in the smallest size that makes sense for a given database.
- 8. Rows in two tables have this relationship when there is exactly one row in one table for every row in the other.
- One of these can help greatly in figuring out the design of a table
- 13. A temporary name used to reference a piece of information in a query.



PHP&MySQLcross Solution



498

Your PHP & MySQL Toolbox

Quite a few new MySQL database techniques were uncovered in this chapter, not to mention a few new PHP tricks. Let's do a quick recap!

Schemas and Diagrams

A schema is a representation of all the structures (tables, columns, etc.) in your database, along with how they connect. A diagram is a visual depiction of your database, including details about the specific columns responsible for connecting tables.

Foreign Key

A column in a table that is used to link the table to another table. A foreign key in a child table typically connects to a primary key in a parent table, effectively linking rows between the two tables.

? :

The ternary operator is a PHP construct that works like a really compact if—else statement. It is handy for performing simple choices based on a true/false expression.

INNER JOIN

This kind of join combines data from two tables that have matching rows. Unlike a normal query, a join allows you to grab data from more than one table, which is extremely helpful when a database consists of multiple tables.

Normalization

Normalization is the process of altering the design of a database to reduce duplicate data and improve the placement of and relationships between data. The goal is to produce a robust design that holds up well to growing data.

for (. . .)


A loop that is ideally suited to looping based on a specific number of iterations. Create a for loop by initializing a counter, establishing a test condition, and specifying how the counter is to be updated after each iteration.

AS name

This SQL statement establishes an alias, which is a name used to identify a piece of data within a query. Aliases are often used to simplify queries by shortening long table and column names. They can also be used to rename result data when the original table column isn't specific enough.

9 string and custom functions

Better living through * functions



Functions take your applications to a whole new level.

You've already been using PHP's built-in functions to accomplish things. Now it's time to take a look at a few more really useful **built-in functions**. And then you'll learn to build your very own **custom functions** to take you farther than you ever imagined it was possible to go. Well, maybe not to the point of raising laser sharks, but custom functions will streamline your code and make it reusable.

this is a new chapter

A good risky job is hard to find

The Internet startup, RiskyJobs.biz, is designed to help companies find the right people to fill their riskiest jobs. The business model is simple: for each risky job we can fill with the right candidate, we get a commission. The more successful matches, the bigger our profit.

Risky Jobs needs help improving its site's job-search functionality. Right now, there's a database full of risky jobs just waiting to be discovered by the right people. Let's take a look at the Risky Jobs search form and the underlying database of available jobs.

This simple search form calls a script that searches the riskyjobs table.




The riskyjobs table contains job titles and descriptions, along with location information and the posting date of each job.

| job_id | title | description | dity | state | zip | | |
|--------|------------------------|-----------------------|--|--------|-------|------------------------|---------------------|
| 1 | Matador | Bustling dairy farm | Rutland | 100000 | | company | date_posted |
| 2 | Paparazzo | Top celebrity | ALC: NO CONTRACT OF THE PARTY O | VT | 05701 | Mad About Milk Dairies | 2008-03-11 10:51:24 |
| 3 | Shark Trainer | | Beverly Hills | CA | 90210 | Diva Pursuit, LLC | 2008-03-24 10:51:24 |
| - | | Training sharks to do | 1 5 A C S C S S S S S S S S S S S S S S S S | FL | 32801 | SharkBait, Inc. | 2008-04-28 03:12:45 |
| 4 | Firefighter | The City of Dataville | Dataville | ОН | 45490 | City of Dataville | |
| 5 | Voltage Checker | You'll be out in the | Durham | NC | 27701 | | 2008-05-22 12:34:17 |
| 6 | Crocodile Dentist | Do you love animals | | 7750 | - | Shock Systems, LLC | 2008-06-28 11:16:30 |
| 7 | Custard Walker | | Everglades City | FL | 34139 | Ravenous Reptiles | 2008-07-14 10:51:24 |
| | | We need people | Albuquerque | NM | 87101 | Pie Technologies | 2008-07-24 10:54:05 |
| 8 | Electric Bull Repairer | Hank's Honky Tonk | Hoboken | NI | 07030 | Hank's Honky Tank | |
| 1 | | | | | | ridik s ridiky lonk | 2008-07-27 11:22:28 |

Each job posting is uniquely identified by the job_id primary key.

Show the search results!








Ernesto, our fearless bullfighter, is seeing red because his job search isn't producing any results.

Sharpen your pencil

When the Risky Jobs form is submitted, the search string is stored in the variable \$user_search, which is plugged into the following SQL query to do the actual searching. Write down how many rows in the riskyjobs database on the facing page will be found as a result of Ernesto's search.

\$search_query = "SELECT job_id, title, state, description FROM riskyjobs " .
 "WHERE title = '\$user_search'";
\$result = mysqli_query(\$dbc, \$search_query);


Write your answer here!



The search leaves no margin for error

The SELECT query in the Risky Jobs script is very rigid, only resulting in a match if the two strings being compared are **identical**. This presents a problem for our job search because people need to be able to enter search terms that match job listings even if the job title isn't an exact match.

Let's go back to Ernesto's search, which results in a query that searches the title column of the riskyjobs table for the text "Bull Fighter Matador": The case of the search term doesn't matter because the MySQL WHERE clause is case—insensitive by default.




See the problem? This query is only going to match rows in the table where the title column contains the exact text "Bull Fighter Matador". The job with the title "Matador" isn't matched, and neither are "Firefighter" or "Electric Bull Repairer". OK, maybe it's good those last two were missed, but the search still isn't working as intended. And it's not the mixed case that presents the problem (MySQL searches are by default case-insensitive), it's the fact that the entire search string must be an exact match due to the equality (=) operator in the WHERE clause.

SQL queries can be flexible with LIKE

What we really need is a way to search the database for a match on any portion of a search string. SQL lets us do just that with the LIKE keyword, which adds flexibility to the types of matches returned by a WHERE clause. You can think of LIKE as a more forgiving version of the = operator. Take a look at the following query, which uses LIKE to match rows where the word "fighter" appears **anywhere** in the title column:

SELECT job id, title, description FROM riskyjobs



LIKE makes it much easier to find matches, especially when you need to match the search string as part of a larger word or phrase. Check out these examples of strings that match up with the above query:

Firefighter Prize Fighter

LIKE clauses typically work in conjunction with wildcard characters, which are stand-ins for characters in the data we're matching. In SQL, the percent sign (%) wildcard stands for any group of zero or more characters. Placing this wildcard in a query before and after a search term, as in the SELECT statement above, tells SQL to return results whenever the term appears somewhere in the data, no matter how many characters appear before or after it.

FightErnestoPlease



Geek Bits

SQL has another wildcard character that can be used with LIKE. It's the underscore (_), and it represents a single character. Consider the following LIKE clause:

LIKE ' fighter%'


It's saying: "Find the string "fighter" with any **four** characters in front of it, and any characters after it." This would match "bullfighter" and "firefighter" but not "streetfighter".



Time out! Take a moment to familiarize yourself with the Risky Jobs database... and try out a few searches.

Download the riskyjobs.sql file for the Risky Jobs application from the Head First Labs web site at www.headfirstlabs.com/books/hfphp. This file contains SQL statements that build and populate the riskyjobs table with sample data.

After you've executed the statements in riskyjobs.sql in a MySQL tool, try out a few queries to simulate job searches. Here are some to get you started.



This query uses LIKE to find jobs with the word "animals" anywhere in the job description.



The complete source code for the Risky Jobs application is available for download from the Head First Labs web site:

www.headfirstlabs.com/books/hfphp

506



LIKE Clause Magnets

A bunch of LIKE clauses are all scrambled up on the fridge.

Can you match up the clauses with their appropriate results?


Some may have multiple answers.

LIKE '% T%'

LIKE '% T%'


LIKE '% T%'


LIKE '%do_' LIKE '%ma%'





LIKE Clause Magnets Solution






Taking what people type in the Risky Jobs search field and matching it exactly won't always work. The search would be much more effective if we searched on each search term entered, as opposed to searching on the entire search phrase. But how do you search on multiple terms? We could store each of the search terms in an array, and then tweak the SELECT query to search for each keyword individually.


Explode a string into individual words

To make Risky Jobs search functionality more effective, we need a way to break apart users' search strings when they enter multiple words in the form field. The data our risky job seekers enter into the search form is text, which means we can use any of the built-in PHP string functions to process it. One extremely powerful function is explode(), and it breaks apart a string into an array of separate strings. Here's an example:

The explode() function breaks a string into an array of substrings.



The explode() function requires two parameters. The first is the **delimiter**, which is a character or characters that indicates **where** to break up the string. We're using a space character as our delimiter, which means the search string is broken everywhere a space appears. The delimiter itself is not included in the resulting substrings. The second parameter is the string to be exploded.



Incorporating the array of search terms into Risky Jobs involves adding a line of code before we run the query on the Risky Jobs database. Now, if someone enters "Tipper Cow" into the search field, this code breaks it into two words and stores each word in an array (\$search_words).

```
Suser_search = S_GET['usersearch'];

Ssearch_words = explode(' ', Suser_search);

The explode() function stores each word in juser_search in an array called isearch_words.
```



In order to incorporate the exploded search terms into the Risky Jobs application, we have to plug each of the terms into an SQL SELECT query using LIKE and OR. For example, here's what a query would look like for Ernesto's earlier search on "Bull Fighter Matador":

| instead of the | ching the job description title since the description |
|--|--|
| SELECT * FROM riskyjobs has more infor | mation to match. |
| | CA CARROLL AND |
| WHERE description LIKE '%Bull%' OR descrip | otion LIKE '%Fighter%' OR |
| description LIKE '%Matador%' | |
| Now suppose we used the following PHP code to attempt to data entered by the user into the Risky Jobs search form: | assemble this query from the search |
| <pre>\$search_query = "SELECT * FROM riskyjobs";</pre> | |
| <pre>\$where_clause = '';</pre> | |
| <pre>\$user_search = \$_GET['usersearch'];</pre> | |
| <pre>\$search_words = explode(' ', \$user_search);</pre> | |
| foreach (\$search_words as \$word) (| |
| <pre>\$where_clause .= " description LIKE '%\$wor</pre> | d%' DR "; |
| £ | |
| | |
| if (!empty(\$where_clause)) { | A O O Risky John - Search |
| <pre>\$search_query .= " WHERE \$where_clause";</pre> | Risky John 9 |
|) | Danger! Your dream job is out there. Do you have the guts to go find it? |
| | Risky Jobs - Search |
| Write down the SQL query generated by this code | Find your risky job: |
| when Ernesto enters "Bull Fighter Matador" as his | Submit |
| search, and then annotate any problems you think it might have. | 9 0 |
| | |
| | |
| | |
| *************************************** | *************************************** |



In order to incorporate the exploded search terms into the Risky Jobs application, we have to plug each of the terms into an SQL SELECT query using LIKE and OR. For example, here's what a query would look like for Ernesto's earlier search on "Bull Fighter Matador":

We're now searching the job description

```
instead of the title since the description
                                         has more information to match.
SELECT * FROM riskyjobs
  WHERE description LIKE '%Bull%' OR description LIKE '%Fighter%' OR
  description LIKE '%Matador%'
Now suppose we used the following PHP code to attempt to assemble this query from the search
data entered by the user into the Risky Jobs search form:
$search query = "SELECT * FROM riskyjobs";
$where clause = '';
$user search = $ GET['usersearch'];
                                                                    Each LIKE clause ends with
                                                                    an OR to link it with the
$search words = explode(' ', $user search);
                                                                    next one, which works great
                                                                    except for the very last one.
foreach ($search words as $word) (
  $where clause .= " description LIKE '%$word%' OR ";
                           Make sure the WHERE clause isn't empty
                           before appending it to the search query.
if (!empty($where clause)) (
  $search query .= " WHERE $where clause";
                                                             Danger! Your dream job is out there
Do you have the guts to go find it?
                   This operator concatenates one string
                    onto the end of another string.
                                                          Risky Jobs - Search
                                                          Find your risky job;
Write down the SQL query generated by this code
                                                          Bull Fighter Matado
when Ernesto enters "Bull Fighter Matador" as his
search, and then annotate any problems you think
it might have.
  SELECT * FROM riskyjobs
```

WHERE description LIKE "Bull" OR description LIKE "Fighter" OR

description LIKE 'Matador' (OR)

512

There's an extra OR at the end of

the query, which will make it fail!

implode() builds a string from substrings

What we really need to do is only put OR between the LIKEs in our WHERE clause, **but not after the last one.** So how exactly can that be done? How about a special case inside the loop to see if we're on the last search term, and then not include OR for that one? That would work but it's a little messy. A much cleaner solution involves a function that does the reverse of the explode() function. The implode() function takes an array of strings and builds a single string out of them.


This is the delimiter that is wedged between each of the strings when they are stuck together as one.

\$where_clause = implode(' OR', \$where_list);
The implode() function
 returns a single string.

But how does that help the dangling OR problem in our query? Well, implode() lets you specify a delimiter to stick between the strings when combining them together. If we use 'OR' as the delimiter, we can construct a WHERE clause that only has OR **between** each LIKE clause.

This must be an array of strings that you want to join together.

| Sharpen your pend | cil |
|---|---|
| | Rewrite the PHP code that generates the Risky Jobs ${\tt SELECT}$ query so that it fixes the dangling ${\tt OR}$ problem by using the implode function. |
| | |
| | ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| *************************************** | |




514 Chapter 9




Take the Risky Jobs search form for a spin.

Download the Risky Jobs application from the Head First Labs site at www.headfirstlabs.com/books/hfphp. The search.php script contains the query generation code you just worked through, and is used to process the search data entered into the form in the search.html page.


Upload the script and other Risky Jobs files to your web server, and then open the search form (search.html) in a web browser. Try a few different searches to see how your query generation code fares. Make sure to try Ernesto's "Bull Fighter Matador" search, which is a good test of the new implode () code.






| arpen your pencil | Write down the SQL query generated when Selma enters "tightrope, walker, circus" as her search, and then annotate any problems you think it might have. |
|---|---|
| *************************************** | |
| | |
| | |

517



I don't see what the big deal is. Just call the explode() function twice - first to get rid of spaces and then to get rid of commas.




The explode() function lets you explode a single string into substrings, but in this case we already have substrings.

The first call to the explode () function leaves us with **multiple strings** stored in an array, so there's isn't a single string left to explode. And attempting to explode each string in the array would likely just create more problems. Instead of trying to solve the delimiter problem with multiple calls to explode (), we need to **preprocess** the search string to get it down to a **single delimiter** before we ever even call explode (). Then it can do what it does best—break apart the string using one delimiter.

Preprocess the search string

We want to hand the explode() function a string that it can break apart cleanly in one shot. How do we do that? By making sure that explode() only has to worry with a single delimiter, such as a space character. This means we need to **preprocess** the search string so that each search term is separated by a space, even if the user entered commas.

Preprocessing data allows us to remove unwanted characters and make the data easier to process.



Dumb Questions

Can we use more than one character as the delimiter when exploding the search string?

A: Yes, you can specify any number of characters to serve as your delimiter, but that's not the same as specifying **different** delimiters, and won't solve our problem here.


If we used explode (', ', Suser_search) to break apart our string, it would use a combined comma and space as a delimiter, and would work if someone entered "tightrope, walker, circus". But it would fail if someone entered "tightrope walker circus". In that case, we'd be left with one long string—not good.

Q: Can we just delete the commas instead of turning them into spaces?

A: That will work only if users separate their search terms with both a comma and a space, which we can't count on. If we deleted commas, we'd run the risk of turning "tightrope,walker" into "tightropewalker", which probably wouldn't match anything in the Risky Jobs database.

Replace unwanted search characters

If you think about it, preprocessing the Risky Jobs search string is a lot like using find-and-replace in a word processor. In our case, we want to find commas and replace them with spaces. PHP's str_replace() lets you do just that by supplying it three parameters: the text you want to find, the text you want to replace it with, and the string you want to perform the find-and-replace on. Here's an example of str replace() in action:



But what about those commas in the search string? The str_replace () function works just as well at replacing individual characters:

After this code runs, the variable \$clean_string will contain the string "tightrope walker circus".



Do you see anything suspicious about the results of the str_replace() function? Do you think replacing commas with spaces will work like we want?



Given the PHP code below, show what the output of the \$search_words array will be for each of the following search strings. Make sure to write in data for the appropriate array elements, and scratch through elements if the \$search_words array ends up being shorter.

\$clean_search = str_replace(',', ' ', \$user_search);
\$search_words = explode(' ', \$clean_search);

bull, matador cape



3 spaces! bull matador cape



bull , matador cape




2 spaces! bull, matador, cape



you are here >

521



So we're all set now that we're preprocessing the search string, right?



Uh, no. Preprocessing gets rid of unwanted characters, but unfortunately, it doesn't result in an array containing all good search terms.

Remember, our goal is to end up with a string where each search term is separated by exactly the same delimiter, a space. Take another look at what happened in the last three examples on the facing page. Some of the elements in the \$search_words array are empty. If we try to build our WHERE clause with the empty search elements, we might end up with something like this:

SELECT * FROM riskyjobs WHERE description LIKE '%bull%' OR description LIKE '%matador%' OR

description LIKE '% %' OR description LIKE '% %' OR

description LIKE '%cape%'

Those single spaces will match every single space in each job description. They are a real problem.

But those spaces won't match anything, right?

Wrong! They will match everything.

If there's a space anywhere in a job description (which is pretty much a given), this query will match it and return it as a result. So every job in the Risky Jobs database will be matched by this query. We need to get rid of those empty array elements before we construct the SQL query in order to make the search script useful again.




The query needs legit search terms

The good news it that it's not too difficult to clean up our search terms before using them in a query. We'll need to create a new array that only contains the real search terms. So we'll copy all the non-empty elements from our first array into the second array, and then use that array to construct the SELECT query.

To construct the new array, we can use a foreach loop to cycle through each element in the original array, and then use an if statement to find non-empty elements. When we find a non-empty element, we just add it to the new array. Here's what this process looks like:

Here's the original array that contains the search terms and empty elements caused by extra spaces.



524

Copy non-empty elements to a new array

Now let's look at the code that will copy the non-empty elements from our \$search words array to the new \$final search words array.

```
$search_query = "SELECT * FROM riskyjobs";

// Extract the search keywords into an array
$clean_search = str_replace(',', ' ', $user_search);
$search_words = explode(' ', $clean_search);

$final_search_words = array();

if (count($search_words as $word) {
   if (!empty($word)) {
        $final_search_words[] = $word;
        }

} Loop through each element of
        the *search_word array* If the
        element is not empty, put it in the
        array named *final_search_words.
```

After checking to make sure there is at least one search term in the \$search_words array, the foreach loop cycles through the array looking for non-empty elements. When it finds a non-empty element, it uses the [] operator to add the element onto the end of the \$final_search_words array. This is how the new array is assembled.

Then what? Well, then we generate the SELECT query just as before, except now we use the \$final_search_words array instead of \$search_words:

```
// Generate a WHERE clause using all of the search keywords
$where_list = array();
if (count($final_search_words) > 0) {
    foreach($final_search_words as $word) {
        $where_list[] = "description LIKE '%$word%'";
    }

but {
    final_search_words as $word);

    Swhere_clause = implode(' OR ', $where_list);

// Add the keyword WHERE clause to the search query
if (!empty($where_clause)) {
    $search_query .= "WHERE $where_clause";
}
```

This code gives us a search query that no longer has empty elements. Here's the new query for the search "bull, matador, cape":

```
SELECT * FROM riskyjobs
WHERE description LIKE '%bull%' OR
description LIKE '%matador%' OR
description LIKE '%cape%'
```

This is the same code you've seen that builds the WHERE clause of the search query, but this time it uses the new sfinal_search_words array that contains no empty elements.




Will this search give our users the results they're looking for?



Update the Search script to preprocess the user search string.

Update the search.php script to use the explode() and implode() functions to preprocess the user search string and generate a more robust SELECT query. Then upload the script to your web server and try out a few searches.



I'm getting job listings, but I'm getting huge descriptions for each job. I don't need that much information. I may have to try hazardpays.com, where they show only part of the job, and I can see more listings per page.



Although Risky Jobs is doing much better at finding jobs, the huge job descriptions are a bit much.

What's really irking Selma is her inability to see more job listings in her browser without doing a bunch of scrolling. It isn't necessary to show the entire description of each job in the search results. Ideally, we really need to show part of the description of each job, maybe just the first few sentences.


| Write down how you think we could trim the job descript so that they aren't quite so huge in the search results: | | | | | | |
|--|--------|--|--|--|--|--|
| | | | | | | |
| | •••••• | | | | | |
| | | | | | | |

Sometimes you just need part of a string

Since the lengths of the job descriptions in the Risky Jobs database vary quite a bit and some are quite long, we could clean up the search results by chopping all the descriptions down to a smaller size. And to keep from confusing users, we can just stick an ellipsis (...) on the end of each one to make it clear that they're seeing only part of each description.

The PHP substr() function is perfect for extracting part of a string. You pass the "substring" function the original string and two integers. The first integer is the index of where you want the substring to start, and the second integer is its length, in characters. Here's the syntax:


The PHP substr() function allows you to extract a portion of a string.




When it comes to the substr() function, you can think of a string as being like an array where each character is a different element. Consider the following string:

```
$job desc = 'Are you a practioner of the lost art of cat juggling? ';
```

Similar to elements in an array, each character in this string has an index, starting at 0 and counting up until the end of the string.




We can use these character indexes with the substr () function to grab portions of the string:



Extract substrings from either end

The substr() function is not limited to grabbing substrings from the start of a string. You can also extract characters starting from the end of a string. The extraction still works left to right; you just use a negative index to identify the start of the substring.



Here are a couple of examples:

```
Start at -9 and take

Start at -9 and take

Start of the string.

Start at -9 and take

Substr ($job_desc, -9)

juggling?
```

Sharpen your pencil

Below is PHP code that generates an HTML table for the Risky Jobs search results. Finish the missing code, whose task is to limit the job description text to 100 characters, and also trim down the date posted text to only show the month, day, and year.

Sharpen your pencil Solution

Below is PHP code that generates an HTML table for the Risky Jobs search results. Finish the missing code, whose task is to limit the job description text to 100 characters, and also trim down the date posted text to only show the month, day, and year.



Geek Bits

It's possible to skip the PHP substr () function and limit the job description data in the SQL query itself. You use a very similar MySQL function called SUBSTRING () that accepts the same arguments as substr(). The only difference is that the starting index starts at 1 instead of 0. So grabbing the first 100 characters of the job description looks like this:

SELECT SUBSTRING(job_description, 1, 100) FROM riskyjobs;

The advantage of sticking with the PHP function is that we have both the partial job description and the full job description available to us. If we use MySQL, we only get the partial job description, and would have to make another query to get the full description.

Dumb Questions

Q: Does substr () work on numeric values?

A: No, it operates strictly on strings. However, If you have a number stored as a CHAR, VARCHAR, or TEXT, when you retrieve it via SQL, it's treated by PHP as a string, not a number, so you can use a substr() function on it.

Q: What if your length value is longer than the string? Will it return a string with spaces at the end to make it match the length value?


A: It will return the entire string. But it won't pad the end of the string with spaces to change the length. For example, the following code will return the string "dog": substr('dog', 0, 10)

530



Tweak the Search script to limit the text displayed for job descriptions and dates posted.

Modify the search.php script so that it uses the PHP substr() function to trim down the job description and date posted text for the search results. Then upload the script to your web server and test it out with a few searches.






How can we change the page layout and query to allow us to sort by date posted, state, or job title?

Multiple queries can sort our results

In order to allow visitors to sort their search results, we need a way for them to identify how they want their results ordered. Maybe a form... or a button? It's actually way simpler than that. We can use HTML to turn each of the column headings in the search result table into links. Users can click a link to indicate which column they want to sort the results by.



We can use these links to reload the same Search script but with a query that sorts the results according to the link clicked. We already know how to use ORDER BY to structure a query with sorted results. If we create different SQL queries to ORDER BY each individual column, we can allow the user to sort the search results alphabetically by job title, description, or state, or chronologically by date posted.

Here is the SQL query to sort results alphabetically by job description:

```
SELECT * FROM riskyjobs

WHERE description LIKE '%Bull%' OR description LIKE '%Fighter%' OR description LIKE '%Matador%'

ORDER BY description

This sorts the results of the query on job descriptions in ascending alphabetical order.
```

| _ Sharpen your | pencil | | | |
|----------------|---|--|--|--|
| | Write three different queries that sort the Risky Jobs results according to job title, state, and date posted. Assume the user has typed in the search string "window, washer, skyscraper". | | | |
| | | | | |
| | | | | |
| | | | | |
| | •••••••••••••••••••••••••••••••• | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | How could we rewrite these queries if you wanted to see the job titles and states in reverse order? What about the newest jobs first? | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| 90 | olution | Write three different queries that sort the Risky Jobs results according to job title, state, and date posted. Assume the user has typed in the search string "window, washer, skyscraper". | | |
|--------------------------------|---|---|--|--|
| | SELECT * | FROM riskyjobs | | |
| | WHERE d | escription LIKE '%window%' OR description LIKE '%washer%' OR n LIKE '%skyscraper%' | | |
| | | Yjob_title | | |
| 10-110 | | | | |
| ne default for RDER BY is | SELECT * | FROM riskyjobs | | |
| SCending order, which | WHERE description LIKE '%window%' OR description LIKE '%washer%' OR | | | |
| the same as saying | description LIKE '%skyscraper%' | | | |
| RDER job_title ASC. | ARDER BY 1-1 | | | |
| | | y state | | |
| | SELECT * | FROM riskyjobs | | |
| | WHERE description LIKE '%window%' OR description LIKE '%washer%' OR | | | |
| | | | | |
| | description LIKE '%skyscraper%' ORDER BY date_posted | | | |
| | UNDER D | y date posted | | |
| | | ve rewrite these queries if you wanted to see the job titles and states in er? What about the newest jobs first? | | |
| (| SELECT * | FROM riskyjobs | | |
| | WHERE description LIKE '%window%' OR description LIKE '%washer%' OR | | | |
| | descriptio | n LIKE '%skyscraper%' | | |
| We might want | ORDER B | y job_title DESC | | |
| these if we've | | | | |
| already ordered one of the | SELECT * | FROM riskyjobs | | |
| columns and the | WHERE d | escription LIKE '%window%' OR description LIKE '%washer%' OR | | |
| ser clicks on it | descriptio | n L KE '%skyscraper%' | | |
| again to reverse the order. | ORDER BY state DESC | | | |
| | | | | |
| | SELECT * | FROM riskyjobs | | |
| | WHERE description LIKE '%window%' OR description LIKE '%washer%' OR | | | |
| | ************** | | | |
| | descriptio | n LIKE '%skyseraper%' | | |

It seems like a lot of redundant code will be needed to generate all those queries. Can't we avoid having the same query generation code repeated three, or even six times?

Yes. While it's true that we'll need to run a different query when a user clicks a different link, it's possible construct a single query based on the link clicked.

The first time the results are displayed, no links have been clicked so we don't have to worry about sorting. We can just take the keywords submitted into our form and build a query without an ORDER BY. The results are displayed with clickable headings, each of which links back to the script, but with a different sort order. So each link consists of a URL with the original keywords and a parameter named sort that indicates which order the results should be in.

What would really help in pulling this off is if we create our very own custom function that takes information about how to sort the job data, and returns a string with the WHERE clause and ORDER BY in place. Our new custom function takes a look at the sort parameter to figure out how to sort the search results. Here are the steps the function has to follow:

- Preprocess the search keywords, and store them in an array.
- Optionally take a sort parameter that tells the function what column to sort by.
- Get rid of any empty search keywords.
- Create a WHERE clause containing all of the search keywords.
- 6 Check to see if the sort parameter has a value. If it does, tack on an ORDER BY clause.
- 6 Return the newly formed query.


This might look like a lot of work, but we already have most of the code written. We just need to turn it into a function. But before we do that, let's take a look at how to put together custom functions...

Functions let you reuse code


A **function** is a block of code separate from the rest of your code that you can execute wherever you want in your script. Until now, you've used **built-in functions** that PHP has already created. explode(), substr(), and mysqli_query() are all functions that are predefined by PHP and can be used in any script.

But you can also write your own **custom functions** to provide features not supplied by the language. By creating a custom function, you can use your own code again and again without repeating it in your script. Instead, you just call the function by name when you want to run its code.

Following is an example of a custom function called replace_ commas () that replaces commas with spaces in a string: Custom functions allow you to organize a chunk of PHP code by name so that it can be easily reused.




When you're ready to use a custom function, just call it by name and enter any values that it expects in parentheses. If the function is designed to return a value, you can assign it to a new variable, like this:



Build a query with a custom function

We've already written much of the code we need to create the custom function that generates a Risky Jobs search query. All that's left is dropping the code into a PHP function skeleton. Here's the custom build We're passing into the function query() function: the fuser search array we created from the data entered into the search form. function build query(\$user search) \$search query = "SELECT * FROM riskyjobs"; // Extract the search keywords into an array \$clean search = str replace(',', ' ', \$user search); \$search words = explode(' ', \$clean search); \$final search words = array(); if (count (\$search words) > 0) { foreach (\$search_words as \$word) { if (!empty(\$word)) (\$final search words[] = \$word; Nothing new inside the function // Generate a WHERE clause using all of the search keywords \$where list = array(); if (count (\$final search words) > 0) (foreach (\$final search words as \$word) { \$where list[] = "description LIKE '%\$word%'"; \$where_clause = implode(' OR ', \$where_list); // Add the keyword WHERE clause to the search query if (!empty(\$where clause)) { \$search query .= " WHERE \$where clause"; Actually, this is new. Here's where we return \$search query; return the new query so the code that called the function can use it

The build_query() function returns a complete SQL query based on the search string passed into it via the <code>\$user_search</code> argument. To use the function, we just pass along the search data entered by the user, and then store the result in a new string that we'll call <code>\$search</code> query:





Custom Functions Exposed

This week's interview: Custom functions: how custom are they really?

Head First: Look, we're all wondering one thing: what's so wrong with redundant code? I mean really, it's easy to create, you just copy and paste and boom. You're done.

Custom Function: Oh, don't get me started about redundant code. It's just plain ugly and makes your code more difficult to read. That's bad enough. But there is a much much more important reason to avoid redundant code.

Head First: Yes?

Custom Function: Well, what if something changes in your code? That happens pretty often.

Head First: So what? Things change all the time. You just go in and you fix it.

Custom Function: But what if the thing that changed was in your redundant code? And was in five, or maybe ten places throughout your application?

Head First: I don't see a problem. You'd just find them and change them all. Done.

Custom Function: Fine, okay. But what if you missed changing it in one place? You're only human, you programmers. If you missed it, you might have a very tough time tracking it down.

Head First: Sure, I guess that could happen. But how do you help?

Custom Function: Ah, but that's the beauty that is me. If that code had been in a function, you could have changed it once. Just once. Bim bam boom and done.

Head First: I have to admit, that's pretty compelling. But I still don't see why I should go out of my way to use you. I mean, you're pretty limited, right? You can only use strings.

Custom Function: Whoa! Wait a sec there, buckaroo! I can take any data type you care to send me. As long as the code inside me handles that data the way it should, I can use any data you want me to. Heck, I used an array in that last example. That's pretty darn sophisticated, I'd say.

Head First: But you returned a string.

Custom Function: I can return whatever you want. It's all about making the most of what I offer and using me correctly.

Head First: That's another thing. You're so demanding. You have to have data passed in.

Custom Function: Where are you getting these crazy ideas? You can call me with no variables if you want, and if I'm set up that way. If you don't want to send me data, don't write any variables in the parentheses next to my name when you create me. Although I can't think of many reasons why you wouldn't want to pass data to me. And get data back out again with a return statement.

Head First: We're all out of time. Thanks for the time.

Custom Function: Don't mention it. I live to serve. Or is that serve to live? Or serve liver? Something like that.

538



Modify the Search script to use the build query () function.

Create the new build_query() function in the search.php script, making sure to replace the original code with a call to the new function. Upload the script to your web server and try out a search in a web browser to make sure it works OK.

That new custom build_query() function is cool, but it doesn't yet sort the search results. Could we add in another parameter that does that?



Absolutely. We can pass the build_query() function two parameters instead of just one.

We're already passing the function the <code>\$user_search</code> argument, which contains the user's search terms. Now we need another argument, <code>\$sort</code>, that indicates how to sort the data. The new <code>\$sort</code> argument needs to control the order of data returned by the query in the six ways we came up with back on page 535: sorting by the <code>job_title</code>, <code>state</code>, and <code>date_posted</code> columns of the <code>riskyjobs</code> table in <code>both</code> ascending and descending order.

We could store the actual ORDER BY strings in \$sort to indicate the sort order. Or we could use the numbers 1 through 6 to represent each of the sorts, like this:

\$sort == 1 ■ ORDER BY job title

\$sort == 2 ➡ ORDER BY job title DESC

\$sort == 3 ■ ORDER BY state

\$sort == 4 → ORDER BY state DESC

\$sort == 5 ■ ORDER BY date_posted

\$sort == 6 → ORDER BY date posted DESC

We just arbitrarily chose these numbers and the meaning that each one has. There are no special rules about it other than to use them consistently.

But aren't integers more cryptic when reading through your code? Without helpful comments, yes, but there's a more important reason to go with integers here. If we used ORDER BY strings, our data would show up in the URL of the script as part of each heading link. This would inadvertently reveal our table's column names, which you'd rather not make public for security reasons.

There's not much point in sorting by job description, as alphabetical order doesn't mean much there.

▶ 539

0

OK, I get how the new \$sort argument works, but how do we know which value for \$sort to pass into our function? Doesn't the user have to tell us that?

Yes, users must specify how to sort the search results, just as they specify the search terms themselves.

The good news is we already know how we want to implement this functionality: we're going to turn the column headings on our results page into hyperlinks. When a user clicks on a given heading, like "State," we'll pass the number for sorting by state into our build query () function.

But we still have to get the sort order from the link to the script. We can do this when generating custom links for the headings by tacking on a sort parameter to the URL:

The search results are generated as part of an HTML table, which is why there's a tag here.

We want to reload the page when users click a column heading to sort results, so we make this a self-referencing form.


\$sort links .= '<a href = "' . \$ SERVER['PHP SELF'] .

'?usersearch=' . \$user search . '&sort=3">State';

Our build query() function needs the user's search keywords to display results, so we pass that in the URL

We pass along sort data to indicate the desired sorting of the search. Since this is the state link, "sort" is equal to 3.

When the results page is generated, each heading link (except "Job Description") has its own customized URL, including a sort value for how the results should be sorted.



Hmm. I see how those links work for the first three queries, but what about the other three ORDER BYs that sort in descending order? Where do they go?



Joe: Normally, the same heading would allow the user to sort in either ascending or descending order.

Jill: That's right. Each time they click a heading it just reverses the order.

Frank: Doesn't that mean we now have to somehow keep up with the state of the headings each time the user clicks them because they now have to link differently depending on what link they currently hold.

Joe: I don't see what you mean.

Frank: Well, the headings don't always do the same sort. For example, if you click the "Job Title" heading and it sorts the results by ascending job titles, then the link must change to now sort on descending job titles the next time it is clicked.

Jill: That's right. But keep in mind that each type of sort has a number in the link URL to let the script know what kind of sort to carry out. And since we're generating those links, we can control exactly what sort numbers get put in them.

Joe: I see. So the challenge for us is to somehow structure our code to be able to generate the correct link based on the current state of the sort, right?

Frank: Ah, I've got it! Isn't that something we can solve with a few if statements? I mean, that's the kind of decision making they're good for, right?

Joe: Yes, that would work but we're talking about several decisions involving the exact same piece of data, the sort type. It would really be nice if we could come up with a better way to make those decisions other than a bunch of nested if-else statements.

Jill: That's a great point, and it's a perfect opportunity to try out a new statement I heard about. The switch statement lets you make multiple decisions, way more than two, based solely on a single value.

Frank: That sounds great. Let's give it a try.

Joe: I agree. Anything to avoid complicated if-else statements. Those things give me a headache!

Jill: Yeah, me too. I think the switch statement might just be the ticket...

542

Chapter 9

SWITCH makes far more decisions than IF

The switch statement offers an efficient way to check a value and execute one of several different blocks of code depending on that value. This is something that would require a small army of if-else statements, especially in situations involving quite a few options.

Instead of writing nested if-else statements to check for each possible value, you instead write a switch statement that has a case label corresponding to each possible value. At the end of each case label, you put the statement break;, which instructs PHP to drop out of the entire switch statement and not consider any other cases. This ensures that PHP will execute the code in no more than one case.

Let's take a look at an example that uses switch:

A SWITCH statement contains a series of CASE labels that execute different code blocks depending on the value of a variable.

```
This is the value the switch
                                        statement is checking - it
switch ($benefit code) {
                                        controls the entire switch.
case 1:
  $benefits = 'Major medical, 10 sick days';
                                                                  This code is only
  break; The break statement tells PHP to drop out of
                                                               - executed when
                                                                  Ebenefit code is 1.
case 2:
  $benefits = 'Death and dismemberment only, one month paid leave';
  break;
                         If you need to do the same thing for two or more values, just leave off the break statement until you reach the last value.
case 3:
case 4:
  $benefits = 'Good luck!';
                                 Any values stored in sbenefit code
  break;
                               other than 1, 2, 3, or 4 will cause the default code to execute.
default:
  $benefits = 'None.';
echo 'We offer four comprehensive benefits packages';
echo 'The plan you have selected: ' . $benefits;
                        Not really. There are only three
                        packages since 3 and 4 are both the
                        same thanks to 3 not having a break
```



Risky Jobs has a new function called <code>generate_sort_links()</code> that allows users to sort search results by clicking on the result headings. Unfortunately, it's missing some important code. Finish the code for the function. And don't forget the numbers for each search type:

1 = ascending job title, 2 = descending job title, 3 = ascending state, 4 = descending state,

5 = ascending date posted, and 6 = descending date posted.

```
generate_sort_links($user_search, $sort) {
  $sort links = '';
 .....($sort)
    $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
     '&sort= ......">Job Title</a>Ctd>Description':
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .</pre>
     '&sort= ......">State</a>';
    $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
      '&sort= ......">Date Posted</a>';
   ......
  case 3:
    $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
     '&sort= ____">Job Title</a>td>Description':
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .</pre>
     '&sort= .....">State</a>';
    $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
      '&sort= ____">Date Posted</a>';
   ......
  case 5:
    $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= ......">Job Title</a>Description':
   $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
     '&sort= ......">State</a>';
    $sort_links .= '<a href = "' . $ SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
      '&sort= ">Date Posted</a>';
   ......
   $sort_links .= '<a href = "' . $_SERVER['FHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= ____">Job Title</a>Description':
    $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
     '&sort= ">State</a>';
   $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
     '&sort= ">Date Posted</a>';
                                       ____ This is the default set of headings that should
                                             appear when the user hasn't chosen a sort method.
  rsturn ....;
```



Risky Jobs has a new function called generate_sort_links() that allows users to sort search results by clicking on the result headings. Unfortunately, it's missing some important code. Finish the code for the function. And don't forget the numbers for each search type:

1 = ascending job title, 2 = descending job title, 3 = ascending state, 4 = descending state,

5 = ascending date posted, and 6 = descending date posted.

```
function generate_sort_links($user_search, $sort) {
  $sort links = '';
                               If fort is I, it means we've already

    sorted by job title, so now we need
to re-sort it in descending order.

 switch ($sort) {
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= 2 ">Job Title</a>Ctd>Description':
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .</pre>
     '&sort= 3 ... ">State</a>';
    $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= 5 ">Date Posted</a>';
   break;
  case 3:
   $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
     '&sort= / ">Job Title</a>Description':
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= 4 ... ">State</a>';
    $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user_search .
      '&sort= 3 ">Date Posted</a>';
   break;
  case 5:
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user search .
      '&sort= .....">Job Title</a>Description':
   $sort links .= '<a href = "' . $ SERVER['PHP SELF'] . '?usersearch=' . $user search .
     '&sort= 3 ... ">State</a>';
   $sort_links .= '<a href = "' . $ SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= b ">Date Posted</a>';
   break;
  default:
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= / ">Job Title</a>Description':
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= 3 ">State</a>';
   $sort_links .= '<a href = "' . $_SERVER['PHP_SELF'] . '?usersearch=' . $user_search .
     '&sort= 5 ">Date Posted</a>';
                                        If fort hasn't been set yet or if it's 2,
                                        4, or 6, we should display the original links
  return fort links ;
                                        that sort the data in ascending order
```

Give build_query() the ability to sort

We now have two functions to handle Risky Jobs searches. build_ query() constructs an SQL query based on search terms entered by the user, and generate_sort_links() generates hyperlinks for the search result headings that allow the user to sort the results. But build_query() isn't quite finished since the query it generates doesn't yet sort. The function needs to append an ORDER_BY clause to the query. But it has to be the correct ORDER_BY clause, as determined by a new \$sort argument:


```
We're now passing in the foort
                                                       argument to our function, in
function build query ($user search, $sort) {
                                                       addition to fuser search.
  $search query = "SELECT * FROM riskyjobs";
  // Add the keyword WHERE clause to the search query
  if (!empty($where clause)) {
    $search query .= " WHERE $where clause";
  // Sort the search query using the sort setting
  switch ($sort) {
  // Ascending by job title
  case 1:
                                                                      - Here are the code additions
   $search query .= " ORDER BY title";
                                                                        to build query(). This
  // Descending by job title
                                                                        switch statement checks
  case 2:
                                                                       the value of fort and adds
   $search query .= " ORDER BY title DESC";
                                                                       the corresponding ORDER
  // Ascending by state
                                                                       by statement to the end of
  case 3:
                                                                       the search query.
   $search_query .= " ORDER BY state";
  // Descending by state
  case 4:
   $search query .= " ORDER BY state DESC";
  // Ascending by date posted (oldest first)
   $search query .= " ORDER BY date posted";
                                                                         When users load the results
  // Descending by date posted (newest first)
  case 6:
                                                                         page without clicking a
   $search query .= " ORDER BY date posted DESC";
                                                                         column heading, foot will be
   break;
                                                                         empty, so as a default we
  default:
    // No sort setting provided, so don't sort the query 4
                                                                         won't sort the results at all.
  return $search query;
                                  We return frearch query as before, only this time with an ORDER BY clause at the end.
```



Revamp the Search script to use the two new custom functions.

Create the new generate_sort_links() function in the search.php script, and then add the new code to the build_query() function so that it generates a query with sorted results. Don't forget to actually call the generate_sort_links() function in the script in place of the code that echoes the result headings.

Upload the script to your web server, open the search.html page in a browser, and try doing a search. Now click the headings above the search results to sort the jobs based on the different data. Make sure to click the same heading more than once to swap between ascending and descending order.



But sometimes I try a broader search and the results are overwhelming.



Risky Jobs - Search



Danger! Your dream job is out there.
Do you have the guts to go find it?

Risky Jobs - Search Results

This is an awful lot of job listings to try and take in at once.

| | | State | Date Posted |
|----------------------------|--|----------|-------------|
| Job Title | Description | NM | 2008-07-24 |
| Custard Walker | We need people willing to test the theory that you can walk on custard. We're going to fill a swi | 7.700 | 2008-04-28 |
| Shark Trainer | Training sharks to do cute tricks for the audiences at eu- new water theme park. You'll spend tim | | 2008-06-28 |
| Voltage Checker | You'll be out in the field checking a.c. and d.c. voltage in the range of 3 to 250 or more volts. Y | | 2008-09-04 |
| Antenna Installer | You'll be installing antennas and other metallic | FL | 2008-07-29 |
| Elephant Proctologist | Needed: experienced proctologist willing to work will | | 2008-07-27 |
| Airplane Engine Cleaner | Jet airplanes needing engines cleaned. In need of clean- minded individuals willing to handle rust an | | 2008-03-11 |
| Matador | Bustling dairy farm looking for part-time matador to entertain spirited bull with mild case of ADD | VT CA | 2008-03-24 |
| Paparazzo | Top celebrity photography firm looking for seasoned | | 2008-11-14 |
| Tightrope Walker | Fledgling big top looking for three-ring professional | | 2008-07-14 |
| M | D. Jave animals and hate plaque? Well, then the | s FL | |
| ER | fresh new faces. Full health insurance provided. Must love kids | NY | 2008-11-02 |
| avoid having I | and any met found tautes | мо | 2008-11-09 |
| a cinala naga | mest intro- | nt ID | 2008-11-14 |

How do other sites avoid having lots of search results on a single page?

Tonk needs an experienced electric bull NJ ides (after you fix it) and hal... The City of Dataville is hiring firefighters. No experienced required - you will be trained. Non-uno 2008-05-22 OH Firefighter 2008-11-14 Up and coming super fly gnat weight boxer needs an opponent to help build his winning record. Slow f... MO. Prize Fighter Are you a practitioner of the lost art of cat juggling? Banned in forty countries, only the Jim Ruiz... 2008-11-14 AZ Master Cat Juggler 2008-11-14 Tithe thought of dangling for hours on end from great

waiting for your superior non-violent ID tills. Must pass basic bull fighti...

2008-11-14

2008-07-27

We can paginate our results

We're displaying all of our results on a single page right now, which is a problem when a search matches lots of jobs. Instead of forcing users to scroll up and down a huge page to see all the job matches, we can use a technique called **pagination** to display the search results. When you paginate results, you break the collection of job matches into groups, and then display each group on a separate web page, like this:

Each page shows five results, along with links to access the other pages of results. Users can easily click through each page and avoid having to scroll.



Pagination breaks query results into sets, and displays each set on its own web page.

We need a query that will return just a subset of the results, not all of them.


Luckily, SQL already gives us a way to do that: the LIMIT clause. Let's revisit LIMIT and see how we can use it to split our results up into groups of five...



548

Get only the rows you need with LIMIT

The key to controlling which rows we display on any given page is to add another clause to our search query, a LIMIT clause. To get a maximum of five rows, we add LIMIT 5 to the end of our query, like this:



matches are actually found

Without a WHERE clause, this query returns all the jobs in the database, which is equivalent to searching with no search terms.

If you recall, we use the custom build_query() function to create our Risky Jobs query. To force it to only display the first five matches, we just concatenate LIMIT 5 to the end of the query string after it's built:

LIMIT controls what and how many rows are returned by an SQL query.

\$query = build_query(\$user_search, \$sort);

Adding a LIMIT clause to the end of a query limits the number of rows returned by the query, in this case to five rows.

This works well for getting the first five rows of results, but what about the next five rows, and the five rows after that? To pull out rows deeper in the result set, we have to change our LIMIT up a bit. But how? LIMIT 10 would get the first 10 rows, so that wouldn't work. We need to get rows 6 through 10, and to do that we use LIMIT with different syntax. When you add two arguments to LIMIT, the first arguments controls how many rows you skip, and the second argument controls how many rows you get back. For example, here's how you get rows 11 through 25, which would be the third page of results:

\$query = build_query(\$user_search, \$sort);

\$query = \$query . " LIMIT 10, 5";

The first argument tells

LIMIT how many rows
to skip - the first ten.

The second argument
controls how many rows
are returned - five,

Custard Walker Shark Trainer Voltage Checker Antenna Installer **Elephant Proctologist** Airplane Engine Cleaner Matador Paparazzo Tightrope Walker Crocodile Dentist Mime Pet Food Tester Toreador *** Electric Bull Repairer Firefighter


you are here >

same as earlier.

Control page links with LIMIT

An important part of pagination is providing links that allow the user to move back and forth among the different pages of results. We can use the LIMIT clause to set up the naviagation links for the bottom of each page of results. For example, the "next" and "previous" links each have their own LIMIT. The same thing applies to the numeric links that allow the user to jump straight to a specific page of results.

Here are the LIMIT clauses for the first three pages of search results, along with LIMITs for some of the page links:



Keep track of the pagination data

In order to add the new pagination functionality to build_query(), we need to set up and keep track of some variables that determine which search results to query and show on a given page. These variables are also important in determining how the navigation links at the bottom of the page are generated.

\$cur_page

Get the current page, \$cur_page, from the script URL via \$_GET. If no current page is passed through the URL, set \$cur_page to the first page (1).

\$results_per_page

This is the number of results per page, which you choose based on the look and feel of the page, and how many search results fit nicely on the page with the layout. This is where the second argument to the LIMIT clause comes from.

\$skip

Compute the number of rows to skip before the rows on the current page begin, \$skip. This variable is what controls where each page begins in terms of results, providing the first argument to the LIMIT clause.

\$total


Run a query that retrieves all the rows with no LIMIT, and then count the results and store it in \$total. In other words, this is the total number of search results.

\$num pages

Compute the number of pages, \$num_pages, using \$total divided by \$results_per_page. So for any given search, there is a total of \$total matching rows, but they are displayed a page at a time, with each page containing \$results_per_page matches. There are \$num_pages pages, and the current page is identified by \$cur_page.

Set up the pagination variables

Most of the pagination variables can be set up purely through information provided via the URL, which is accessible through the \$_GET superglobal. For example, the \$sort, \$user_search, and \$cur_page variables all flow directly from GET data. We can then use these variables to calculate how many rows to skip to get to the first row of data, \$skip. The \$results_per_page variable is a little different in that we just set it to however many search results we want to appear on each page, which is more of a personal preference given the layout of the results page.



We're still missing a couple of important variables: \$total and \$num_pages. These variables can only be set after performing an initial query to find out how many matches are found in the database. Once we know how many matches we have, it's possible to set these variables and then LIMIT the results...

Revise the query for paginated results

Now that we've got our variables set up, we need to revise the Search script so that instead of querying for all results, it queries for just the subset of results we need for the page the user is currently viewing. This involves first doing a query so that the \$total variable can be set and the \$num_pages variable can be calculated. Then we follow up with a second query that uses \$skip and \$results_per_page to generate a LIMIT clause that we add to the end of the query. Here's the revised section of the search.php script with these new additions highlighted:

```
mysali_num_rows() returns a
               count of how many total rows
               were returned by the query.
         This query retrieves all
         the rows with no LIMIT.
                                          Store away the total number
// Query to get the total results
                                          of rows with a call to the
$query = build query($user Search, $sort);
                                          mysali_num_rows() function.
$result = mysqli_quepy($dbc, $query);
                                                     Compute number of pages by dividing the total
                                                     number of rows by the number of results per
$total = mysqli num rows($result);
                                                     page, and then rounding up the result
$num pages = ceil($total / $results per page);
                                                       The ceil() function rounds
                                                       a number up to the nearest
// Query again to get just the subset of results
                                                       integer - the "ceiling".
$query = $query . " LIMIT $skip, $results per page";
$result = mysqli query($dbc, $query);
                                                         and return
while ($row = mysqli \fetch array($result))
                                                        this many rows.
  echo '';
  echo '' , $row['title'] , '';
  echo '' . substr($row['description'], 0, 100) . '...';
  echo '' . $row['state'] . '';
  echo '' . substr($row['date posted'], 0, 10) . '';
  echo '';
                               Issue a second query, but
                               this time LIMIT the
                               results to the current page.
echo '';
```

Generate the page navigation links

So we've set up some variables and built a new SQL query that returns a subset of results for the page. All that's left to do is to generate the page navigation links for the bottom of the sarch results page: the "previous" link, numerical links for each page of results, and the "next" link. We already have all the information we need to put together the links. Let's go over it again to make sure it's clear how it will be used.

\$user search

Every page link still has to know what the user is actually searching for, so we have to pass along the search terms in each link URL.

\$num pages

We need to know how many pages there are in order to generate links for each of them.

\$cur_page

The page navigation links are entirely dependent on the current page, so it's very important that it get packaged into every link URL.

\$sort

The sort order also factors into the pagination links because the order has to be maintained or else the pagination wouldn't make any sense.

OK, we know what information we need in order to generate the page navigation links, so we're ready to crank out the PHP code to make it happen. This code could just be dropped into the search.php script, but what if we put it in its own custom function? That way the main script code that generates the search results can be much simpler, requiring only a single line of code to generate the page links—a call to to this new function, which we'll call generate_page_links().

The only catch is that we don't want this function to get called if there is only one page of results. So we need to do a check on the number of pages before calling the new generate_page_links() function. Here's how we can perform the check and call the function, making sure to pass along the required information as function arguments:

if (\$num_pages > 1) {

// echo generate_page_links(\$user_search, \$sort, \$cur_page, \$num_pages);

// First check to make sure there is

Pass along the search

First check to make sure there is more than one page of search results; otherwise, don't generate the page links. Pass along the search string, sort order, current page, and total number of pages to use in generating the page links.



PHP & MySQL Magnets

The generate_page_links () function is almost finished, but it's missing a few pieces of code. Use the magnets to plug in the missing code and give Risky Jobs the ability to generate page navigation links.

```
function generate page links ($user search, $sort, $cur page, $num pages) (
                $page links = '';
                // If this page is not the first page, generate the "previous" link
                if (
                    ......
                  $page links .= '<a href="' . $ SERVER['PHP SELF'] .</pre>
                    '?usersearch=' . $user search .
                    '&sort=' . $sort .
                    '&page=' . ( ) . '"><-</a> ';
                spage_links .= '<- '; as a left arrow, as in "<-"
                // Loop through the pages generating the page number links
                for ($i = 1; $i <= $num pages; $i++) {
                  if (_____) (
                    $page links .= ' ' . $i;
                  else (
                    $page_links .= ' <a href="' . $ SERVER['PHP_SELF'] .</pre>
$cur page
                      '?usersearch=' . $user search .
                      '&sort=' . $sort .
  $cur page
                      '&page=' . $i . '"> ' . $i . '</a>';
$cur page
 $cur page
                // If this page is not the last page, generate the "next" link
                   ......
                  $page links .= ' <a href="" . $ SERVER['PHP SELF'] .</pre>
                    '?usersearch=' . $user search .
                    '&sort=' . $sort .
                    '&page=' . ($cur_page + 1) . '">-></a>';
                else (
                 Spage_links .= ' ->'; The "next" link appears as a right arrow, as in "->".
$num_pages
                return $page_links;
```



PHP & MySQL Magnets Solution

The generate_page_links () function is almost finished, but it's missing a few pieces of code. Use the magnets to plug in the missing code and give Risky Jobs the ability to generate page navigation links.

```
function generate page links ($user search, $sort, $cur page, $num pages) [
  Spage links = '';
  // If this page is not the first page, generate the "Previous" link
         $cur page
    $page links .= '<a href="' . $ SERVER['PHP SELF'] .</pre>
                                                                 We still have to pass
      '?usersearch=' . $user search
                                                                along the user search
      '&sort=' . $sort .
                                                                 data and the sort
                      $cur page
                                  The "previous" link appears
  else (
  // Loop through the pages generating the page number links
  for ($i = 1; $i <= $num pages; $i++) {
           $cur_page
                                                      Make sure each page link points
                                                       back to the same script - we're
      $page links .= ' ' . $i;
                                                      just passing a different page
                                                      number with each link.
    else (
      $page links .= ' <a href="" . $ SERVER['PHP SELF'] .</pre>
         '?usersearch=' . $user_search .
         '&sort=' . $sort .
         '&page=' . $i . '"> ' . $i . '</a>';
                                                   specific page is just the page number.
  // If this page is not the last page, generate the "Next" link
        $cur page
                          $num_pages
    $page links .= ' <a href="" . $ SERVER['PHP SELF'] .</pre>
      '?usersearch=' . $user search .
      '&sort=' . $sort .
      '&page=' . ($cur_page + 1) . '">-></a>';
    $page links .=
                                The "next" link appears as
                                a right arrow, as in "->".
  return $page_links;
```

Putting together the complete Search script

And finally we arrive at a complete Risky Jobs Search script that displays the appropriate search results based on the user's search terms, generates clickable result heading links for sorting, paginates those results, and generates page navigation links along the bottom of the page.

```
<?php
  // This function builds a search query from the search keywords and sort setting
  function build query($user search, $sort) {
                                        We've already built these functions,
                                        so there's no need to rehash every
    return $search query;
                                        line of their code here
  // This function builds heading links based on the specified sort setting
  function generate_somt_links($user_search, $sort) (
    return $sort links;
  // This function builds navigational page links based on the current page and
  // the number of pages
  function generate page links ($user_search, $sort, $cur_page, $num_pages) {
                                         Grab the sort order and search
string that were passed through
the URL as GET data.
    return $page links;
  // Grab the sort setting and search keywords from the URL using GET
  $sort = $ GET['sort']; &
                                                             Initialize the pagination variables
  $user search = $ GET['usersearch'];
                                                              since we'll need them in a moment
  // Calculate pagination information
                                                              to LIMIT the query and build the
  $cur_page = isset($ GET['page']) ? $ GET['page'] : 1;
                                                              pagination links.
  $results per page = 5; // number of results per page
  $skip = (($cur page - 1) * $results per page);
  // Start generating the table of results
  echo '';
                                                  Call the generate sort links()
                                                  function to create the links for the
  // Generate the search result headings
                                                  result headings, and then echo them.
  echo '';
  echo generate sort links ($user search, $sort);
  echo '';
                                                         Hang on,
                                                         there's more
                                                                                    search.php
                                                                             you are here >
                                                                                              557
```

The complete Search script, continued...

```
// Connect to the database
require once ('connectvars.php');
$dbc = mysqli connect(DB HOST, DB USER, DB PASSWORD, DB NAME);
                                               Call the build query() to build
// Query to get the total results
                                               the SQL job search query.
$query = build query($user search, $sort);
$result = mysqli query($dbc, $query);
$total = mysqli num rows($result);
$num pages = ceil($total / $results per page);
                                                           Here's the LIMIT clause
// Query again to get just the subset of results
                                                          we created to query only a subset of job results.
$query = $query . " LIMIT $skip, $results per page";
$result = mysqli query($dbc, $query);
while ($row = mysqli fetch array($result)) {
 echo '';
 echo '' . $row['title'] . '';
 echo '' ...'; echo '' ...'; $row['description'], 0, 100) . '...'; echo '' ...';
                                         substr($row['date_posted'], 0, 10) . '';
 echo '' .
                                          And here's the code we wrote that trims down the job description and date posted
 echo '';
echo '';
// Generate navigational page links if we have more than one page
if ($num pages > 1) {
 echo generate page links ($user search, $sort, $cur page, $num pages);
                            - Call the generate_page_links()
mysqli_close($dbc);
                             function to generate the page
                             links, and then echo them.
              Keep things tidy by closing
              the database connection.
```

Dumb Questions

O: Do we really have to pass the search, sort, and pagination information into generate_page_links()?

A: Yes. And the reason has to do with the fact that well-designed functions shouldn't manipulate data outside of their own code. So a function should only access data passed to it in an argument, and then only make changes to data that it returns.

OK, so what about echoing data? Why doesn't generate page links () just echo the links?


A: Same problem. By echoing data to the browser, the function would be effectively reaching beyond itself to make a change somewhere else It's much harder to debug and maintain functions when it isn't clear what data they change. The solution is to always return the data affected by a function, and then do whatever you want with the data returned by the function, outside of the function.



Finish the Risky Jobs Search script.

Add the new generate_page_links () function to the search.php script, making sure to also add the code that calls it after checking to see if there is more than one page of results. Also create and initialize the variables used as arguments to the function. And don't forget to update the query code so that it uses LIMIT to pull out the correct subset of results for each page.

When all that's done, upload the new search.php script to your web server, and then open the search.html page in a web browser. Try a few searches, making sure to search on some terms that will end up with lots of results so that the new pagination features kick in. For maximum result pages, do a search with an empty search form.



you are here >

559

Your PHP & MySQL Toolbox

The Risky Jobs Search script required quite a few new PHP and MySQL techniques. Let's recap some of the most important ones.

LIKE

Use LIKE to look for data within an SQL query without necessarily requiring an identical match. Put a % in front of and/or after a search term to let LIKE know that the term can have other characters surrounding it.

explode(), implode()

The PHP explode() function breaks a string apart into an array of substrings that are separated by a common delimiter, such as a space or comma. implode() does the opposite — it builds a single string from an array of strings, inserting a delimiter between them.

str_replace()

Call this PHP function to do a find—and—replace on a string of text, replacing one character or sequence of characters with another.

switch-case

A PHP decision—making construct that allows you to execute one of many groups of code based on a single value. If you find yourself with a bunch of nested if—else statements, you may find that you can code it more efficiently as a switch statement.

substr()

This PHP function extracts a portion of a string based on arguments you supply it. You can grab the beginning of a string, the end of a string, or some piece in between.

Custom function

A chunk of PHP code organized into a named, reusable package. The idea is to isolate code that performs a certain task so that it can be reused with minimal effort and code duplication.

LIMIT

The LIMIT clause lets you control exactly how many rows are returned by an SQL query. Not only that, but LIMIT can skip rows in the result set, allowing you to isolate a subset of results.

10 regular expressions






String functions are kind of lovable. But at the same time, they're limited. Sure, they can tell the length of your string, truncate it, and change certain characters to other certain characters. But sometimes you need to break free and tackle more complex text manipulations. This is where regular expressions can help. They can precisely modify strings based on a set of rules rather than a single criterion.

Risky Jobs lets users submit resumes

Riskyjobs.biz has grown. The company now lets job seekers enter their resumes and contact information into a web form so that our Risky Jobs employers can find them more easily. Here's what the form looks like:





Below is some of the code for the registration.php script, which displays and processes the user data entered into the form to register a new job candidate. Annotate what you think is wrong with the code, and how it could be changed to resolve the bad data problem.

```
<?php
  if (isset($ POST['submit'])) {
    $first name = $ POST['firstname'];
    $last name = $ POST['lastname'];
    $email = $ POST['email'];
    $phone = $ POST['phone'];
    $job = $ POST['job'];
    $resume = $ POST['resume'];
    Soutput form = 'no';
    if (empty($first name)) {
      // $first name is blank
      echo 'You forgot to enter your first name.';
      $output form = 'yes';
    if (empty($last name)) {
      // $last name is blank
      echo 'You forgot to enter your last name.';
      $output form = 'yes';
    if (empty($email)) {
      // Semail is blank
      echo 'You forgot to enter your email address.';
      Soutput form = 'yes';
    if (empty($phone)) {
     // $phone is blank
      echo 'You forgot to enter your phone number.';
      $output form = 'yes';
               Continuing validating non-empty job and resume fields.
  else (
    Soutput form = 'yes';
  if ($output form == 'yes') (
... Show the form.
```



Below is some of the code for the registration.php script, which displays and processes the user data entered into the form to register a new job candidate. Annotate what you think is wrong with the code, and how it could be changed to resolve the bad data problem.

```
<?php
  if (isset($ POST['submit'])) {
                                                      The script checks for empty
    $first name = $ POST['firstname'];
                                                       form fields, which is good, but
    $last name = $ POST['lastname'];
                                                       some of the form fields have
    $email = $ POST['email'];
                                                       more specialized data that must
    $phone = $ POST['phone'];
    $job = $ POST['job'];
                                                       adhere to a certain format
    $resume = $ POST['resume'];
    Soutput form = 'no';
    if (empty($first name)) {
      // $first name is blank
      echo 'You forgot to enter your first name.';
      Soutput form = 'yes'; 7
                                       - There isn't much else we can
                                        check in regard to first and
                                        last names, so this code is fine.
    if (empty($last name)) {
      // $last name is blank
      echo 'You forgot to enter your last name.';
      Soutput form = 'yes';
                                     An email address has a very specific
                                     format that we should enforce before
                                     accepting form data from the user.
    if (empty(Semail))
      // $email is blank
      echo 'You forgot to enter your email address.';
      Soutput form = 'yes';
                                                          Four Fingers McGraw left a dot out
                                                          of his email address near the end - the
                                                          form should catch those kind of errors!
    if (empty($phone)) {
      // $phone is blank
      echo 'You forgot to enter your phone number.';
      Soutput form = 'yes';
                                                            Same thing with a phone number - the
                                                             user's form submission shouldn't be allowed
                 . Continuing validating non-empty job and resume fields.
                                                             unless we can be certain that their phone
                                                             number is in the correct format
  else (
                                      Jimmy Swift
    Soutput form = 'yes';
                                       didn't provide an
                                                            What we really need is a way to verify
                                       area code with
                                                            email addresses and phone numbers, the
                                       his phone number,
  if (Soutput form == 'yes') (
                                                            two fields in the form that have a
                                       which the form
                                                            specific format For the other fields it's
                                       should've demanded.
          - Show the form
                                                            OK to just make sure they aren't empty.
```

Why don't we use some string functions to fix the bad data? Can't we use str_replace() to add in the missing data?


0

You can fix some data with string functions but they don't help much when data must fit a very specific pattern.

String functions are well suited to simple find-and-replace operations. For example, if users submitted their phone numbers using dots to separate the blocks of digits instead of hyphens, we could easily write some str replace () code to substitute in hyphens in their place

But for anything that we can't possibly know, like the area code of Jimmy Swift's phone number, we need to ask the person who submitted the form to clarify. And the only way we can know that he's missing an area code is to understand the exact pattern of a phone number. What we really need is more advanced validation to ensure that things like phone numbers and email addresses are entered exactly right.

functions to do this validation?





Think about how you might attempt to validate an email address using string functions. PHP has a function called strlen() that will tell you how many characters are in a string. But there's no predefined character length for data like email addresses. Sure, this could potentially help with phone numbers because they often contain a consistent quantity of numbers, but you still have the potential dots, dashes, and parentheses to deal with.

Getting back to email addresses, their format is just too complex for string functions to be of much use. We're really looking for specific patterns of data here, which requires a validation strategy that can check user data against a pattern to see if it's legit. Modeling patterns for your form data is at the heart of this kind of validation.



Decide what your data should look like

Our challenge is to clearly specify exactly what a given piece of form data should look like, right down to every character. Consider Jimmy's phone number. It's pretty obvious to a human observer that his number is missing an area code. But form validation isn't carried out by humans; it's carried out by PHP code. This means we need to "teach" our code how to look at a string of data entered by the user and determine if it matches the pattern for a phone number.

Coming up with such a pattern can be a challenge, and it involves really thinking about the range of possibilities for a type of data. Phone numbers are fairly straightforward since they involve 10 digits with optional delimiters. Email addresses are a different story, but we'll worry about them a bit later in the chapter.

> It's easy for a human to look and see that Jimmy forgot his area code, but not so trivial making the same "observation" from PHP code.

First Name: Jimmy Last Name: Swift Email: JS@sim-u-duck.com

Phone: 636 4652 Desired Job: Ninja





there are no Dumb Questions

I'm still not sure I see why I can't just stick with isset () and empty () for our form validation.

A: These two functions will tell you whether or not someone who submitted a form put data in a text field, but they won't tell you anything about the actual data they entered. As far as the empty () function is concerned, there's absolutely no difference between a user entering "(707) 827-700" or "4FG8SXY12" into the phone number field in our form. This would be a huge problem for sites like Risky Jobs, which depends on reliable data to get in touch with job candidates.

Q: |fisset() and empty() won't work, can't we simply have someone check the data after it goes into the database?

A: You can, but by then it's often too late to fix the bad data. If a phone number is missing an area code, we need to ask the user to clarify things by resubmitting the data in that form field.

If you wait until later and check the data once it's already in the database, you may have no way of contacting the user to let them know that some of their data was invalid. And since the user probably won't realize they made a mistake, they won't know anything's wrong either.


So, the best plan of action is to validate the users form data immediately when they submit the form. That way you can display an error message and ask them to fill out the form again.

Q: So then how do you decide whether the data the user entered is valid or not?

A: That depends on what kind of data it is. Different types of information have different rules that they need to follow: what kind of characters they contain, how many characters they have, what order those characters are in. So you need to communicate those rules in your PHP code. Let's take a closer look at the rules governing phone numbers...

| Sharpen your pe | |
|---|---|
| | Write down all the different ways you can think of to represent a phone number. |
| | |
| | /************************************* |
| | |
| | |
| | |
| | |
| | *************************************** |
| | *************************************** |
| | |
| | |
| | What are some rules that are reasonable to expect your users to follow when |
| | filling out your form? For example, phone numbers should not contain letters. |
| Here's a rule to —— get you started. | We could insist on rules such as only digits and all 10 digits must be run together |
| | |
| | *************************************** |
| | |
| | |
| | |
| | |


you are here > 567



There are so many possible patterns. How can we make rules to cover all of them?

00

les to cover all of them?




First, they can't begin with 1 (long distance) or 0 (operator). Second, there should be 10 digits. And even though some people might have clever ways to represent their phone numbers with letters, phone numbers are esentially numbers—10 digits when we include an area code.

568

Formulate a pattern for phone numbers

To go beyond basic validation, such as empty() and isset(), we need to decide on a pattern that we want our data to match. In the case of a phone number, this means we need to commit to a single format that we expect to receive from the phone field in our form. Once we decide on a phone number format/pattern, we can validate against it.

Following is what is likely the most common phone number format in use today, at least for domestic U.S. phone numbers. Committing to this format means that if the phone number data users submit doesn't match this, the PHP script will reject the form and display an error message.



Dumb Questions

Q: Do I have to use that pattern for matching phone numbers?

A: That's what we're using for Risky Jobs because it's pretty standard, but when you're designing your own forms you should pick one that makes sense to you. Just keep in mind that the more commonly accepted the pattern is, the more likely users will follow it.

O: Couldn't I just tell users to enter a pattern like ######## and then use PHP's string functions to make sure the data contains 10 numeric characters?

A: You could, and that would be sufficient if that was the pattern your users expected. Unfortunately, it's not really a very good pattern because most people don't run their phone number together like that when filling out forms. It's a bit non-standard, which means users won't be used to it, and will be less likely to follow it.

Q: So? It's my pattern, I can do what I want, right?

A: Sure, but at the same time you want your users to have a good experience.

Otherwise they'll quit visiting your site.

OK, so couldn't I use three text fields for the phone number: one for area code, then three digits in the second, and then the last four digits in the third. Then I could use PHP's string functions.


A: Yes, you could, and some sites do that. But being able to match patterns gives you more flexibility. And matching patterns is useful for lots more things than just making sure your user enters the right pattern for a phone number, as you'll see later in this chapter.

you are here > 569

Match patterns with regular expressions

PHP offers a powerful way to create and match patterns in text. You can create rules that let you look for patterns in strings of text. These rules are referred to as **regular expressions**, or **regex** for short. A regular expression represents a pattern of characters to match. With the help of regular expressions, you can describe in your code the rules you want your strings to conform to in order for a match to occur.

As an example, here's a regular expression that looks for 10-digits in a row. This pattern will only match a string that consists of a 10 digit number. If the string is longer or shorter than that, it won't match. If the string contains anything but numbers, it won't match. Let's break it down.



There's also a more concise way of writing this same regular expression, which makes use of curly braces. Curly braces are used to indicate repetition:

This means the same thing as the pattern above. {10} is a

shorthand way to say 10 digits.

/^\d{10}\$/

Regular expressions are rules used to match patterns in one or more strings.

570

Yeah, regular expressions are really clear. About as clear as mud.



It's true, regular expressions are cryptic and often difficult to read... but they are very powerful.

Power often comes at a cost, and in the case of regular expressions, that cost is learning the cryptic syntax that goes into them. You won't become a master of regular expressions overnight, but the good news is you don't have to. You can do some amazingly powerful and useful things with regular expressions, especially when it comes to form field validation, with a very basic knowledge of regular expressions. Besides, the more you work with them and get practice breaking them down and parsing them, the easier they'll be to understand.

Build patterns using metacharacters

Being able to match digits in a text string using \d is pretty cool, but if that's all the functionality that regular expressions provided, their use would be sorely limited. Just matching digits isn't even going to be enough for Risky Jobs phone number validation functionality, as we're going to want to be able to match characters like spaces, hyphens, and even letters.

Luckily, PHP's regex functionality lets you use a bunch more special expressions like \d to match these things. These expressions are called **metacharacters**. Let's take a look at some of the most frequently used regex metacharacters.

Metacharacters let us describe patterns of text within a regular expression.

\d

As you saw on the previous page, this metacharacter looks for a digit. It will match any number from 0 to 9. Keep in mind, on its own, \d matches just one digit, so if you wanted to match a two-digit number, you'd need to use either \d\d or \d{2}.

\s

Looks for whitespace. This doesn't mean just the space character you get on the screen when you hit the Space bar; \s also matches a tab character, or a newline or carriage return. Again, keep in mind that \s will only match one of these characters at a time. If you wanted to match exactly two space characters in a row, you'd need to use \s\s or \s{2}.

The period metacharacter, matches any one character, except a newline. It'll match a letter or digit, just like \w, as well as a space or tab, like \s.

\w

Looks for any alphanumeric character—in other words, either a letter or a number. It will match one character from the following: a–z and A–z (both uppercase and lowercase letters), as well as 0–9 (just like \d).

We saw the caret metacharacter on the previous page as well. It looks for the beginning of a string, so you can use it to indicate that a match must happen at the start of a text string, rather than anywhere in the string. For example, the regex /^\d{3}/ will match the string "300 applications", but not the string "We received 300 applications".

S

Looks for the end of a string. You can use this metacharacter with ^ to bookend your match, specifying exactly where it will start and finish. For example, / ^\ w{5}\s\d{3}\$/ will match "Nanny 411", but not "Nanny 411 is great" or "Call Nanny 411".


These metacharacters are cool, but what if you really want a specific character in your regex? Just use that character in the expression. For example, if you wanted to match the exact phone number "707-827-7000", you would use the regex /707-827-7000/.



Match each different phone number regular expression with the phone number that it matches.

| Regex | String it matches |
|--------------------------|-------------------|
| /^\d{3}\s\d{7}\$/ | 5556364652 |
| /^\d{3}\s\d{3}\s\d{4}\$/ | 555 636 4652 |
| /^\d{3}\d{3}-\d{4}\$/ | 555636-4652 |
| /^\d{3}-\d{3}-\d{4}\$/ | 555 ME NINJA |
| /^\d{3}\s\w\w\s\w{5}\$/ | 555 6364652 |
| /^\d(10)\$/ | 555-636-4652 |

you are here ▶ 573



574 Chapter 10

BE the Regular Expression Your job is to play the role of regular expression, and either accept or reject phone numbers for Risky Jobs users. Check the

box of phone numbers that you deem valid, and leave the others unchecked. Annotate why any invalid numbers are invalid.

This is the phone number regular expression - be it!

/^\d{3}-\d{3}-\d{4}\$/



(555) 935-2659



(555)672-0953



555-343-8263



555-441-9005



555.903.6386



555-612-8527-8724

you are here >

575



BE the Regular Expression Solution Your job is to play the role of regular expression, and either accept or reject phone numbers for Risky Jobs users. Check the

box of phone numbers that you deem valid, and leave the others unchecked. Annotate why any invalid numbers are invalid.

This is the phone number regular expression - be it!

/^\d{3}-\d{3}-\d{4}\$/



Sometimes people add additional digits to their telephone numbers, like a four-digit extension at the end. Is there any way we can match these patterns, too?




Yes, but the key is to specify such a pattern as optional in your regular expression.

If we changed our regex to /^d{3}-\d{3}-\d{4}-d{4}\$, we'd be **requiring** our string to have a four-digit extension at the end, and we'd no longer match phone numbers like "555-636-4652". But we can use regular expressions to indicate that parts of the string are optional. Regexes support a feature called **quantifiers** that let you specify **how many times** characters or metacharacters should appear in a pattern. You've actually already seen quantifiers in action in regexes like this:

/^\d{10}\$/
This says "a digit should show up 10 times in a row."

Here, curly braces act as a quantifier to say how many times the preceding digit should appear. Let's take a look at some other frequently used quantifiers.



A quantifier specifies how many times a metacharacter should appear.

So, if we wanted to match those optional digits at the end of our phone number, we could use the following pattern:

you are here > 577

You forgot one thing.
U.S. phone numbers
can't begin with 0 or 1.



You're absolutely right. 0 connects you to an operator, and 1 dials long distance.

We simply want the area code and number. We need to make sure the first digit is not 1 or 0. And to do that, we need a **character class**.

Character classes let you match characters from a specific set of values. You can look for a range of digits with a character class. You can also look for a set of values. And you can add a caret to look for everything that **isn't** in the set.

To indicate that a bunch of characters or metacharacters belongs to a character class, all you need to do is surround them by square brackets, []. Let's take a look at a few examples of character classes in action:

[0-2]

This matches a range of numbers. It will match 0, 1, or 2.

[A-D]

This will match A, B, C, or D.

In a character class, the means "don't match".

[^b-f]

This carat has a different meaning when it's used inside a character class. Instead of saying, "the string must start with...", the caret means "match everything except..."

This will match everything except b, c, d, e, or f.


A character class is a set of rules for matching a single character.

| rite a regular expression that matches international pho | ne |
|--|----|
| umbers: | |
| | |
| | |
| | |

578

Fine-tune patterns with character classes

With the help of character classes, we can refine our regular expression for phone numbers so that it won't match invalid digit combinations. That way, if someone accidentally enters an area code that starts with 0 or 1, we can throw an error message. Here's what our new-and-improved regex looks like:



Dumb Questions

Q: So character classes let you specify a range of characters that will match the text string.

A: Yes, a character class lets you specify in your regular expression that any member of a specified set of characters will match the text string, instead of just one.

For example, the character class <code>[aeiou]</code> will match one instance of any lowercase vowel, and the class <code>[m-zM-Z]</code> will match one instance of any letter in the second half of the alphabet, lowercase or uppercase.

And the character class [0-9] is equivalent to the metacharacter \d , which is really just a shorthand way of saying the same thing.

O: Don't I need to put spaces or commas in between the characters or ranges I specify in character classes?

A: No, if you do that, those extra characters will be interpreted as part of the set of characters that should match the text string. For example, the character class

[m-z, M-Z]

would match not only uppercase and lowercase letters from m to z, but also a comma or space, which is probably not what you want.

What if I want to match a character in a character class more than once? Like one or more vowels consecutively.

A: Just add a quantifier after the character class. The expression / [aeiouAEIOU] + / will match one or more vowels in a row.

I thought quantifiers only applied to the character that immediately preceded them.

A: Usually that's the case, but if a quantifier directly follows a character class, it applies to the whole class.

And if you want to make a quantifier apply to a whole series of characters that aren't in a character class, you can surround these characters with parentheses to indicate that they should be grouped together. As an example, the regular expression / (hello) +/ will match one or more consecutive instances of the word "hello" in a text string.

Q: What if I wanted to match two different spellings of a word, like "ketchup" or "catsup"?

A: You can use the vertical-pipe character (|) in your regular expressions to indicate a set of options to choose from.

So, the regular expression / (ketchup | catsup | catchup) / will match any one of the three most common spelling variants of the

you are here ▶ 579

word.



What about putting characters like periods or question marks in a regular expression. If I type those in, won't PHP think they're metacharacters or quantifiers and screw up processing my regex?

If you want to use reserved characters in your regular expression, you need to escape them.

In regular expression syntax, there are a small set of characters that are given special meaning, because they are used to signify things like metacharacters, quantifiers, and character classes. These include the period (.), the question mark (?), the plus sign (+), the opening square bracket ([]), opening and closing parentheses, the caret (^), the dollar sign (\$), the vertical pipe character ([]), the backslash (\), the forward slash (/), and the asterisk (*).

If you want to use these characters in your regular expression to signify their literal meaning instead of the metacharacters or quantifiers they usually represent, you need to "escape" them by preceding them with a backslash.

For example, if you wanted to match parentheses in a phone number, you couldn't just do this:

These will simply be

Instead, both the opening and closing parentheses need to be preceded by backslashes to indicate that they should be interpreted as actual parentheses:

Now PHP knows that these are literal parentheses.

(555)636-4652 /^\(\\d{3}\\)\\d{3}-\\d{4}\$/

580



Come up with a string that will match each pattern shown.

$$/^([A-Z]\d){2}$$
\$/

Suppose we want to expand the Risky Jobs validation scheme for phone numbers to allow users to submit their numbers in a few more formats. Write a single regular expression that will match ALL of the following text strings, and won't allow a 0 or 1 as the first digit. Your pattern should only allow digits, parentheses, spaces, and dashes.


555-636-4652 555 636-4652 (555)-636-4652 (555) 636-4652



Come up with a string that will match each pattern shown.

String must
begin with...

3 through 6... and repeat that
character class
four times.




Any string that starts with four digits in the range 3, 4, 5, or 6 will match. These will all match: "5533", "3546 is a number.", "6533xyz"

Any string that starts with an uppercase letter and then a digit and then another uppercase letter and digit and then ends: "B5C9", "R2D2"

Suppose we want to expand the Risky Jobs validation scheme for phone numbers to allow users to submit their numbers in a few more formats. Write a single regular expression that will match ALL of the following text strings, and won't allow a 0 or 1 as the first digit. Your pattern should only allow digits, parentheses, spaces, and dashes.

555-636-4652 555 636-4652 (555)-636-4652 (555) 636-4652



582


I've pretty much had it with the bad data in the Risky Jobs resume bank. What good do these expressions do me if we don't use them in some way?




Risky Jobs needs to put regular expressions to work validating form data!

Check for patterns with preg_match()

We haven't been developing patterns just for the fun of it. You can use these patterns with the PHP function preg_match(). This function takes a regex pattern, just like those we've been building, and a text string. It returns false if there is no match, and true if there is.



Here's an example of the preg_match() function in action, using a regex that searches a text string for a four-character pattern of alternating uppercase letters and digits:



```
if (preg_match('/^\d{3}-\d{2}-\d{4}\$/', '555-02-9983')) {

echo 'Valid social security number.'; | If the match is successful, preg_match() returns true, which signifies to PHP that the condition is true. So, this code is run.

echo 'That social security number is invalid!';

If the match is not successful, preg_match() returns false, which makes the condition evaluate to false. So, this code is run.
```

what code will run.



Rewrite the highlighted portion of the Risky Jobs PHP script for checking the Registration form data below to validate the text entered into the phone field using $preg_match()$ instead of empty(). Use the regex you created earlier in the $preg_match()$ function.

| if (empty(\$phone)) { |
|--|
| // \$phone is blank |
| echo 'Your phone number is invalid.'; |
| <pre>\$output_form = 'yes';</pre> |
| } |
| |
| |
| |
| |
| |
| |
| |
| ······································ |



Rewrite the highlighted portion of the Risky Jobs PHP script for checking the Registration form data below to validate the text entered into the phone field using preg_match() instead of empty(). Use the regex you created earlier in the preg_match() function.

```
if (empty($phone)) {
    // $phone is blank
    echo 'Your phone number is invalid.';
    $output form = 'yes';
        Instead of empty(), we use a preg_match
        to validate the phone number. We precede it
       with the not operator (!), because we want to
        throw an error whenever the data entered
                                               Our phone number regular
       DOESN'T match the pattern
                                               expression from before.
if (!preq_match('/1\(?[2-9]\d{2}\)?[-\s]\d{3}-\d{4}j/', fphone))[
                                                            The echo needs to be changed a
// fphone is not valid
                                                bit, since we're not only checking
                                                           to make sure data is entered,
echo 'Your phone number is invalid ; but that it matches a standard
foutput form = 'yes';
                                                           phone number pattern.
           We set foutput form
                                                               ......
                                         I got an error and
             to 'yes', just as before.
                                         then entered my entire
                                         phone number. And
                                          then I got a ninja job!
                                                                0
```

First Name: Jimmy Last Name: Swift

Email: JS@sim-u-duck.com Phone: (555) 636 4652

Desired Job: Ninja







Not just empty phone numbers!

Check for valid phone numbers in the Risky Jobs Registration script.

Download the registration.php script from the Head First Labs site at www. headfirstlabs.com/books/hfphp, along with the Risky Jobs style sheet (style.css) and images (riskyjobs_title.gif and riskyjobs_fireman.png). Then modify the registration.php script so that it uses the preg_match() function to validate phone numbers against the phone number regular expression. Make sure to tweak the error message so that users know the phone number is invalid, not just empty.

Upload the changed script to your web server, and then open it in a web browser. Try entering a few phone numbers with varying formats, and notice how the script catches the errors.



you are here >

587

Hmm. If our regex matches multiple patterns for the phone number, isn't the text going to be in all different formats in our database? That's not good. I think we need to standardize this stuff.



Just because you're permitting data to be input in all different formats doesn't necessarily mean you want your data stored in all those formats.

Luckily, there's another regex function that'll let us take the valid phone number data submitted by Risky Jobs's users and make all of it conform to just one consistent pattern, instead of four.

The preg_replace() function goes one step beyond the preg_match() function in performing pattern matching using regular expressions. In addition to determining whether a given pattern matches a given string of text, it allows you to supply a replacement pattern to substitute into the string in place of the matched text. It's a lot like the str_replace() function we've already used, except that it matches using a regular expression instead of a string.

When we find an The string we're doing unwanted characters want to turn it into this.

The string we're doing the find—and—replace to.

Here's an example of the preg replace () function in action:


\$new_year = preg_replace('/200[0-9]/', '2010', 'The year is 2009.');


The result of the preg_replace() function, our revised text string after the find—and—replace is complete, is stored in fnew_year.

This regex tells preg_replace to look for a match for 2000 through 2009.

When a match is found, it will be replaced with 2010.

Every time a year from 2000-2009 is found in our string, it will be replaced by 2010.







Standardize the phone number data

Right now, Risky Jobs is using the following regular expression to validate the phone numbers users submit via their registration form:

This will match phone numbers that fall into these four patterns:



This leaves us with four characters to find and replace. We want to find and **remove** open and closing parentheses, spaces, and dashes. And we want to find these characters no matter where in the string they are, so we don't need the starting carat (^) or ending dollar sign (\$). We know we're looking for any one of a set, so we can use a character class. The order of the search doesn't matter. Here's the regex we can use:




Standardizing your data gives you better SQL query results.

you are here > 591

Get rid of the unwanted characters

Now that we have our pattern that finds those unwanted characters, we can apply it to phone numbers to clean them up before storing them in the database. But how? This is where the preg_replace() function really pays off. The twist here is that we don't want to replace the unwanted characters, we just want them gone. So we simply pass an empty string into preg_replace() as the replacement value. Here's an example that finds unwanted phone number characters and replaces them with empty strings, effectively getting rid of them:



I don't know, it seems kinda like overkill to worry about having 10 digit strings in our database. Couldn't we just insist that users type that in in the first place?



Sure, but it would end up causing problems later since phone number queries won't work as expected.

Most users are accustomed to entering phone numbers with some combination of dashes (hyphens), parentheses, and spaces, so attempting to enforce pure numeric phone numbers may not work as expected. It's much better to try and meet users halfway, giving them reasonably flexible input options, while at the same time making sure the data you store is as consistent as possible.

Besides, we're only talking about one call to preg_replace() to solve the problem, which just isn't a big deal. If we were talking about writing some kind of custom function with lots of code, it might be a different story. But improving the usability and data integrity with a single line of code is a no-brainer!




Clean up phone numbers in the Registration script.

Modify the registration.php script to clean up phone numbers by adding the following lines of code to the script, right after the line that thanks the user for registering with Risky Jobs:

```
$pattern = '/[\(\)\-\s]/';
$replacement = '';
$new_phone = preg_replace($pattern, $replacement, $phone);
echo 'Your phone number has been registered as ' . $new phone . '.';
```

Upload the script to your web server, and then open it in a web browser. Fill out the form, making sure to enter a phone number with extra characters, such as (707) 827-7000. Submit the form and check out the results.



Try out a few other variations on the number, like these: 707.827.7000, (707)-827-7000, 707 827-7000. Notice how the regular expression and preg_replace() get rid of the extra characters.



We know email addresses must contain these two characters.


LocalName@DomainPrefix.DomainSuffix

makes up an email address:

them in our PHP script. So let's first take a look at what exactly

These will contain alphanumerics, where LocalName is at least one character and DomainPrefix is at least two characters.

This is usually 3 alphanumeric characters.



you are here > 595

Matching email addresses can be tricky

It seems like it should be pretty simple to match email addresses, because at first glance, there don't appear to be as many restrictions on the characters you can use as there are with phone numbers.

For example, it doesn't seem like too big of a deal to match the LocalName portion of an email address (everything before the @ sign). Since that's just made up of alphanumeric characters, we should be able to use the following pattern:




This would allow any alphanumeric character in the local name, but unfortunately, it doesn't include characters that are also legal in email addresses.


Believe it or not, valid email addresses can contain any of these characters in the *LocalName* portion, although some of them can't be used to start an email address: All these characters
can appear in the
LocalName part of an
email address.

!\$&*-=^`|~#%'+/?_{]

If we want to allow users to register that have email addresses containing these characters, we really need a regex that looks something more like this:



This won't match every single valid *LocalName*, as we're still skipping some of the really obscure characters, but it's very practical to work with and should still match the email addresses of most of Risky Jobs users.



This email stuff is easy. We just use the same pattern we used for the local name to validate the domain name... no big deal!



That would work for part of the domain, the prefix, but it wouldn't account for the suffix.

While the domain prefix can contain pretty much any combination of alphanumerics and a few special characters, just like the *LocalName*, the restrictions on domain suffixes are much more stringent.

Most email addresses end in one of a few common domain suffixes: .com, .edu, .org, .gov, and so on. We'll need to make sure email addresses end in a valid domain suffix, too.

Dumb Questions

Q: What if I want to allow every possible valid email address?

A: You can, and if it makes sense for your web site you certainly should. But sometimes it's best to take commonly accepted formats and not necessarily accept every possible variation. You need to decide what 99.9% of your users will have as their emails and be willing to not validate the remaining .1% simply for the sake of more streamlined code. Validation is really a trade-off between what's allowed and what is practical to accept.

If you do want to implement more robust email validation on your site, you can find some great open source (i.e., free) PHP code here: http://code.google.com/p/php-email-address-validation/.

Q: Won't people get angry at me if they have an email address I refuse to validate?

A: Possibly, but most people will not have crazy email addresses.

Most online email services have their own restrictive rules that keep users from creating crazy, although valid, email addresses like:

"i'm crazy"@gregs-list.net.


Validation is often a trade-off between what's allowed and what is practical to accept.

you are here > 597

Domain suffixes are everywhere

In addition to super-common domain suffixes that you see quite frequently, like .com and .org, there are many, many other domain suffixes that are valid for use in email addresses. Other suffixes recognized as valid by the Domain Name System (DNS) that you may have seen before include .biz and .info. In addition, there's a list of suffixes that correspond to different countries, like .ca for Canada and .tj for Tajikistan.

Here is a list of just a few possible domain suffixes. This is not all of them.



Even I wouldn't want to juggle all of those domains.



Geek Bits

The *Domain Name System* is a distrubuted data service that provides a worldwide directory of domains and their IP addresses. It makes the use of domain names possible. Without DNS, we'd be typing 208.201.239.36 instead of oreilly.com.

Some of those domains are only two letters long. Some have 2 or 3 letters, and a period and then two or three letters. Some are even 4 and 5 letters long. So do we need to keep a list of them and see if there's a match?

We could do that, and it would work.

But there's an easier way. Instead of keeping track of all the possible domains and having to change our code if a new one is added, we can check the domain portion of the email address using the PHP function checkdnsrr(). This function connects to the Domain Name System, or DNS, and checks the validity of domains.

Use PHP to check the domain

PHP provides the checkdnsrr() function for checking whether a domain is valid. This method is even better than using regular expressions to match the pattern of an email address, because instead of just checking if a string of text could possibly be a valid email domain, it actually checks the DNS records and finds out if the domain is actually registered. So, for example, while a regular expression could tell you that lasdjlkdfsalkjaf.com is valid, checkdnsrr() can go one step further and tell you that, in fact, this domain is not registered, and that we should probably reject sdfhfdskl@lasdjlkdfsalkjaf.com if it's entered on our registration form.

The syntax for checkdnsrr() is quite simple:

Returns 1 if it's a real domain or O if it's not

checkdnsrr() expects a string containing a domain name. This is everything after the @ sign.

checkdnsrr('headfirstlabs.com')



If you're running PHP on a Windows <u>server</u>, this command won't work for you.

Instead, you can use this code:

```
function win_checkdnsrr($domain,$recType='') {
  if (!empty($domain)) {
    if ($recType=='') $recType="MX";
    exec("nslookup -type=$recType $domain",$output);
    foreach($output as $line) {
        if (preg_match("/^$domain/", $line)) (
            return true;
        }
        return false;
    }
    return false;
}
```

This is only an issue if your web server is Windows. If you're using a Windows computer to build your web site, but you're actually posting it to a UNIX/Linux server, then this is not a problem.

This exec commands calls an external program running on the server to check the domain.

Just for fun, try echoing fline just after the foreach. You'll see something like this:

Server: 68.87.64.146Address: 68.87.64.146#53Non-authoritative answer: oreilly.com mail exchanger = 20 smtpl. oreilly.com.

Email validation: putting it all together

We now know how to validate both the LocalName portion of an email address using regular expressions, and the domain portion of an email address using checkdnsrr(). Let's look at the step-by-step of how we can put these two parts together to add full-fledged email address validation to Risky Jobs's registration form:

Use preg match () to determine whether the LocalName portion of our email address contains a valid pattern of characters.

We can use the following regex to do so:

dollar sign at the end of this regex, as there will be characters /^[a-zA-Z0-9][a-zA-Z0-9\._\-&!?=#]*@/ following the @

> The email must start with an alphanumeric character, and then can contain any number of alphanumeries and certain special characters.

This time, we'll also search for an at symbol (@), to make sure our email address contains one before the domain.

Note that there's no

- If validation of the LocalName fails, echo an error to the user and reload the form.
- ø If validation of the *LocalName* succeeds, pass the domain portion of the text string users submitted to checkdnsrr().
- **4** If checkdnsrr() returns 0, then the domain is not registered, so we echo an error to the user and reload the form.
- 0 If checkdnsrr() returns 1, then the domain is registered, and we can be fairly confident that we've got a valid email address. We can proceed with validating the rest of the fields in the form.



Below is new PHP code to validate users' email addresses, but some pieces have disappeared. Fill in the blanks to get the code up and running.



Below is new PHP code to validate users' email addresses, but some pieces have disappeared. Fill in the blanks to get the code up and running.

```
Our regex for matching the LocalName portion of an email address, ending in an at symbol.
if (!preg_match('[a-zA-ZO-9][a-zA-ZO-9]. \-&!?=#]*@/ ', $email)) {
  // $email is invalid because LocalName is bad
  echo 'Your email address is invalid. <br />';
                                                           To strip out the Local Name and at
  $output form = 'yes';
                                                           symbol, specify the empty string (") as the replacement string.
else (
  // Strip out everything but the domain from the email
  $domain = preg_replace(' /^[a-zA-ZO-9][a-zA-ZO-9]. \-&!?=#]*@/ '," , femail );
  // Now check if $domain is registered
  if ( !checkdnsrr(fdomain) ) (
                                                                        Perform the replacement
                                                                        on the femail value
      echo 'Your email address is invalid. <br />';
                                         — If you're on a Windows server,
don't forget to include the
code for win_checkdnsrr(),
      Soutput form = 'yes';
         (checkdnsrr() returns true if
          the domain isn't registered.
                                             and then call it here.
```




BULLET POINTS

- preg_match() locates matches for patterns in strings.
- preg_replace() changes matching strings.
- Quantifiers allow you to control how many times a character or set of characters can appear in a row.
- You can specify a set of characters to allow in your pattern using a character class.
- In your pattern, \d, \w, and \s are standins for digits, alphanumeric characters, and whitespace, respectively.
- checkdnsrr() checks the validity of domain names.



Add email validation to the Risky Jobs Registration script.

Use the code on the facing page to add email validation to the registration.php script. Then upload the script to your web server, and open it in a web browser. Try submitting an invalid email address, and notice how the new regular expression code rejects the form submission, and displays an error message to explain what happeened.



Your PHP & MySQL Toolbox

Looking for patterns in text can be very handy when it comes to validating data entered by the user into web forms. Here are some of the PHP techniques used to validate data with the help of regular expressions:

Regular expression

Rules that are used to match patterns of text in strings. PHP includes functions that allow you to use regular expressions to check a string for a certain pattern, as well as find—and—replace patterns of text within a string.

preg_match()

This PHP function checks a string of text to see if it matches a regular expression. The function returns true if there was a match, or false if not.

preg_replace()

Use this PHP function to replace a substring within a string based on a regular expression. The function does a find—and—replace using a regular expression for the find, and replacing with a string you provide it.

\d, \w, \s, ^, \$, ...

Regular expressions are created using metacharacters, which represent text expressions such as three numeric digits (\d\d\d) or whitespace (\w).

Character class

A set of rules for matching a single character within a regular expression. For example, [A-D] matches the characters A, B, C, or D.

checkdnserr()

This PHP function checks a domain name to see if it actually exists. This is handy when validating an email address because you want to make sure that the domain part of the email is real.

604

11 Visualizing your data... and more!

Drawing dynamic graphics

Hold still. Wait, stop moving. Now look directly at me and smile. No, not you, your data. OK, let's try crossing your columns and tilting your primary key just a bit to the left. Ah, perfect!



Sure, we all know the power of a good query and a bunch of juicy results. But query results don't always speak for themselves. Sometimes it's helpful to cast data in a different light, a more visual light. PHP makes it possible to provide a graphical representation of database data: pie charts bar charts, Venn diagrams, Rorschach art, you name it. Anything to help users get a grip on the data flowing through your application is game. But not all worthwhile graphics in PHP applications originate in your database. For example, did you know it's possible to

thwart form-filling spam bots with dynamically generated images?


this is a new chapter

605

Guitar Wars Reloaded: Rise of the Machines

The future is now. Robots have already been let loose in the virtual world and there isn't much to stop them other than some PHP coding vigilance. The robots are **spam bots**, which troll the Web for input forms that allow them to inject advertisements. These robots are chillingly efficient and care nothing about the intended usage of the forms they attack. Their one and only goal is to overrun your content with theirs in a bloodthirsty conquest of ad revenue for their masters. Sadly, the Guitar Wars high score application has fallen prey to the bots.


All web forms are at risk of attack from spam bots.




606

No input form is safe

Fortunately for Guitar Wars, the spam bot attacks remain invisible to the end user thanks to the human moderation feature that was added back in Chapter 6. However, the human moderator is now being completely overwhelmed by the huge volume of spam bot posts, making it tough to sift through and approve legitimate high scores. Human moderation is a great feature, but humans are at a disadvantage when facing an automated adversary that never gets tired.



We need to separate man from machine



The Add Score form needs a new field that requires <u>human</u> verification before allowing a high score to be submitted.

The problem with the Add Score form is that it does nothing to prevent **automated** submissions, meaning that any reasonably crafty bot programmer can create a bot that repeatedly fills the form with ad data and submits it. Sure, it never makes it to the front page of the Guitar Wars site thanks to the moderation feature, but it in many ways renders moderation useless because the human moderator is left manually removing hundreds of bogus ad posts.

The form needs a new verification field that must be entered successfully in order for the score to submit. And the specific verification of this field needs to be something that is easy for a real **human** but difficult for a **machine**.

608



Following are some ideas for form fields that could potentially be used to prevent spam bots from submitting forms. Circle the form fields you think would **simply** and **successfully** allow only human form submissions, making sure to annotate why.

| only human form submissions, n | naking sure to annotate why. |
|--------------------------------|----------------------------------|
| Are you a robot? (| ◯ Yes ◯ No |
| What was Elvis' favorite food? | |
| Retinal scan: | Look into your web cam and click |
| Enter the letters displayed: | kdyqmc |
| What is the result of 7 + 5? | |
| What kind of animal is this? | |
| Enter the letters displayed: | kdyqme |
| Thumbprint scan: | Press your thumb down and click |

| Exercise human Solution Too easy to guess - even with just a 50% success rate through guessing, you'd end up with a ton of boous high score posts. | wing are some ideas for form fields submitting forms. Circle the form field in form submissions, making sure to Are you a robot? Yes | elds you think would simply and o annotate why. Definitely diff potentially diff as well. Not eve peanut butter a This would also | |
|---|--|---|--|
| Not bad, assuming the pass-phrase letters appear an image and not text, but potentially thwarted by bo smart enough to use optical character recognition (OCR | Retinal scan: Look | kdyqmc Simple and effective, | Excellent bot stopper but technically difficult and expensive to implement most bots |
| Remember Fang, the dog that was abducted by aliens earlier in the book? | at interpreting But it does re images and ans | | A nifty improvement on the other pass-phrase verifier where the letters are |
| Not quite as much trouble as retinal scanning but still | letters displayed: \(\text{\text{V}} \) Thumbprint scan: Press | kdyqme your thumb down and | obscured with lines and dots to confuse bots with OCR. |

We can defeat automation with automation

A test to verify that the entity on the other side of a form is a real person is known as *CAPTCHA*, which stands for Completely Automated Public Turing Test to Tell Computers and Humans Apart. That's a long-winded way of referring to any "test" on a form that is ideally passable only by a human. Lots of interesting CAPTCHAs have been devised, but one of the most enduring involves generating a random pass-phrase that the user must enter. To help prevent craftier bots with optical character recognition (OCR) from beating the system, the pass-phrase letters are distorted or partially obscured with random lines and dots.

A CAPTCHA is a program that protects a web site from automated bots by using a test of some sort.

Since the letters in the pass-phrase are randomly generated, the phrase is different every time the form is displayed.


Enter the letters displayed:

A normal text field is used to allow the user to enter the CAPTCHA pass-phrase.

Random lines and dots help to obscure the text just enough to thwart optical character recognition, while still allowing humans to discern it

dpmyta

A CAPTCHA form field is just like any other form field except that its whole purpose is to prevent a form from being submitted unless the CAPTCHA test has been successfully completed. So unlike other form fields, which typically pass along data to the server upon submission, a CAPTCHA field is verified and used to control the submission process.



It's very important for the CAPTCHA pass-phrase to be displayed on the form as an image and not just text; otherwise bots would have a much easier time figuring out the text.

Dumb Questions

Q: That image CAPTCHA with the dog is really cool. Could I use that instead of a pass-phrase CAPTCHA?

Absolutely. Just keep in mind that you'll need to maintain a database of images and descriptions of what they are, because one of the keys to any successful CAPTCHA is variety. A good CAPTCHA should have a deep enough repository of content that a form rarely displays the same test twice. That's the benefit of pass-phrase CAPTCHA: since the pass-phrase is generated from random letters, it's very unlikely the exact same test will appear twice to any given user, even with lots of repeated attempts.

Q: How does CAPTCHA impact the visually impaired? What if they can't pass a visual CAPTCHA test?

A: Visual CAPTCHAs aren't the best answer for users who are visually impaired. An ideal CAPTCHA solution might involve an audio alternative to visual CAPTCHAs. For example, there is an audio CAPTCHA where a series of numbers are read aloud, after which the user must enter them to pass the test. But the same problem exists, where crafty bots use voice recognition to defeat such CAPTCHAs, which is why some of them use highly distorted audio that sounds a little creepy. Audio CAPTCHAs are similar technically to image

CAPTCHAs in that they require a database of audio clips and their respective answers. There are services that offer flexible CAPTCHAs that utilize both image and audio CAPTCHAs, such as www.captcha.net. Such services are excellent in terms of offering the latest in CAPTCHA technology, but they typically don't integrate quite as seamlessly as a custom CAPTCHA that is tailored specifically to your web application.

But there are also people who have poor eyesight and are also hearing impaired. What about them?

A: Ultimately, CAPTCHA is all about weighing the reward of thwarting spam bots against the risk of alienating some users. Similar to viruses and anti-virus software, spam bots and CAPTCHAs will likely continue to play a cat and mouse game where bots are created to defeat a certain CAPTCHA, requiring a more sophisticated CAPTCHA, and on and on. Caught in the crossfire are users who may be left out due to the limited accessibility of some CAPTCHAs. It's up to the individual web developer to weigh the risks of a bot attack against the potential loss of users who may not be able to access parts of the site protected by CAPTCHA. If it's any consolation, keep in mind that the most sophisticated bots typically aim for large targets with huge ad revenue upside, meaning that you may not encounter a truly evil bot until your site grows to the point of being a big enough target for high-powered bots.

OK, so a CAPTCHA pass-phrase has to be displayed as an image with random lines and dots. That's fine, but how in the world can that be created with PHP? PHP can only generate HTML code, right?



With the help of a graphics library called GD (Graphics Draw), our PHP scripts can dynamically generate images in popular formats such as GIF, JPEG, and PNG, and either return them to a web browser for display or write them to a file on the server. This capability of PHP is extremely important because there is no notion of being able to "draw" on a web page purely through HTML. PHP allows you to "draw" on a portion of a page by performing graphics operations on an image, and then displaying that image on the page using the familiar tag.



Generate the CAPTCHA pass-phrase text

Before we can even think about the graphical side of a pass-phrase CAPTCHA, we need to figure out how to generate the random pass-phrase itself, which begins as a sequence of text characters. A pass-phrase can be any number of characters, but somewhere in the range of six to eight characters is usually sufficient. We can use a constant for the pass-phrase length, which allows us to easily change the number of pass-phrase characters later if need be,

define ('CAPTCHA_NUMCHARS', 6); A CAPTCHA pass-phrase six characters long is probably sufficient to stop bots without annoying humans.

So how exactly do we go about generating a random string of text that is six characters long? This is where two built-in PHP functions enter the story: rand () and chr (). The rand () function returns a random number in the range specified by its two arguments, while chr () converts a numeric ASCII character code into an an actual character. ASCII (American Standard Code for Information Interchange) is a standard character encoding that represents characters as numbers. We only need ASCII character codes in the range 97-122, which map to the lowercase letters a-z. If we generate a code in this range six times, we'll get a random six-character pass-phrase of lowercase letters.



\$pass phrase

// Generate the random pass-phrase \$pass phrase = ""; for (\$i = 0; \$i < CAPTCHA NUMCHARS; \$i++) { \$pass phrase .= chr(rand(97, 122)); The pass-phrase is constructed one random This code will eventually character at a time. go into its own reusable script file, captcha.php.

rand()

This built-in function returns a random integer number, either within a specified range or between 0 and the built-in constant RAND MAX (server dependent). To obtain a random number within a certain range, just pass the lower and upper limits of the range as two arguments to rand ().

chr()

This built-in function converts a number to its ASCII character equivalent. As an example, the number 97 is the ASCII code for the lowercase letter 'a'. So calling chr (97) returns the single character 'a'.

> The rand() function returns a random integer within a certain range.

Visualizing the CAPTCHA image

define ('CAPTCHA WIDTH', 100);

// Sprinkle in some random dots for (\$i = 0; \$i < 50; \$i++) (

// Draw the pass-phrase string

header ("Content-type: image/png");

imagesetpixel(\$img, rand() % CAPTCHA_WIDTH,
rand() % CAPTCHA HEIGHT, \$graphic color);

'Courier New Bold.ttf', \$pass phrase);

// Output the image as a PNG using a header

imagettftext(\$img, 18, 0, 5, CAPTCHA HEIGHT - 5, \$text color,

With the random pass-phrase nailed down, we can move on to generating an image consisting of the pass-phrase text along with random lines and dots to help obscure the text from bots. But where to start? The first thing to do is decide what size the CAPTCHA image should be. Knowing that this image will be displayed on a form next to an input field, it makes sense to keep it fairly small. Let's go with 100×25 , and let's put these values in constants so that the image size is set in one place, and therefore easy to change later if necessary.

Drawing a dynamic image in PHP requires using GD library functions.


```
to adjust the size later if desired.
   define ('CAPTCHA HEIGHT', 25);
Drawing the CAPTCHA image involves calling several functions in the GD
library, all of which operate on an image in memory. In other words, you create
an image in memory, then you draw on it, and then when you're all finished,
you output it to the browser so that it can be displayed.
   // Create the image
   $img = imagecreatetruecolor(CAPTCHA WIDTH, CAPTCHA HEIGHT);
                                                                                 This code creates colors
   // Set a white background with black text and gray graphics
                                                                                 to be used by the other
   $bc color = imagecolorallocate($img, 255, 255, 255);
                                                                                 GD functions.
   $text color = imagecolorallocate($img, 0, 0, 0);
                                                                   // black
                                                                   // dark gray
   $graphic color = imagecolorallocate($img, 64, 64, 64);
   // Fill the background
   imagefilledrectangle ($img, 0, 0, CAPTCHA WIDTH, CAPTCHA HEIGHT, $bg color);
   // Draw some random lines
   for ($i = 0; $i < 5; $i++) {
      imageline ($img, 0, rand() % CAPTCHA HEIGHT, CAPTCHA WIDTH,
        rand() % CAPTCHA HEIGHT, $graphic color);
```

The size of the CAPTCHA image is

stored in constants to make it easier

614 Chapter 11

imagepng (\$img);




you are here > 615

Inside the GD graphics functions

The magic behind CAPTCHA image creation is made possible by the GD graphics library, which you've already learned offers functions for dynamically drawing graphics to an image using PHP code. Let's examine some of these functions in more detail as they relate to generating a CAPTCHA image.

imagecreatetruecolor()

This function creates a blank image in memory ready to be drawn to with other GD functions. The two arguments to imagecreatetruecolor() are the width and height of the image. The image starts out solid black, so you'll typically want to fill it with a background color, such as white, before drawing anything. You can do this by calling the imagefilledrectangle() function. The return value of imagecreatetruecolor() is an **image identifier**, which is required as the first argument of most GD functions to identify the image being drawn.



New images are


The width of the new image, in pixels.

The height of the image.

\$img = imagecreatetruecolor(CAPTCHA WIDTH, CAPTCHA HEIGHT);

The function returns an image identifier that is required by other drawing functions to actually draw on the image.

This code creates an image that is 100x25 in size thanks to our constants.



imagecolorallocate()

Use this function to allocate a color for use in other drawing functions. The first argument is the image resource identifier, followed by three arguments representing the three numeric components of the RGB (Red-Green-Blue) color value. Each of these values is in the range 0–255. The return value is a color identifier that can be used to specify a color in other drawing functions, often as the last argument.

The return value is a color \$text color = imagecolorallocate(\$img, 0, 0, 0); identifier that you can use in other drawing functions to control the color being used, such as the color of CAPTCHA text

Blue: (0, 0, 255).


The identifier of the image the color will be used with

The red, green, and blue components of the color, in this case black.

616

imagesetpixel()

This function draws a single pixel at a specified coordinate within the image. Coordinates start at 0,0 in the upper left corner of the image, and increase to the right and down. Like most GD functions, the pixel is drawn using the color that is passed as the last argument to the function.



imagesetpixel(\$img, rand() % CAPTCHA_WIDTH, rand() % CAPTCHA_HEIGHT, \$graphic_color);

The image (identifier) the pixel is being drawn on.

The XY coordinate of the pixel, relative to the upper-left corner of the image, which in this case ends up being a random location within the CAPTCHA image.

The color (identifier) of the pixel.

imageline()


Call this function to draw a line between two coordinates (x1,y1 and x2,y2). The coordinates are specified relative to the upper-left corner of the image, and the line is drawn in the color passed as the last argument to the function.


The XY coordinate of the start of the line, in this case along the left edge of the CAPTCHA image.

The XY end point of the line, which here lies on the right edge of the CAPTCHA image.

imagerectangle()

Draw a rectangle starting at one point (x_1,y_1) and ending at another point (x_2,y_2) , in a certain specified color. The two points and the color are provided as the second through sixth arguments of the function, following the image identifier argument.





imagefilledrectangle()

Similar to imagerectangle(), this function draws a rectangle whose interior is filled with the specified color.

imagefilledrectangle(\$img, 0, 0, CAPTCHA_WIDTH, CAPTCHA_HEIGHT, \$bg_color);

The XY coordinates of the start and end points - here it fills the entire CAPTCHA image.


you are here >


617

The GD graphics functions continued...

imageellipse()


For drawing circles and ellipses, this function accepts a center point and a width and height. A perfect circle is just an ellipse with an equal width and height. The color of the ellipse/circle is passed as the last argument to the function.





imagefilledellipse()


Need a filled ellipse instead? Just call imagefilledellipse(), which works the same as imageellipse() except the specified color is used to fill the ellipse instead of outline it.



imagepng()

When you're all finished drawing to an image, you can output it directly to the client web browser or to a file on the server by calling this function. Either way, the end result is an image that can be used with the HTML tag for display on a web page. If you elect to generate a PNG image directly to memory (i.e., no filename), then you must also call the header () function to have it delivered to the browser via a header.

imagepng(\$img);



The image identifier, that you've been using in other draw functions.

The function returns true or false depending on whether the image was successfully created.

You can pass a filename as an optional second argument - without it, the function generates an image in memory that can be passed back to the browser in a header.

Cleaning up after your images is a good idea to keep the server from wasting resources after you're finished with them.



imagedestroy()

It takes system resources to work with images using the GD library, and this function takes care of cleaning up when you're finished working with an image. Just call it after you output the image with imagepng () to clean up.

Similar to imagepng(), this tunction returns true upon success, or false otherwise.

The identifier of the image you want to destroy.


Always free up images in memory with imagedestroy() once you've output them.

Always try to pair up a call to this function with each image that you create so that all images are destroyed.

imagedestroy (\$img);


imagestring()

This function draws a string of text using PHP's built-in font in the color specified. In addition to the image resource identifier, you pass the function the size of the font as a number (1-5), along with the coordinate of the upper left corner of the string, the string itself, and then the color.



The font size of the string, in the range 1 to 5.

> The XY coordinate corner of the string



Text drawn with imagestringup() is rotated 90 degrees counter-clockwise so that it appears vertically.

imagestringup()

Similar to imagestring (), this function draws a string of text using the built-in font, but it draws the text vertically, as if it were rotated 90 degrees counterclockwise. The function is called with the same arguments as imagestring().

Drawing text with a font

The imagestring() function is easy to use for drawing but it's fairly limited in terms of the control you have over the appearance of the text. To really get a specific look, you need to use a TrueType font of your own. The CAPTCHA pass-phrase image is a good example of this need, since the characters must be drawn fairly large and ideally in a bold font. To get such a custom look, you need the help of one last GD graphics function, which draws text using a TrueType font that you provide on the server.

imagettftext()


For drawing truly customized text, place a TrueType font file on your web server and then call this function. Not only do you get to use any font of your choosing, but you also get more flexibility in the size of the font and even the angle at which the text is drawn. Unlike imagestring(), the coordinate passed to this function specifies the "basepoint" of the first character in the text, which is roughly the lower-left corner of the first character.

This function does require you to place a TrueType font file on your server, and then specify this file as the last argument. TrueType font files typically have a file extension of .ttf.

tighly customized text drawing requires a TrueType font and the imagettftext() function.

x,y Sample text

Unlike imagestring(), the coordinate used to draw text with imagettftext() is at the lower-left corner of the text.




0


Geek Bits

If you'd like to take a stab at creating your very own TrueType font to further customize your CAPTCHA, check out www.fontstruct.com. It's an online font-building community including a web-based tool for creating custom fonts. Use the imagettftext() function to draw highly customized text with your own TrueType font.

620



you are here > 621



Generate a random CAPTCHA image

Putting all the CAPTCHA code together results in the brand-new captcha. php script, which takes care of generating a random pass-phrase and then returning a PNG image to the browser.

The captcha.php script is completely self-contained - you can open it in your browser and view the image that it generates.

```
<?php
session_start();
                                                                              Create constants to hold the
// Set some important CAPTCHA constants
                                                                              number of characters in the
 define ('CAPTCHA NUMCHARS', 6); // number of characters in pass-phrase
                                                                              CAPTCHA and the width and
 define('CAPTCHA_WIDTH', 100); // width of image
                                                                              height of the CAPTCHA image.
 define('CAPTCHA_HEIGHT', 25); // height of image
 // Generate the random pass-phrase
                                                               Although you could store the encrypted
 Spass phrase = "";
 for ($i = 0; $i < CAPTCHA_NUMCHARS; $i++) (
                                                               pass-phrase in the database, it's simpler
  $pass_phrase .= chr(rand(97, 122));
                                                               to just stick it in a session variable - we
                                                               have to store it so the Add Score script
 // Store the encrypted pass-phrase in a session variable
                                                               can access it
 $_SESSION['pass_phrase'] = shal($pass_phrase);
  // Create the image
  Simg = imagecreatetruecolor(CAPTCHA WIDTH, CAPTCHA HEIGHT);
  // Set a white background with black text and gray graphics
  $bg_color = imagecolorallocate($img, 255, 255, 255); // white
  $text color = imagecolorallocate($img, 0, 0, 0);
  $graphic_color = imagecolorallocate($img, 64, 64, 64); // darkgray
  imagefilledrectangle ($img, 0, 0, CAPTCHA WIDTH, CAPTCHA HEIGHT, $bg_color);
   // Draw some random lines
   imageline ($img, 0, rand() % CAPTCHA_HEIGHT, CAPTCHA_WIDTH, rand() % CAPTCHA_HEIGHT, $graphic_color);
   for ($i = 0; $i < 5; $i++) {
   // Sprinkle in some random dots
    imagesetpixel($img, rand() % CAPTCHA_WIDTH, rand() % CAPTCHA_HEIGHT, $graphic_color);
   for (\$i = 0; \$i < 50; \$i++) (
   inagettftext(Simg, 18, 0, 5, CAPTCHA_HEIGHT - 5, Stext_color, "Courier New Bold.ttf", Spass_phrase);
   // Draw the pass-phrase string
    // Output the image as a PNG using a header
                                                                             Some versions of the GD
   header("Content-type: image/png");
                                                                             graphics library require a relative
                                                           The PNG image is
    imagepng($img);
                                                           actually delivered
                                                                             path to the font file, such as
                        - Generate a PNG image based
                                                                             "/Courier New Bold.ttf".
                                                           to the browser
                            on everything that has been
    // Clean up
                                                           through a header.
    imagedestroy($img);
                            drawn
```

Finish up by destroying the image from memory (it still gets sent to the browser via the header).


captcha.php
you are here > 623




Create the CAPTCHA script and try it out.

Create a new text file named captcha.php, and enter the code for the CAPTCHA script from the previous page (or download the script from the Head First Labs site at www.headfirstlabs.com/books/hfphp).

Upload the script to your web server, and then open it in a web browser. You'll immediately see the CAPTCHA image with the random pass-phrase in the browser. To generate a new random pass-phrase, refresh the browser.



These robots are making me crazy! I need help stopping them now!



Returning sanity to Guitar Wars

Now that we've conjured up your inner PHP artist with some GD functions and a CAPTCHA image, it's time to use the CAPTCHA image to rescue the Guitar Wars moderator from the spam bot assault. There are actually a few steps involved in solving the bot problem with a pass-phrase CAPTCHA. The good news is we've already knocked out two of them: generating the random pass-phrase and drawing the CAPTCHA image. Let's knock out the remaining steps to make Guitar Wars officially bot-free!

Already done!

Generate a random pass-phrase.

Drawing complete!

- @ Draw a CAPTCHA image using the pass-phrase.
- Oisplay the CAPTCHA image on the Guitar Wars Add Score form and prompt the user to enter the pass-phrase.
- Werify the pass-phrase against the user input.

| Exercise | Complete Step 3 of the Guitar Wars Add Score CAPTCHA by writing the HTML code for a new Verification text input form field that prompts the user to enter the CAPTCHA pass-phrase. Make sure to give it a label, and follow it with an tag that displays the CAPTCHA image generated by the captcha.php script. |
|----------|--|
| | |
| | |
| | |

www.it-ebooks.info



Complete Step 3 of the Guitar Wars Add Score CAPTCHA by writing the HTML code for a new Verification text input form field that prompts the user to enter the CAPTCHA pass-phrase. Make sure to give it a label, and follow it with an tag that displays the CAPTCHA image generated by the captcha.php script.

A < label > tag is used This text field is where the user will enter the to label the new pass-phrase revealed in Verification text field. the CAPTCHA image. <label for="verify">Verification: </label> <input type="text" id="verify" name="verify" value="Enter the pass-phrase" /> The CAPTCHA image is displayed on the The "source" of the image is the form next to name of the PHP script that a verification dynamically generates the CAPTCHA text input field. image. This works because the captcha.php script returns an image directly to the browser via imagepra() and a header. Guitar Wars - Add Your High Score Screen shot: (Choose file) no file selected wgkeib

Finished! One more step to go

Display the CAPTCHA image on the Guitar Wars

Add Score form and prompt the user to enter the

pass-phrase.

Add CAPTCHA to the Add Score script

On the client side of the equation, the addscore.php script contains the new Verification text field with the CAPTCHA image beside it. The most important change, however, is the new if statement in the Add Score script (Step 4) that checks to make sure the user-entered pass-phrase matches the CAPTCHA pass-phrase.

```
session_start();
                                                                                              Check to
                                                                                              make sure
<html>
<title>Guitar Wars - Add Your High Score</title>
the user
                                                                                             -entered-
                                                                                              the correct
 <h2>Guitar Wars - Add Your High Score</h2>
<body>
                                                                                              CAPTCHA
                                                                                              pass-phrase.
<?php
  require_once('appvars.php');
 require once ('connectvars.php');
                                                                                                We're all done!
  if (isset($ POST['submit'])) {
   $dbc = mysqli_connect(DB_HOST, DB_USER, DB_PASSWORD, DB_NAME);
    // Grab the score data from the POST
    $name = mysqli_real_escape_string($dbc, trim($_POST['name']));
    $score = mysqli_real_escape_string($dbc, trim($_POST['score']));
   $screenshot = mysqli real_escape_string($dbc, trim($_FILES['screenshot']['name']));
$screenshot = mysqli real_escape_string($dbc, trim($_FILES['screenshot']['name']));
$screenshot type = $_FILES['screenshot']['type'];
$screenshot size = $_FILES['screenshot']['size'];
                                                                                        This is where the encrypted
                                                                                        pass-phrase is read from a session
                                                                                        variable and checked to see if the
      / Check the CAPTCHA pass-phrase for verification
                                                                                         user entered it correctly.
    Suser_pass_phrase = shal($ POST['verify']);
    if ($ SESSION['pass_phrase'] == Suser_pass_phrase) {
      echo 'Please enter the verification pass-phrase exactly as shown.';
     else (
    <form enctype="multipart/form-data" method="post" action="<?php echo $ SERVER['PHP_SELF']; ?>">
   ?>
     <input type="hidden" name="MAX_FILE_SIZE" value="<?php echo GW_MAXFILESIZE; ?>" />
     <input type="text" id="name" name="name" value="<?php if (!empty($name)) echo $name; ?>" /><br />
      <input type="text" id="score" name="score" value="<?php if (!empty($score)) echo $score; ?>" /><br />
      <label for="screenshot">Screen shot: </label>
      <input type="file" id="screenshot" name="screenshot" /><br/>


                                                                        -This is where the CAPTCHA script
      <imgsrc="captcha.php"alt="Verification pass-phrase"/>
                                                                         was "wired" to the Add Score script
                                                                         in Step 3, resulting in the CAPTCHA
      <input type="submit" value="Add" name="submit" />
                                                                          image being displayed on the page.
      </form>
     </body>
     </html>
                                                                                                                      addscore.php
```



Modify the Add Score script to support CAPTCHA.

Change the addscore.php script so that it has a new Verification form field, as well as using the captcha.php script to display a CAPTCHA image. Also add the code to check and make sure the user entered the correct pass-phrase before adding a score.

Upload both scripts to your web server, and then open addscore.php in a web browser. Try to add a new score without entering a CAPTCHA pass-phrase. Now try again after entering the pass-phrase displayed in the CAPTCHA image.



Dumb Questions

Q: Can I use the GD functions to create images in formats other than PNG?

A: Yes. The imagegif () and imagejpeg () functions work very similarly to imagepng () but create GIF and JPEG images, respectively.

Q: Can the image creation functions create images with transparency?


A: Yes! There is a function called imagecolortransparent () that sets a color as a transparent color within an image. This must be a color that you've already created using the imagecolorallocate () function. After setting the color as transparent, anything drawn with that color in the image will be considered transparent. To generate the image with transparency, just call imagegif () or imagepng (); you can't use imagejpeg () because JPEG images don't support transparency.

Q: When using imagepng() to output a PNG image directly to the client browser, where is the .png file for the image stored, and what is its name?

A: There is no .png file for the image, and the reason is because the image isn't stored in a file. Instead, the imagepng () function generates a binary PNG image in memory on the server and then delivers it directly to the browser via a header. Since the image data is created and sent directly to the browser, there's no need to store it in an image file.

Q: Is that why I'm able to put the name of the CAPTCHA script directly in the src attribute of an tag?

A: That's correct. Referencing a PHP script in the src attribute of an tag, as was done with the captcha.php script in Guitar Wars, results in the image being delivered directly by the script. This is in contrast to the normal way the tag works, where the name of an image file is specified in the src attribute. Since the script is sourcing the image directly to the browser through a header (by way of the imagepng () function), no file is involved. And the browser knows to connect the image from the header to the tag because the script is specified in the src attribute.





BULLET POINTS


- All web forms are at risk of attack from spam bots, but all spam bots are at risk from clever PHP programmers who use techniques such as CAPTCHA to thwart them.
- GD is a standard PHP graphics library that allows you to dynamically create images and then draw all kinds of different graphics and text on them.
- The createtruecolorimage () GD function is used to create a blank image for drawing.
- To output a PNG image to the browser or to a file on the server, call the imagepng () GD function.
- When you're finished working with an image, call imagedestroy() to clean up after it.

re > 629

Five degrees of opposability

Since Mismatch is a community of registered (human!) users, spam bots haven't been a problem. However, users want a little more out of the mismatch feature of the site, primarily the "five degrees of opposability" that they've been hearing about. Mismatch users want more than just a list of topics for their ideal mismatch—they want some visual context of how those topics break down for each major category of "mismatchiness,"


Mismatch's
"five degrees
of opposability"
involves measuring
mismatched topics
by category.




630

Charting mismatchiness


If you recall, Mismatch includes a categorized questionnaire where users select Love or Hate for a variety of topics. These responses are what determine the topics for an ideal mismatch. When presenting a user's ideal mismatch, the My Mismatch script displays a list of mismatched topics that it builds as an array from the Mismatch database. But users now want more than a list of topics... they want a visual categorized breakdown of their "mismatchiness," perhaps in the form of a bar graph?





Storing bar graph data

When it comes down to it, the data behind a bar graph is perhaps even more important than the graphics. Knowing that a bar graph is really just a collection of headings and values, we can view the data for a bar graph as a twodimensional array where the main array stores the bars, while each sub-array stores the heading/value pair for each bar.





Dumb Questions

Q: Does a bar graph have to be fed with a two-dimensional array of data?

A: No, not at all. But keep in mind that each bar in a bar graph typically involves two pieces of information: a heading and a value. And each bar graph consists of multiple bars, so a two-dimensional

array is a logical and efficient way to store data for use in populating a bar graph. As the old saying goes, "If you only see one solution, you really don't understand the problem." In this case, the problem is how to best store the data that is injected into a bar graph, and one particular solution that works out pretty well is a two-dimensional array. Of course, the challenge still remaining is how exactly to build this two-dimensional array of Mismatch category totals. The first step is to isolate what data in the database factors into the solution.







Bar Graph Exposed

This week's interview: Reading between the lines with the master of charts

Head First: So you're the guy people call when they need a visual representation of some data. Is that right?

Bar Graph: Oh yeah. I'm adept at all facets of data visualization, especially the rectangular variety.

Head First: So your drawing capabilities are limited mostly to rectangles?

Bar Graph: I'd say "limited" is a strong word in this case. It's one of those deals where simpler is better—people just seem to relate to the bars, maybe because they're used to seeing things measured that way. You know, like the little meter on mobile phones that tells you how good your signal is. "Can you hear me now?" I love that.

Head First: Right. But I've also seen some pretty effective graphs that are round. Makes me think comforting thoughts... like apple pie, know what I mean?

Bar Graph: I know where you're headed, and I'm fully aware of Pie Chart. Look, it's two different ways of thinking about the same thing. Pie Chart sees the world in curves; I see it a bit straighter, that's all.

Head First: But don't people inherently relate better to pie than a bunch of bars?

Bar Graph: No, they don't. At least people who aren't hungry don't. You see, Pie Chart is really good at revealing parts of a whole, where the data being represented adds up to something that matters, like 100%, 32 teams, or 50 states. There are 50 states, right?

Head First: Yes. Well, assuming you count Washington, D.C. as a "capital district" and places like Puerto Rico and Guam as "territories." But anyway, I see what you're saying about Pie Chart being more about revealing parts of a whole, but don't you do the same thing?

Bar Graph: Yes, but keep in mind that I'm much more flexible than Pie Chart. You can add as many bars to me as you want and I have no problem at all showing them.

The more you add to Pie Chart, the smaller the slices have to get. At some point the parts get hard to visualize because of the whole. All that matters with me is that the bars all have values that can show up on the same scale.

Head First: What does that mean?

Bar Graph: Well, it's difficult for me to graph things that have wildly different values, unless of course, you don't mind the bars being dramatically different. Where I really excel is at showing the difference between values that are within the same range. For example, maybe you want to use me to show the price of gasoline over a one-year period, in which case all the values would be within a reasonably constrained range, like within a few dollars of each other.

Head First: You sure about that?

Bar Graph: I know, the price of gasoline seems like a wildly varying value, but not really within the realm of what I deal with.

Head First: So you've seen some wild stuff, eh?

Bar Graph: You wouldn't believe some of it. I once had a guy who built a web application that kept up with how many miles he dragged his mouse in a given month. He blogged about it constantly, and used me to chart his "travels." Pretty crazy but people loved it.

Head First: So is that where you fit into the web picture—providing visual glimpses into people's data?

Bar Graph: Yeah, I guess so. Anytime I can drop into a page and provide some eye appeal to data that might otherwise be a little dull and hard to grasp, I consider it a good day.

Head First: Glad to hear it. Hey, I appreciate you sharing your thoughts, and I hope we can do this again.

Bar Graph: It was my pleasure. And don't worry, you'll be seeing me around.

From one array to another

When we last left off at Mismatch, we had a list of topics that corresponded to mismatches between two users. More specifically, we really have an array of topics. Problem is, the bar graph we're trying to draw isn't about topics per se—it's about the **categories** that are associated with the topics. So we're one level removed from the data we actually need. It appears that some additional SQL querying is in order. Not only do we need the array of mismatched topics, but we also need a similar, parallel array of mismatched categories.

An alias is used to eliminate confusion when referring to the name column of the mismatch category table.

A multiple join connects the category table to the response table so that the category name can be extracted

\$query = "SELECT mr.response id, mr.topic id, mr.response, mt.name AS topic name, mc.name AS category name " "FROM mismatch response AS mr " . "INNER JOIN mismatch topic AS mt USING (topic id) " . "INNER JOIN mismatch category AS mc USING (category id) " . "WHERE mr.user id = '" . \$ SESSION['user id'] . "'";

The new "column" of

mismatch result data

The additional join in this query causes the category name corresponding to each response topic to be tacked on to the result data, ultimately making its way into the \$user responses array. But remember, we need only the mismatched categories, not all of the categories. We need to build another array containing just the mismatched categories for the responses.

We still need a new array holding only the mismatched response categories for this pair of users


Appearance

Appearance

Appearance

Entertainment

Activities



\$user_responses

holds the category Entertainment name of every response. Entertainment Entertainment Food Food Food We need to extract Food only the category People People names of mismatched responses into an array. Activities Activities Activities Activities

But we're still falling short of our goal of building an array of mismatched categories. To do that, we need to revisit the code that builds the array of mismatched topics...

636



Try out the new query to grab mismatched topics and categories.

Using a MySQL tool, issue the following query to SELECT mismatched topics and categories for a specific user. Make sure to specify a user ID for a user who not only exists in the database, but who also has filled out the Mismatch questionnaire form:

```
SELECT mr.response_id, mr.topic_id, mr.response,
mt.name AS topic_name, mc.name AS category_name
FROM mismatch_response AS mr
INNER JOIN mismatch_topic AS mt USING (topic_id)
INNER JOIN mismatch_category AS mc USING (category_id)
WHERE mr.user_id = 3;
```

The user ID must be for a valid user who has answered the Mismatch questionnaire.

Notice that the results of this query match up with the fuser_responses array on the facing page, which is what we want

It's always a good idea to test out a query in a MySQL tool before sticking it in PHP code.

Build an array of mismatched topics

We now have a query that performs a multiple join to grab the **category** of each response in addition to the topic, which is then extracted into the \$user_responses array. Remember that another similar query also grabs data for each other user in the database so that mismatch comparisons can be made. So \$user_responses holds the response data for the user logged in to Mismatch, while \$mismatch_responses holds one of the other users in the system. This allows us to loop through all of the users and update \$mismatch_responses for each mismatch user comparison.

We're already using these two arrays to score mismatches and build an array of mismatched topics. We can now add a new line of code to also construct an array of mismatched categories—this array contains the category of each mismatched topic between two users.

```
This is the same code from the earlier version of

Mismatch, except now it builds an array of mismatched

categories in addition to the array of topics.

$categories = array();

for ($i = 0; $i < count($user_responses); $i++) (

if ($user_responses[$i]['response'] + $mismatch_responses[$i]['response'] == 3) (

$score += 1;

array_push($topics, $user_responses[$i]['topic_name']);

array_push($categories, $user_responses[$i]['category_name']);

When all is said and done, the

fcategories array contains one

category for each and every mismatch.

This code results in an array containing only the mismatched categories.

There are no

Dumb Questions
```

Q: I'm a little confused. What's the difference between a MySQL result set and a PHP array?

A: One big difference is access. A result set is only made available a row of cata at a time, while an array can hold multiple "rows" of data thanks to multiple dimensions. Extracting a result set into a two-dimensional array lets us move through rows of data efficiently without having to constantly go back to the database server to fetch and re-fetch rows. This doesn't work with huge sets of data, as you'd be creating huge arrays, but in the case of Mismatch responses, the arrays are never larger than the total number of topics in the system.

O: Don't we still need to count how many times a category was mismatched in order to generate the bar graph?

A: Yes. An array of mismatched categories is not enough.

Remember that the idea behind the Mismatch bar graph is that each bar represents a mismatched category, and the height of the bar represents how many times the category was mismatched. So we need to come up with a count of how many times each category was mismatched. But it's probably worth taking a step back to formulate a general plan of attack...

Formulating a bar graphing plan

With an array of mismatched categories and a bunch of big ideas about how to use it to generate a bar graph image for the My Mismatch page, we're still missing a plan. As it turns out, there are only three steps required to dynamically generate the bar graph, and we've already knocked out one of them.

Query the Mismatch database for mismatched category names.

This step provides us with the list of mismatched categories.

Calculate the mismatch totals for each category.


The list of categories needs to be converted into — a list of category totals.

Oraw the bar graph using the categorized mismatch totals.

To complete Step 2 of our plan, we somehow need to take the array of mismatched categories and turn it into a set of category totals, meaning a count of how many times each category appears in the mismatched

category array. If you recall, this is precisely the kind of data required to drive a bar graph, where the categories are the headings and the count for each category is the value of each bar. A two-dimensional array can be

With the category totals in hand, we can get down to the fun part of drawing the bar graph with GD functions.




Once this array of category totals is built, we'll be ready to move on to Step 3 and actually use some GD functions to crank out the bar graph visuals.

> 639 you are here >

Crunching categories

The challenge now is to get the array of categories totaled up and put into a two-dimensional array of headings and values. We have an array of mismatched categories stored in the \$categories array. We need to build a new array called \$category_totals that contains one entry for each category, along with the number of mismatches for each.





How would you go about totaling the mismatched categories in the \$categories array to build the two-dimensional \$category totals array?

Doing the category math

Moving from a one-dimensional array of mismatched categories to a twodimensional array of category totals is a bit trickier than you might think at first glance. For this reason, it's helpful to work through the solution in **pseudocode** before actually cranking out any PHP. Pseudocode frees you from syntactical details and allows you to focus on the core ideas involved in a particular coding solution.

Create a new two-dimensional array to store the category totals, making sure to initialize the first element with the first mismatched category and a count of 0.

Loop through the array of mismatched categories. For each category in the array...


Is the last element in the category totals array a different category than the current mismatched category?

- Yes! This is a new category so add it to the category totals array and initialize its count to 0.
- No. This is another instance of the current category, so increment the count of the last element in the category totals array.

The product of this code is a two-dimensional array of category totals where the main array holds a single category, while each sub-array contains the category name and its value.

| A . — | |
|--------------|--|
| Exercise | Translate the pseudocode to finish the real PHP code that builds a two-dimensional array of Mismatch category data called \$category_totals. |
| 7.75 | <pre>\$category_totals = array(array(\$mismatch_categories[0], 0));</pre> |
| | foreach (\$mismatch_categories as \$category) (|
| | |
| | |
| | |
| | |
| | ••••••••••••••••••••••••• |
| | |
| |) |

you are here > 641



Dumb Questions

Q: What happens to the category total code if the categories in the \$mismatch_categories array aren't in order?

A: Big problems. The code is entirely dependent upon the categories in the \$mismatch_categories array being in order. This is revealed in how the code assumes that any change in the category is the start of a new category, which works as long as categories are grouped together. Fortunately, the query in the Questionnaire script that originally selects topics for insertion into the mismatch_response table is smart enough to order the responses by category.

SELECT topic id FROM mismatch topic ORDER BY category id, topic id


This query is the one that first grabs topics from the database and then inserts them as empty responses for a given user. This ensures that user responses are stored in the database ordered by category, which allows the category total code to work properly.

Q: But isn't it risky writing code that is dependent upon the order of data stored in a database table?

A: Yes and no. Remember that this database is entirely controlled by script code that you write, so the order of the data really only changes if you write script code that changes it. Even so, an argument could certainly be made for ordering the join query in the My Mismatch script by category to make absolutely sure that the mismatched category list is in order.

Bar graphing basics

With a shiny new two-dimensional array of mismatched category data burning a hole in your pocket, it's time to get down to the business of drawing a bar graph. But rather than focus on the specifics of drawing the Mismatch bar graph, why not take a more generic approach? If you design and create an all-purpose bar graph function, it's possible to use it for Mismatch **and** have it at your disposal for any future bar graphing needs. In other words, it's **reusable**. This new function must perform a series of steps to successfully render a bar graph from a two-dimensional array of data.



644 Chapter 11



PHP Magnets


The My Mismatch script contains a new draw_bar_graph () function that takes care of drawing a bar graph given a width, height, a two-dimensional array of graph data, a maximum value for the range, and a filename for the resulting PNG image. Use the magnets to add the missing GD drawing function calls.

| | at the Costs Smay value, Sfilename) (| - 10 |
|---|--|------|
| unction draw_bar_graph(\$wid //Create the empty graph ima | dth, Sheight, Sdata, Smax_value, Sfilename) [age | -1 |
| Sing = | | -1 |
| | | -1 |
| // Set a white background wit | th black text and gray graphics | -1 |
| \$bg_color = | (\$img, 255, 255, 255); // white | -1 |
| Stext_color = | (\$img, 255, 255, 255); // white | - 1 |
| | (\$img, 0, 0, 0); //black | -1 |
| ************* | /e/ 102 102 1021+ // LIGHT GLAV | - 1 |
| 4001der_00100 | (\$1mg, 192, 192), 1721, 17 11900 9-12 | - 1 |
| // Fill the background | | - 1 |
| | (\$img, 0, 0, \$width, \$height, \$bg_color); | - 1 |
| // D-su the hars | | - 1 |
| <pre>\$bar width = \$width / ((cour for (Si = 0: Si < count (\$data)</pre> | (a); \$1++) 1 | -1 |
| | (\$img, (\$i * \$bar_width * 2) + \$bar_width, \$height, | - 1 |
| 102 + Char width * 2) + (S | Sbar_width * 2), Sheight - ((Sheight / Smax_value) * Sdata[Si][1]), Sbar_color |) ‡ |
| (\$1 - \$Dai_width 2) . (* | Simg, 5, (\$i * \$bar_width * 2) + (\$bar_width), \$height - 5, \$data[\$i][0], | - 1 |
| | ing, 5, 152 vbat_ | - 1 |
| \$text_color); | | - 1 |
| // Draw a rectangle around t | the whole thind | - 1 |
| // Draw a rectangle around | img, 0, 0, \$width - 1, \$height - 1, \$border_color); | |
| | | - 1 |
| <pre>// Draw the range up the lef for (\$i = 1; \$i <= \$max_valu</pre> | ue; \$1++) (| |
| (\$imc | g, 5, 0, \$height - (\$i * (\$height / \$max_value)), \$i, \$bar_color); | |
|) } | | |
| // Write the graph image to | o a file | |
| | ilename, 5); | |
| *************** | | |
| (\$img) |) 2 | |
| 1 | | |
| 1 | | |
| | imaged | lest |
| | Imageo | |
| | imagestringup imagerectangle | _ |
| imagecreatetruecolor | imagestringup imagerectangle imagecolorallocatimagecolorallocate imagepng imagestring imagefilledred | |



PHP Magnets Solution

The My Mismatch script contains a new draw_bar_graph () function that takes care of drawing a bar graph given a width, height, a two-dimensional array of graph data, a maximum value for the range, and a filename for the resulting PNG image. Use the magnets to add the missing GD drawing function calls.



The folder on the server where the file is to be written must be writeable in order for this function to work.

Dumb Questions

Q: Why does the draw_bar_graph () function write the bar graph image to a file instead of just returning it directly to the browser?

A: Because the function isn't contained within its own script that can return an image through a header to the browser. Remember, the only way to return a dynamically generated image directly to the browser is for a script to use a header, meaning that the entire purpose of the script has to be the generation of the image.

Q: So then why isn't the draw_bar_graph () function placed in its own script so that it can return the bar graph image directly to the browser using a header?

A: While it is a good idea to place the function in its own script for the purposes of making it more reusable, there is still a problem when it comes to returning an image via a header. The problem has to do with how you reuse code. When code is included in a script using include, include_once, require, or require once, the code is dropped into the script as if it had

originally existed there. This works great for code that doesn't do anything that manipulates the browser. But sending a header impacts the output of a script, which can be problematic for included code. It's not that you can't send a header from included code; you've actually done so in earlier examples. The problem is that you have to be extremely careful, and in some cases it isn't safe to assume that headers haven't already been sent. The My Mismatch script, for example, can't return an image to the browser because its job is to output HTML code containing mismatch results. Including script code that dynamically generates and returns an image would cause a header conflict.

OK, so can I just reference the bar graph code like the captcha. php script from Guitar Wars. That seemed to work fine without an include, right?

A: Yes, it did, and it referenced the captcha.php script directly from the src attribute of an tag. The problem here is that we have a lot of data that needs to be passed to the bar graph code, and this would be very cumbersome to try and pass via GET or POST.

Draw and display the bar graph image

The draw_bar_graph () function makes it possible to dynamically generate a bar graph image, provided you give it the proper information. In the case of the Mismatch bar graph, this involves sending along a suitable width and height that works on the My Mismatch page (480×240), the two-dimensional array of mismatched category data, 5 as the maximum range value (maximum number of mismatch topics per category), and a suitable upload path and filename for the resulting bar graph image. After calling the function, the image is generated and suitable for display using an HTML tag.

The image file generated by this function call is named mymismatchgraph.png, and is stored on the web server in the path identified by MM_UPLOADPATH.

you are here >


echo '<h4>Mismatched category breakdown:</h4>'; draw bar graph (480, 240, \$category totals, 5, MM UPLOADPATH . 'mymismatchgraph.png'); echo '
'; With the help of a reusable function, The same path and image it's possible to go from database data filename are specified in the sre attribute of the tag. to a bar graph stored in an image file. Appearance 3 Entertainment 4 Food 4 001010 People 2 101011 Activities mymismatchgraph.png



Create the My Mismatch script and try it out.

Create a new text file named mymismatch.php, and enter the code for the My Mismatch script (or download the script from the Head First Labs site at www.headfirstlabs.com/books/hfphp). Also add a new menu item for My Mismatch to the navmenu.php script.

Upload the scripts to your web server, and then open the main Mismatch page (index.php) in a web browser. Log in if you aren't already logged in, and the click "My Mismatch" on the main navigation menu. Congratulations, this is your ideal mismatch!



648 Chapter 11


So I'm curious, how are we able to store the My Mismatch bar graph image in a single file when a unique image is generated for every different user?

0

A bit of luck, as it turns out.

It's true, there is only one bar graph image at any given time, no matter how many users there are. This could present a problem if two users ever happen to view the My Mismatch page at the exact same moment. We run the risk of generating separate images for the two people and then trying to write them to a single image file.


This problem is probably fairly isolated in reality, but as Mismatch grows in popularity and expands to thousands and thousands of users, it could become significant. The fact that each one of the users thinks of the bar graph image as **their own** is a clue that there's a weakness in the single image bar graph design.



you are here > 649

Individual bar graph images for all

The solution to the shared bar graph image problem lies in generating multiple images, one for every user, in fact. But we still need to ensure that each of these images is tied to exactly one user and no more. That's where a familiar database design element comes into play... the primary key! The primary key for the mismatch_user table, user_id, uniquely identifies each user, and therefore provides an excellent way to uniquely name each bar graph image and also associate it with a user. All we have to do is prepend the users' IDs to the filename of their bar graph image.



650 Chapter 11

Dumb Questions

Q: Is there any advantage to outputting dynamically generated images as PNG images versus GIFs or JPEGs?


A: No, none beyond the reasons you would choose one image format over another for static images. For example, GIFs and PNGs are better for vector-type graphics, whereas JPEGs are better for photorealistic graphics. In the case of Mismatch, we're dealing with vector graphics, so either PNG or GIF would work fine. PNG happens to be a more modern image standard, which is why it was used, but GIF would've worked too. To output a GD image to a GIF and JPEG, respectively, call the imagegif() and imagejpeg() functions

O: How do I know what compression level to use when outputting PNG images to a file?

A: The compression level settings for the imagepng () function enter the picture when outputting a PNG image to a file, and they range from 0 (no compression) to 9 (maximum compression). There are no hard rules about how much compression to use when, so you may want to experiment with different settings. Mismatch uses 5 as the compression level for the bar graphs, which appears to be a decent tradeoff between quality and efficiency.

Are there file storage issues introduced by generating a bar graph image for each user?

A: No, not really. This question relates back to the compression level question to some degree, but it's unlikely that you'll overwhelm your server with too many or too huge files unless you really go crazy generating thousands of large image files. As an example, consider that the Mismatch bar graph images average about 2 KB each, so even if the site blows up and has 50,000 users, you're talking about a grand total of 100 MB in bar graph images. Granted, that's a decent little chunk of web hosting space, but a site with 50,000 users should be generating plenty of cash to offset that kind of storage.





Below is the Mismatch code that dynamically generates a bar graph image and then displays it on the page. Rewrite the code so that it generates a unique image for each user. Hint: use \$_SESSION['user_id'] to build a unique image filename for each user.

| echo ' <h4>Mismatched category breakdown:</h4> '; |
|--|
| draw_bar_graph(480,240,\$category_totals,5,MM_UPLOADPATH.'mymismatchgraph.png'); |
| echo ' '; |
| |
| |
| |
| |
| |
| |

you are here > 651

www.it-ebooks.info




Below is the Mismatch code that dynamically generates a bar graph image and then displays it on the page. Rewrite the code so that it generates a unique image for each user. Hint: use \$ SESSION['user id'] to build a unique image filename for each user.

echo '<h4>Mismatched category breakdown:</h4>'; draw bar graph (480, 240, \$category totals, 5, MM UPLOADPATH . 'mymismatchgraph.png'); echo '
'; Make sure this folder on the The standard file upload server is writeable so that the path is still used to ensure that the image image file can be written. The unique image filename follows is stored in the desired the form X-mymismatchgraph.png, place on the server. where X is the ID of the user. echo '<h4>Mismatched category breakdown:</h4>'; draw bar graph(480, 240, scategory totals, 5, MM_UPLOADPATH . f SESSION['user_id'] . '-mymismatchgraph.png'); echo '
';] The same image filename is used We can use the user ID when setting the src attribute that we already have stored of the tag for the bar away in a session variable. graph image in HTML code.



Change the My Mismatch script to generate unique bar graph images.

Modify the My Mismatch script so that it generates a unique bar graph image for each user. Upload the mymismatch.php script to your web server, and then open it in a web browser. The page won't look any different, but you can view source on it to see that the bar graph image now has a unique filename.



you are here > 653

Your PHP & MySQL Toolbox

Dynamic graphics open up all kinds of interesting possibilities in terms of building PHP scripts that generate custom images on the fly. Let's recap what makes it all possible.

CAPTCHA

A program that protects a web site from automated spam bots by using a test of some sort. For example, a CAPTCHA test might involve discerning letters within a distorted pass-phrase, identifying the content of an image, or analyzing an equation to perform a simple mathematical computation.

imageline(),
imagerectangle(), ...

The GD graphics library offers lots of functions for drawing graphics primitives, such as lines, rectangles, ellipses, and even individual pixels. Each function operates on an existing image that has already been created with imagecreatetruecolor().

GD library

A set of PHP functions that are used to draw graphics onto an image. The GD library allows you to dynamically create and draw on images, and then either return them directly to the browser or write them to image files on the server.

imagepng()

When you're finished drawing to an image using GD graphics functions, this function outputs the image so that it can be displayed. You can choose to output the image directly to the web browser or to an image file on the server.

imagecreatetruecolor()

This function is part of the GD graphics library, and is used to create a new image for drawing. The image is initially created in memory, and isn't output for display purposes until calling another function, such as imagepng ().

imagestring(),
imagestringup(),
imagettftext()

The GD graphics library also allows you to draw text, either with a built-in font or with a TrueType font of your own choosing.


imagedestroy()

After drawing to an image and outputting it as desired, it's a good idea to destroy the resources associated with it by calling this function.



PHP&MySQLcross

When you could actually use a robot, they're nowhere to be found. Oh well, your analog brain is up to the challenge of solving this little puzzle.



Across

- 1. This PHP graphics function draws a line.
- 6. The visual used to show how mismatched users compare on a categorized basis.
- To generate custom bar graph images for each user in Mismatch, this piece of information is used as part of the image filename.
- 8. Mismatch uses this kind of array to store bar graph data.
- 10. Give it two points and this graphics function will draw a rectangle
- 11. If you want to draw text in a certain font, call the image...text () function.
- Always clean up after working with an image in PHP by calling this function.
- 14. Call this graphics function to create a new image.


Down

- 2. The name of PHP's graphics library.
- Call this function to output an image as a PNG.
- 4. Owen's ideal mismatch.
- 5. Mismatch uses a bar graph to compare users based upon "five degrees of".
- A test used to distinguish between people and automated spam bots.
- 12. When PHP outputs an image, the image is either sent directly to the client browser or stored in a

e ▶ 655



PHP&MySQLcross Solution



12 syndication and web services



This is amazing. Instead of having to travel around asking people what's going on, we can get news delivered to us... brilliant!

Indeed. Technology brings the world to our ink-smudged fingertips!




It's a big world out there, and one that your web application can't afford to ignore. Perhaps more importantly, you'd rather the world not ignore your web application. One excellent way to tune the world in to your web application is to make its data available for syndication, which means users can subscribe to your site's content instead of having to visit your web site directly to find new info. Not only that, your application can interface to other applications through web services and take advantage of other people's data to provide a richer experience.

this is a new chapter

Owen needs to get the word out about Fang

One of the big problems facing any web site is keeping people coming back. It's one thing to snare a visitor, but quite another to get them to come back again. Even sites with the most engaging content can fall off a person's radar simply because it's hard to remember to go visit a web site regularly. Knowing this, Owen wants to offer an alternative means of viewing alien abduction reports—he wants to "push" the reports to people, as opposed to them having to visit his site on a regular basis.



658


Chapter 12

Push alien abduction data to the people

By pushing alien abduction content to users, Owen effectively creates a virtual team of people who can help him monitor abduction reports. With more people on the case, the odds of identifying more Fang sightings and hopefully homing in on Fang's location increase.

Some email clients support "push" content, allowing you to receive web site updates the same way you receive email messages.

Pushing web content to users is a great way to help gain more exposure for a web site.



Owen isn't exactly sure how to push content to users but he really likes the idea.



Owen's virtual team of alien abduction content viewers will hopefully increase the chances of him finding Fang.

you are here >

659

RSS pushes web content to the people


The idea behind posting HTML content to the Web is that it will be viewed by people who visit a web site. But what if we want users to receive our web content without having to ask for it? This is possible with RSS, a data format that allows users to find out about web content without actually having to visit a site.

RSS is kinda like the web equivalent of a digital video recorder (DVR). DVRs allow you to "subscribe" to certain television shows, automatically recording every episode as it airs. Why flip channels looking for your favorite show when you can just let the shows come to you by virtue of the DVR? While RSS doesn't actually record anything, it is similar to a DVR in that it brings web content to you instead of you having to go in search of it.

By creating an RSS feed for his alien abduction data, Owen wants to notify users when new reports are posted. This will help ensure that people stay interested, resulting in more people combing through the data. The cool thing is that the **same database** can drive both the web page and the RSS feed.

HTML is for viewing: RSS is for syndicating.

A newsreader allows you to subscribe to newsfeeds, which contain news items that are derived from web site content



RSS offers a view on web data that is delivered to users automatically as new content is made available. An RSS view on a particular set of data is called an **RSS feed**, or **newsfeed**. Users subscribe to the feed and receive new content as it is posted to the web site—no need to visit the site and keep tabs.

To view an RSS feed, all a person needs is an RSS **newsreader**. Most popular web browsers and email clients can subscribe to RSS feeds. You just provide the newsreader with the URL of the feed, and it does all the rest.

660

Chapter 12

RSS is really XML

RSS is like HTML in that it is a plain text markup language that uses tags and attributes to describe content. RSS is based on XML, which is a general markup language that can be used to describe any kind of data. XML's power comes from its flexibility—it doesn't define any specific tags or attributes; it just sets the rules for how tags and attributes are created and used. It's up to specific languages such as HTML and RSS to establish the details regarding what tags and attributes can be used, and how.

In order to be proficient with RSS, you must first understand the ground rules of XML. These rules apply to all XML-based languages, including RSS and the modern version of HTML known as XHTML. These rules are simple but important—your XML (RSS) code won't work if you violate them! Here goes:

RSS is a markup language used to describe web content for syndication.

Tags that contain content must appear as matching pairs.

Incorrect! There's no matching end-tag

Phone home!

Incorrect! The empty tag needs a space and a forward slash before the >.

Empty tags that have no content must be coded with a space and a forward slash at the end before the closing brace.

Incorrect! The attribute must

All attribute values must be enclosed in double quotes.

be enclosed in double quotes.

XML is a markup language used to describe any kind of data.

Unlike PHP, which allows you to use double or single quotes in most situations, XML is rigid in only allowing double quotes for attribute values

you are here >

Dumb Questions

Q: Why is RSS so much better than someone just coming to my web site?

A: If people regularly visited your web site to seek out the latest content, then RSS wouldn't be any better than simply displaying content on your web site. But most people forget about web sites, even ones they like. So RSS provides an effective means of taking your web content directly to people, as opposed to requiring them to seek it out.

Q: What does RSS stand for?

A: Nowadays RSS stands for Really Simple Syndication.

Throughout its storied history there have been several different versions, but the latest incarnation of RSS (version 2.0) stands for Really Simple Syndication, which is all you need to worry about.

Q: So what does RSS consist of?

A: RSS is a data format. So just as HTML is a data format that allows you to describe web content for viewing in a web browser, RSS is a data format that describes web content that is accessible as a news feed. Similar to HTML, the RSS data format is pure text, and consists of tags and attributes that are used to describe the content in a newsfeed.


Q: Where do I get an RSS reader?

A: Most web browsers have a built-in RSS reader. Some email clients even include RSS readers, in which case RSS news items appear as email messages in a special news feed folder. There are also stand-alone RSS readers available.



Below is RSS code for an Aliens Abducted Me news feed. Annotate the highlighted code to explain what you think each tag is doing.

```
<?xml version="1.0" encoding="utf-8"?>
<rss version="2.0">
  <channel>
    <title>Aliens Abducted Me - Newsfeed</title>
    <link>http://aliensabductedme.com/</link>
    <description>Alien abduction reports from around the world courtesy of Owen and his
     abducted dog Fang. </description>
    <language>en-us</language>
    <item>
      <title>Belita Chevy - Clumsy little buggers, had no rh...</title>
      <link>http://www.aliensabductedme.com/index.php?abduction id=7</link>
      <pubDate>Sat, 21 Jun 2008 00:00:00 EST</pubDate>
      <description>Tried to get me to play bad music.
    </item>
    <item>
      <title>Sally Jones - green with six tentacles...</title>
      <link>http://www.aliensabductedme.com/index.php?abduction id=8</link>
      <pubDate>Sun, 11 May 2008 00:00:00 EST</pubDate>
      <description>We just talked and played with a dog</description>
    </item>
  </channel>
</rss>
```



664 Chapter 12

OK, so RSS is really XML, which means it's just a bunch of tags. That seems easy enough. So all we have to do to create a newsfeed is just create an XML file, right?



Yes, sort of. But you don't typically create XML code by hand, and it often doesn't get stored in files.


It's true that XML can and often does get stored in files. But with RSS we're talking about dynamic data that is constantly changing, so it doesn't make sense to store it in files—it would quickly get outdated and we'd have to continually rewrite the file. Instead, we want XML code that is generated on-the-fly from a database, which is how the HTML version of the main Aliens Abducted Me page already works. So we want to use PHP to dynamically generate RSS (XML) code and return it directly to an RSS newsreader upon request.

From database to newsreader

In order to provide a newsfeed for alien abduction data, Owen needs to dynamically generate RSS code from his MySQL database. This RSS code forms a complete RSS **document** that is ready for consumption by RSS newsreaders. So PHP is used to format raw alien abduction data into the RSS format, which is then capable of being processed by newsreaders and made available to users. The really cool part of this process is that once the newsfeed is made available in RSS form, everything else is automatic—it's up to newsreaders to show updated news items as they appear.

An RSS newsreader is designed to consume the data made available by an RSS newsfeed.

aliens_abduction




666 Chapter 12



Creating RSS feeds is all about understanding the RSS language, which means getting to know the tags that are used to describe news items. Match each RSS tag to its description.

| <rss></rss> | This tag has nothing to do with RSS. But it sure sounds like a cool name for a piece of news data! |
|-----------------------|--|
| channel> | The publication date is an important piece of information for any news item, and this tag is used to specify it. |
| cronkite> | This tag represents a single channel in an RSS feed, and acts as a container for descriptive data and individual news items. |
| ctitle> | Represents an individual news item, or story, which is further described by child elements. |
| <language></language> | This tag always contains a URL that serves as the link for a channel or news item. |
| dînk> | Encloses an entire RSS feed—all other tags must appear inside of this tag. |
| description> | This tag stores the title of a channel or news item, and is typically used within the <channel> and <item> tags.</item></channel> |
| <pubdate></pubdate> | Used to provide a brief description of a channel or news item, appearing within either the <channel> and <item> tags.</item></channel> |
| <item></item> | This tag applies to a channel, and specifies the language used by the channel, such as en-us (U.S. English). |


you are here ▶ 667



668 Chapter 12

RSS Visualizing XML

You already learned that XML code consists of tags, which are also sometimes referred to as **elements**, that form **parent-child relationships** within the context of a complete XML document. It is very helpful to be able to visualize this parent-child relationship as you work with XML code. As an example, the RSS document on the facing page can be visualized as a hierarchy of elements, kind of like a family tree for newsfeed data, with parent elements at the top fanning out to child elements as you work your way down.



Below is a brand-new alien abduction report that has been added to the aliens_abduction database. Write the XML code for an RSS <item> tag for this abduction report, making sure to adhere to the RSS format for newsfeeds.

aliens_abduction

| abduction_id | first_name | last_name | when_it_happened | how_long | how_many | alien_description | what_they_did | |
|--------------|------------|------------|---------------------|---|--------------|---|---|-----|
| aparenon_ia | | | No. | 144 | | | | |
| 14 | Shill | Watner | 2008-07-05 | 2 hours | don't know | There was a bright light in the sky | They beamed me toward a gas station | *** |
| | | | | | | | | |
| ********** | | ********** | ******************* | ********** | ************ | ****************** | | |
| ********** | | | **************** | | | | | *** |
| ********** | ••••• | | | *************************************** | | | | *** |
| | | | | | | | | *** |



Below is a brand-new alien abduction report that has been added to the aliens_abduction database. Write the XML code for an RSS <item> tag for this abduction report, making sure to adhere to the RSS format for newsfeeds.

aliens_abduction

| abduction_id | first name | last_name | when_it_happened | how_long | how_many | alien_description | what_they_did | *** |
|-------------------------|------------|-------------|---|------------|---|---|--|-----------------------|
| | | | | in | | | | |
| 14 | Shill | Watner | 2008-07-05 | 2 hours | don't know | There was a bright light in the sky | They beamed me toward a gas station | 344 |
| k> | http://ww | w aliensabo | re was a bright l ductedme.com/inc 108 00:00:00 [| dex.php?a | bduction_i | itle> | The <pubdate be="" in="" mi<="" must="" td=""><td>e> tag</td></pubdate> | e> tag |
| <desc </desc | | ey beamed | me toward a ga | s station. | <td>tion></td> <td>with the capi can't be <pub <pubdate></pubdate></pub </td> <td>tal D, so date> or</td> | tion> | with the capi can't be <pub <pubdate></pubdate></pub | tal D, so date> or |

Dumb Questions

Q: Is XML case-sensitive?

A: Yes, the XML language is case-sensitive, so it matters whether text is uppercase or lowercase when specifying XML tags and attributes. A good example is the RSS <pubDate> tag, which must appear in mixed case with the capital D. Most XML tags are either all owercase or mixed-case.

Q: What about whitespace? How does it fit into XML?

A: First of all, whitespace in XML consists of carriage returns (\r), newlines (\r), tabs (\t), and spaces (' '). The majority of whitespace in most XML documents is purely for aesthetic formatting purposes, such as indenting child tags. This "insignificant" whitespace is typically ignored by applications that process XML data, such as RSS news readers. However, whitespace that appears inside of a tag is considered "significant," and is usually rendered exactly as it appears. This is what allows things like poems that have meaningful spacing to be accurately represented in XML.

Q: Can an RSS feed contain images?

A: Yes. Just keep in mind that not every news reader is able to display images. Also, in RSS 2.0 you can only add an image to a channel, not individual news items. You add an image to a channel using the <image> tag, which must appear inside the <channel> tag. Here's an example:

<image>

<url>http://www.aliensabductedme.com/fang.jpg</url>
<title>My dog Fang</title>

<link>http://www.aliensabductedme.com</link>
</image>

It is technically possible to include an image in a news item in RSS 2.0; the trick is to use the HTML < img> tag within the description of the item. While this is possible, it requires you to encode the HTML tag using XML entities, and in many ways, it goes against the premise of an RSS item being pure text content.

670 Chapter 12



Head First: So I hear that when people are looking for news on the Web, they turn to you. Is that true?

RSS: I suppose it depends on what you consider "news." I'm mainly about packaging up information into a format that is readily accessible to newsreaders. Now whether that content is really news or not... that's something I can't control. That's for people to decide.

Head First: Ah, so by "newsreaders," you mean individual people, right?

RSS: No, I mean software tools that understand what I am and how I represent data. For example, a lot of email programs support me, which means that you can subscribe to a newsfeed and receive updates almost like receiving email messages.

Head First: Interesting. So then how are you different than email?

RSS: Oh, I'm a lot different than email. For one thing, email messages are sent from one person to another, and are usually part of a two-way dialog. So you can respond to an email message, get a response back, etc. I only communicate one way, from a web site to an individual.

Head First: How does that make it a one-way communication?

RSS: Well, when a person elects to receive a newsfeed by subscribing to it in their newsreader software, they're basically saying they want to know about new content that is posted on a given web site. When new content actually gets posted, I make sure it gets represented in such a way that the news reader software knows about it and shows it to the person. But they aren't given an opportunity to reply to a news item, which is why it's a one-way communication from a web site to an individual.

Head First: I see. So what are you exactly?

RSS: I'm really just a data format, an agreed-upon way to store content so that it can be recognized and consumed by news readers. Use me to store data, and newsreaders will be able to access it as a newsfeed.

Head First: OK, so how are you different than HTML?

RSS: Well, we're both text data formats that are ultimately based on XML, which means we both use tags and attributes in describing data. But whereas HTML is designed specifically to be processed and rendered by web browsers, I'm designed to be processed and rendered by newsreaders. You could say that we provide different views on the same data.

Head First: But I've seen where some web browsers can display newsfeeds. How does that work?

RSS: Good question. As it turns out, some web browsers include built-in newsreaders, so they are really two tools in one. But when you view a newsfeed in a web browser, you're looking at something completely different than an HTML web page.

Head First: But most newsfeeds link to HTML web pages, correct?

RSS: That's right. So I work hand in hand with HTML to provide better access to web content. The idea is that you use me to learn about new content without having to go visit a web site directly. Then if you see something you want to find out more about, you click through to the actual page. That's why each news item has a link.

Head First: So you're sort of a preview for web pages.

RSS: Yeah, kinda like that. But remember that I come to you, you don't have to come to me. That's what people really like about me—I keep them from having to revisit web sites to keep tabs on new content.

Head First: I see. That is indeed convenient. Thanks for clarifying your role on the Web.


RSS: Hey, glad to do it. Stay classy.

you are here > 671

Dynamically generate an RSS feed

Understanding the RSS data format is all fine and good, but Owen still needs a newsfeed to take alien abduction reports to the people. It's time to break out PHP and dynamically generate a newsfeed full of alien abduction data that has been plucked from Owen's MySQL database. Fortunately, this can be accomplished by following a series of steps:

The resulting newsfeed isn't stored in a file but it is an XML <u>document</u>.



We have to set the content type of the RSS document to XML by using a header.


<?php header('Content-Type: text/xml'); ?>

Generate the XML directive to indicate that this is an XML document.


<?php echo '<?xml version="1.0" encoding="utf-8"?>'; ?>

Generate the static RSS code that doesn't come from the database, such as the <rss> tag and the channel information.

Query the aliens_abduction database for alien abduction data.



6 Loop through the data generating RSS code for each news item.



Generate the static RSS code required to finish up the document, including closing </channel> and </rs> tags.


</channel>
</rss>

672 Chapter 12



& XML! PHP & MySQL\Magnets

Owen's Aliens Abducted Me RSS newsfeed script (newsfeed.php) is missing some important code. Carefully choose the appropriate magnets to finish the code and dynamically generate the newsfeed.




Chapter 12



& XML! PHP & MySQL Magnets Solution

Owen's Aliens Abducted Me RSS newsfeed script (newsfeed.php) is missing some important code. Carefully choose the appropriate magnets to finish the code and dynamically generate the newsfeed.






Add the RSS Newsfeed script to Aliens Abducted Me.

Create a new text file named newsfeed.php, and enter the code for Owen's RSS Newsfeed script from the Magnets exercise a few pages back (or download the script from the Head First Labs site at www.headfirstlabs.com/books/hfphp).

Upload the script to your web server, and then open it in a newsreader. Most web browsers and some email clients allow you to view newsfeeds, so you can try those first if you don't have a stand-alone newsreader application. The Newsfeed script should display the latest alien abductions pulled straight from the Aliens Abducted Me database.



The newsfeed php

If your browser has trouble viewing the

newsfeed, try using

feed:// in the URL

instead of http://.

script generates an RSS newsfeed document that can be viewed by any RSS newsreader




about it?

Just provide a link to it from the home page.

Don't forget that newsfeed.php is nothing more than a PHP script. The only difference between it and most of the other PHP scripts you've seen throughout the book is that it generates an RSS document instead of an HTML document. But you still access it just as you would any other PHP script—just specify the name of the script in a URL. What Owen is missing is a way to share this URL with people who visit his site. This is accomplished with very little effort by **providing a syndication link**, which is just a link to the newsfeed. php script on Owen's server.

Link to the RSS feed

It's important to provide a prominent link to the newsfeed for a web site because a lot of users will appreciate that you offer such a service. To help aid users in quickly finding an RSS feed for a given site, there is a standard icon you can use to visually call out the feed. We can use this icon to build a newsfeed link at the bottom of Owen's home page (index.php).



A standard RSS

icon is available to

676



Add the newsfeed link to the Aliens Abducted Me home page.


Modify the index.php script for Aliens Abducted Me to display the newsfeed link near the bottom of the page. Also download the rssicon.png image as part of the code from this chapter from the Head First Labs site at www.headfirstlabs.com/books/hfphp.

Upload the index.php script and rssicon.php image to your web server, and then open the script in a web browser. Click the new link to view the RSS newsfeed.



Video million A pieture is worth a thousand words

After a newsfeed subscriber alerted Owen to a YouTube video with a dog in it that resembles Fang, Owen realized that he's going to have to use additional technology to expand his search for Fang. But how? If Owen could incorporate YouTube videos into Aliens Abducted Me, his users could all be on the lookout for Fang. Not only that, but he really needs to come up with a way to avoid constantly doing manual video searches on YouTube.






- Visit Owen's YouTube videos at www.youtube.com/user/aliensabductedme.
- Watch a few of the alien abduction videos that Owen has found.

 Do you think the dog in the videos is Fang?


Wouldn't it be dreamy if I could see videos directly on Aliens Abducted Me rather than having to search on YouTube? If only there was a way I could just go to a web page and have the search already done for me. But that's nothing but a dream...



Pulling web content from others

The idea behind an RSS newsfeed is that it **pushes your content** to others so that they don't have to constantly visit your web site for new content. This is a great way to make it more convenient for people to keep tabs on your site, as Owen has found out. But there's another side to the web syndication coin, and it involves **pulling content from another site** to place on your site. So you become the consumer, and someone else acts as the content provider. In Owen's case of showing YouTube videos on his site, YouTube becomes the provider.

YouTube is the provider of videos.



Syndicating YouTube videos

In order to source videos from YouTube, we must learn exactly how YouTube makes videos available for syndication. YouTube offers videos for syndication through a **request/response communication process** where you make a request for certain videos and then receive information about those videos in a response from YouTube's servers. You are responsible for both issuing a request in the format expected by YouTube and handling the response, which includes sifting through response data to get at the specific video data you need (video title, thumbnail image, link, etc.).


Following are the steps required to pull videos from YouTube and display them:

Syndicating videos from YouTube involves issuing requests and handling responses.

YouTube uses

XML to respond to video requests.

- Build a request for YouTube videos. This request is often in the form of a URL.
- Issue the video request to YouTube.
- B Receive YouTube's response data containing information about the videos.
- Process the response data and format it as HTML code.



Make a YouTube video request

Pulling videos from YouTube and incorporating them into your own web pages begins with a request. YouTube expects videos to be queried through the use of a **REST request**, which is a custom URL that leads to specific resources, such as YouTube video data. You construct a URL identifying the videos you want, and then YouTube returns information about them via an XML document.

The details of the URL for a YouTube request are determined by what videos you want to access. For example, you can request the favorite videos of a particular user. In Owen's case, the best approach is probably to perform a keyword search on all YouTube videos. The URL required for each of these types of video REST requests varies slightly, but the base of the URL always starts like this:

http://gdata.youtube.com/feeds/api/ <

This base URL is used for all YouTube REST requests.

there are no Dumb Questions

Q: What does REST stand for?

A: REpresentational State Transfer. This is definitely one of those acronyms that sounds way fancier and more technical than it really is. The main idea behind REST is that web resources should be accessible through unique links, which means you should be able to access "RESTful" data simply by constructing a URL for it. In terms of YouTube, it means that you can perform video queries purely through a URL that contains the search criteria.

X

Request videos by user

Requesting the favorite videos for a particular YouTube user involves adding onto the base URL, and also providing the user's name on YouTube.

The user name of a YouTube user provides access to that user's favorite videos.

http://gdata.youtube.com/feeds/api/users/username/favorites

To request the favorite videos for the user elmerpriestley, use the following URL:

http://gdata.youtube.com/feeds/api/users/elmerpriestley/favorites

The result of this REST request are the favorite videos for the YouTube user elmerpriestley.



Request videos with a keyword search

A more powerful and often more useful YouTube video request is to carry out a keyword search that is independent of users. You can use more than one keyword as long as you separate them by forward slashes at the end of the URL. Multiple keywords can be used in a video search by separating them with forward slashes.

http://gdata.youtube.com/feeds/api/videos/-/keyword1/keyword2/...

The URL starts the same as requesting by user but here you use "videos" instead of "users".

Don't forget the slashes and the hyphen

To request the favorite videos for the keywords "elvis" and "impersonator," use the following URL: Here the search keywords "elvis" and "impersonator" are used to search for videos

http://gdata.youtube.com/feeds/api/videos/-/elvis/impersonator

The keywords are case-insensitive, so "elvis", "Elvis", and "eLvls" all give you the same result.

BE the YouTube REST Request Your job is to get inside the mind of YouTube and become a video REST request. Use the magnets below to assemble video REST requests for the following YouTube videos, and then try them out in your web browser.

| All videos that | match the keyword "l | Roswell": | | | |
|-----------------|-------------------------|-----------------|----------|---|---|
| | match the keywords " | | | *************************************** | |
| All videos tagg | ed as favorites for the | user headfirsti | mork: | | ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, |
| | match the keywords " | | | | |
| All videos tagg | ed as favorites for the | | uctedme: | *************************************** | *************************************** |
| | http://gdata.youtube.c | com/feeds/api/ | You | may need to use | |
| alien headf | abduction / | Roswell | ufo more | of the magnets than once. | sighting |
| Area 51 | aliensa | bductedme | users | | favorites |

| BE the YouTube REST Request Solution Your job is to get inside the mind of YouTube and become a video REST request. Use the magnets below to assemble video REST requests for the following YouTube videos, and then try them out in your web browser. |
|--|
| The same base YouTube URL is used for all of the REST requests. The single keyword appears last in the URL. |
| All videos that match the keyword "Roswell": |
| http://gdata.youtube.com/feeds/api/ videos / - / Roswell |
| All videos that match the keywords "alien" and "abduction": http://gdata.youtube.com/feeds/api/ videos / - / alien / abduction Each of the search keywords appear at the end of the URL, and are separated by forward slashes. |
| All videos tagged as favorites for the user headfirstmork: http://gdata.youtube.com/feeds/api/ users / headfirstmork / favorites |
| The URL for a user's favorites requires the word "users" here instead of "videos". All videos that match the keywords "ufo", "sighting", and "dog": |
| http://gdata.youtube.com/feeds/api/ videos / - / ufo / sighting / dog |
| All videos tagged as favorites for the user aliensabductedme: http://gdata.youtube.com/feeds/api/ users / aliensabductedme / favorites This magnet wasn't used it's a conspiracy! This is the name of the user whose favorite |

Dumb Questions

Q: How is REST different than, say, a GET request?


A: It's not. Any time you've used a GET request, such as simply requesting a web page, you're using REST. You can think of a normal web page as a REST resource in that it can be accessed via a URL, and GET is the REST "action" used to access the resource. Where REST gets more interesting is when it is used to build queries, such as YouTube video requests. In this case you're still dealing with REST requests but they are querying a database for data instead of simply requesting a static web page.

Q: Does the order of arguments matter when performing a YouTube keyword search?

A: Yes. The first keywords are given a higher precedence than later keywords, so make sure to list them in order of decreasing importance.

Q: When there are multiple matches for a video search, how does YouTube determine what videos to return?

A: YouTube keyword video requests return videos based on search relevance, meaning that you will get the videos that best match the keywords, regardless of when the videos were posted to YouTube.





Owen is ready to build a REST request

Since Owen's goal is to scour YouTube for alien abduction videos that might have Fang in them, a keyword search makes the most sense as the type of REST request to submit to YouTube. There are lots of different keyword combinations that could be used to search for possible Fang videos, but one in particular will help home in on videos related specifically to Fang:




http://gdata.youtube.com/feeds/api/videos/-/alien/abduction/head/first

While you probably wouldn't reference the title of a book series when carrying out a normal YouTube video search, it just so happens to be a good idea in this particular case. Let's just say it's a coincidence that a lot of alien abduction videos have been made by Head First fans! With a REST request URL in hand, Owen can scratch off Step 1 of the YouTube video syndication process.

The last two keywords help to make sure you find the alien abduction videos related to Owen and Fangl





- Build a request for YouTube videos.
- Issue the video request to YouTube.
- Receive YouTube's response data containing information about the videos.
- Process the response data and format it as HTML code.

686




Try out Owen's YouTube request URL.

Enter Owen's YouTube request URL in a web browser:

http://gdata.youtube.com/feeds/api/videos/-/alien/abduction/head/first

What does the browser show? Try viewing the source of the page to take a look at the actual code returned by YouTube.



Requesting videos from YouTube by typing a URL into a web browser is neat and all, but what does that have to do with PHP? Why can't we access the video results from a script?



The SimpleXML extension to PHP, which offers the simplexml_load_file() function, was added to PHP in version 5. So prior versions of PHP don't have built-in support for XML processing.

We can, we just need a PHP function that allows us to submit a REST request and receive a response.

The built-in PHP function simplexml_load_file() lets us submit REST requests that result in XML responses, such as YouTube requests/responses. The function actually loads an XML document into a PHP object, which we can then use to drill down into the XML data and extract whatever specific information is needed. So how does that impact Owen's YouTube video request? Check out this code, which creates a constant to hold a YouTube URL, and then issues a REST request using the simplexml load file() function:

define('YOUTUBE_URL', 'http://gdata.youtube.com/feeds/api/videos/-/alien/abduction/head/first');

\$xml = simplexml load file(YOUTUBE URL);

Although not strictly necessary, it's / generally a good idea to store static URLs in constants so that you know where to change them if the need ever arises.

- Build a request for YouTube videos.
- 2 Issue the video request to YouTube.
- Receive YouTube's response data containing information about the videos.
- Process the response data and format it as HTML code.

These two steps are now done!

688 Chapter 12



Don't sweat it if you don't know what an object is, especially in the context of PHP.

A PHP object is a special data type that allows data to be packaged together with functions in a single construct. All you need to know for now is that it's much easier to process XML data in PHP by using objects. You'll learn more about how this is possible in just a bit.

```
clost volum='http://www.mi.org/2007/Anne/
efcet volum='http://www.mi.org/2007/Anne/
efcet volum='http://www.mi.org/2007/Anne/
eximal volum='http://ww
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   This is the XML file
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    returned by the
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    simplexml load file()
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    function, which
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    consists of YouTube
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               XML data for the
                    Controls

commonal oneshdartados/(game)
com/shttp://ghata.youtube.fom/famin/apt/common/alternagidochammen/uris
com/shttp://ghata.youtube.fom/famin/apt/common/alternagidochammen/uris
cfaminose
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                videos requested.
                  #/authous-
question="2.0" wis="http://gdata.postude.com/'sfouthde data AFT
densition variable="2.0" wis="http://gdata.postude.com/'sfouthde data AFT
densition="1.0" wis="http://gendearthitotallessaliza-
depsition="1.0" utasition="1.0" pendearthitotallessaliza-
depsition="1.0" wis="http://gendearthitotallessaliza-
depsition="1.0" wis="http://ge
         coptiDearcin finamPurPoges25/(permear)% itams% 1990*
contry*
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       Awesome... an even bigger problem!
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        What on earth do we do with all that
             A See minores later several All Force jets appeared and circles in the sky where the light best disappeared. c/consum:

Cles sel-salternate types 'seat/high' bret-"http://wer.pussine.com/seatch)**— subjects the disappeared.c/consum:

disk sel-"http://gdats.pussine.com/semman/2019/selbox.responses; types 'agplication/secend! http://gdats.pussine.com/semman/2019/selbox.responses; types 'application/attended. Here'starty//gdats.youthe.com/semman/2019/selbox.related types 'application/attended. Here'starty//gdats.youthe.com/semman/2019/selbox.related types 'application/attended. Here'starty//gdats.youthe.com/semman/2019/selbox.related types 'application/attended. Here'starty//gdats.youthe.com/semman/2019/selbox.related types'sapplication/attended.
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          messy XML data? There's no way a
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          PHP script can make sense of all that.
                                         comcognations/name>
cur/reds/spi/samrs/qualites/uni>
cur/reds/spi/samrs/qualites/uni>
                  configuration types plain's two flighting in Towards Park near Area 51/hosdistilled configuration to the border between California and Novale, and Cross to configuration types plain's west on a tip to Youngte Park is 2002. Youngte Park le very stone to the border between California and Novale, and Cross to configuration types plain's a west on a tip to Youngte Park is 2002. Youngte from a mention, on my way out of the park is was critical down a standard could not then I grapped my camers to take some pluture and the video is surrouncing in, and a long skiled retail bening to tipe in a few socials and then I grapped my camers to take some pluture as the video I such performs and any common all is a special is well amount. On the pluture of the pluture of light disappeared, and only the field remained. The trail after about 2 minutes the half of light disappeared, and only the field remained. The trail
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                0
                     The hall of light with the hope halo moved women the sky, leaving a trail. After about 2 minutes the hall of light disappeared, and only the final measured. The trail was illustrated and still hydrally visible were when the currenting sty was already pitch black.
```

Oh, but there is! The XML code returned by YouTube isn't really as messy as it looks... you just have to know where to look.

YouTube speaks XML


The video response from YouTube isn't exactly a DVD packaged up in a shiny box and delivered to your front door. No, it's an XML document containing detailed information about the videos you requested, not the videos themselves.

```
to video requests
<?xml version='1.0' encoding='UTF-8'?>
                                                                            with XML data that
<feed xmlns='http://www.w3.org/2005/Atom'
 xmlns:openSearch='http://a9.com/-/spec/opensearchrss/1.0/'
 xmlns:gml='http://www.opengis.net/gml'
                                                                             describes the videos.
 xmlns:georss='http://www.georss.org/georss'
 xmlns:media='http://search.yahoo.com/mrss/'
 xmlns:batch='http://schemas.google.com/gdata/batch'
                                                                                      Although there's a lot going
 xmlns:yt='http://gdata.youtube.com/schemas/2007'
 xmlns:gd='http://schemas.google.com/g/2005'>
                                                                                       on in this XML code, one
 <id>http://gdata.youtube.com/feeds/api/users/aliensabductedme/favorites</id>
                                                                                      thing to home in on is that
 <updated>2008-07-25T03:22:37.001Z</updated>
 <category scheme='http://schemas.google.com/g/2005#kind'</pre>
                                                                                      each individual video appears
  term='http://gdata.youtube.com/schemas/2007#video'/>
                                                                                      inside of an centrys tag.
 <title type='text'>Favorites of aliensabductedme</title>
  <id>http://gdata.youtube.com/feeds/api/videos/ 6Uibqf0vtA</id>
  <published>2006-06-20T07:49:05.000-07:00</published>
  <media:group>
  <media:title type='plain'>UFO Sighting in Yosemite Park near Area 51</media:title>
   <media:description type='plain'>I went on a trip to Yosemite Park in 2002. Yosemite Park is very
   close to the border between California and Nevada, and close to Area 51...</media:description>
   <media:keywords>51, alien, aliens, area, ca, california, nevada, sighting, sightings,
   ufo</media:keywords>
   <yt:duration seconds='50'/>
   <media:category label='Travel &amp; Events'</pre>
   scheme='http://gdata.youtube.com/schemas/2007/categories.cat'>Travel</media:category>
  <media:contenturl='http://www.youtube.com/v/_6Uibqf0vtA' type='application/x-shockwave-flash'
medium='video' isDefault='true' expression='full' duration='50' yt:format='5'/>
   <media:content url='rtsp://rtsp2.youtube.com/ChoLENy73wIaEQnQvvSnbiK1_xMYDSANFEgGDA==/0/0/0/video.3gp*</pre>
   type='video/3gpp' medium='video' expression='full' duration='50' yt:format='1'/>
  <media:contenturl='rtsp://rtsp2.youtube.com/ChoLENy73wIaEQnQvvSnbik1 xMYESARFEgGDA==/0/0/0/video.3gp'
type='video/3gpp' medium='video' expression='full' duration='50' yt:format='6'/>
   <media:player url='http://www.youtube.com/watch?v= 6Uibqf0vtA'/>
   <media:thumbnailurl='http://img.youtube.com/vi/_6Uibqf0vtA/2.jpg' height='97' width='130'</pre>
   time='00:00:25'/>
   <media:thumbnailurl='http://img.youtube.com/vi/ 6Uibqf0vtA/1.jpg'height='97'width='130'</pre>
   tine='00:00:12.500'/
   <media:thumbnailurl='http://img.youtube.com/vi/_6Uibqf0vtA/3.jpg'height='97'width='130'</pre>
   tine='00:00:37.500'/>
   <media:thumbnailurl='http://img.youtube.com/vi/ 6Uibqf0vtA/0.jpg'height='240'width='320'</pre>
   tine='00:00:25'/>
  </media:group>
  <yt:statistics viewCount='2478159' favoriteCount='1897'/>
  <gd:ratingmin='1'max='5'numRaters='1602'average='4.17'/>
  <gd:comments>
  <gd:feedLinkhref='http://gdata.youtube.com/feeds/api/videos/ 6Uibqf0vtA/comments'
   countHint='4426'/>
  </gd:comments>
 </entry>
 <entry>
  <id>http://gdata.youtube.com/feeds/api/videos/XpNd-Dg6_zQ</id>
  <published>2006-11-19T16:44:43.000-08:00</published>
 </entry>
                                   This centry> tag starts another video
</feed>
                                       within the XML response data.
```

YouTube responds


Chapter 12

690



Study the highlighted XML code for the YouTube response on the facing page and answer the following questions. You might just know more about YouTube's video XML format than you thought at first glance!

| 1. What is the title of the video? |
|--|
| 2. What are three keywords associated with the video? |
| 3. How long is the video, in seconds? |
| 4. To what YouTube video category does the video belong? |
| 5. How many times has the video been viewed? |
| 6. What average rating have users given the video? |
| |



syndication and web services

Hmm, I'm a little confused with those XML tags that have two names separated by a colon. Is that somehow a way to organize tags? And what about the weird & to code in the video category?



The unusual XML code uses namespaces and entities, which help organize tags and encode special characters.

When you see an XML tag that has two names separated by a colon, you're looking at a **namespace**, which is a way of organizing a set of tags into a logical group. The purpose of namespaces is to keep tags with the same name from clashing when multiple XML vocabularies are used in the same document. As an example, consider the following two XML tags:

<title type='text'>Favorites of aliensabductedme</title>

<media:title type='plain'>UFO Sighting in Yosemite Park near Area 51</media:title>

Namespaces are named groups of XML tags, while entities are used to encode special characters within XML documents.

It may seem odd that a Yahoo!
namespace appears in YouTube


XML code - it just means that
YouTube relies partly on an XML
data format created by Yahoo!

Without the media namespace in the second <title> tag, it would be impossible to tell the two tags apart if they appeared in the same XML code. So you can think of a namespace as a surname for tags—it helps keep an XML document full of "first names" from clashing by hanging a "last name" on related tags. The YouTube response code uses several different namespaces, which means it is using several different XML languages at once—namespaces allow us to clearly tell them apart.

To ensure uniqueness, an XML namespace is always associated with a URL. For example, the media namespace used in YouTube XML data is established within the <feed> tag like this:

This URL isn't actually a web page - it's just a unique identifier for a namespace.

The other strange thing in the YouTube XML code is & , which is XML's way of representing the ampersand character (&). This is an XML **entity**, a symbolic way of referencing a special character, such as &, <, or >, all of which have special meaning within XML code. Following are the five predefined XML entities that you will likely encounter as you delve deeper into XML code:



Deconstruct a YouTube XML response

Once you get to know the structure of a YouTube response, extracting the video data you need is pretty straightforward. In addition to understanding what tags and attributes store what data, it's also important to understand how the tags relate to one another. If you recall from earlier in the chapter when analyzing an RSS feed, an XML document can be viewed as a hierarchy of elements. The same is true for the XML data returned in a YouTube video response.


```
The <title> tag contains
                                                                        the title of the video.
<entry>
  <id>http://gdata.youtube.com/feeds/api/videos/ 6Uibqf0vtA</id>
                                                                                        In this code, the tag is
  <published>2006-06-20T07:49:05.000-07:00</published>
                                                                                        named "title" and the
  <media:group>
                                                                                        namespace is "media"
   <media:title type='plain'>UFO Sighting in Yosemite Park near Area 51</media:title>
   <media:description type='plain'>I went on a trip to Yosemite Park in 2002. Yosemite Park is very
   close to the border between California and Nevada, and close to Area 51...</media:description> The keywords
   <media:keywords>51, alien, aliens, area, ca, california, nevada, sighting, sightings,
                                                                                                I for the video.
   ufo</media:keywords>
                                                                                                The length of the
   <yt:duration seconds='50'/>
   cmedia:category label='Travel & Events'
                                                                                                video, in seconds
   scheme='http://gdata.youtube.com/schemas/2007/categories.cat'>Travel</media:category>
   <media:content url='http://www.youtube.com/v/_6Uibqf0vtA' type='application/x-shockwave-flash'</pre>
   medium='video'isDefault='true'expression='full'duration='50'yt:format='5'/>
   <media:content url='rtsp://rtsp2.youtube.com/ChoLENy73wIaEQnQvvSnbiKl xMYDSANEEgGDA==/0/0/0/video.3gp</pre>
   type='video/3gpp' medium='video' expression='full' duration='50' yt:format='1'/2
   <media:content url='rtsp://rtsp2.youtube.com/ChoLENy73wIaEQnQvvSnbiKl_xMYESARFEgGDA</pre>
                                                                                                 0/0/video.3gp
   type='video/3gpp' medium='video' expression='full' duration='50' yt:format='6'/>
                                                                                                   The YouTube
   <media:player url='http://www.youtube.com/watch?v= 6Uibqf0vtA'/> 
   kmedia:thumbnailurl='http://img.youtube.com/vi/ 6Uibgf0vtA/2.jpg'height='97' width='130'
                                                                                                   category for
   time='00:00:25'/>
                                                                                                   the video.
   <media:thumbnailurl='http://img.youtube.com/vi/6Uibqf0vtA/1.</p>
                                                                     gpg' height='97' width='130'
   time='00:00:12.500'/>
                                                                                                     The link to
   <media:thumbnailurl='http://img.youtube.com/vi/ 6Uibqf0vtA/3.jpy'height='97'width='130'</p>
   time='00:00:37.500'/>
                                                                                                     the video on
   <media:thumbnailurl='http://img.youtube.com/vi/ 6Uibqf0vtA/0.jpg height='240' width='320'</p>
                                                                                                     YouTube.
   time='00:00:25'/>
  </media:group>
                                                                             A thumbnail image of
  <yt:statistics viewCount='2478159' favoriteCount='1897'/</pre>
                                                                             the video, for previewing.
  <gd:ratingmin='1'max='5'numRaters='1602'average='4.17'/>
   <gd:feedLink href='http://gdata.youtube.com/feeds/api\videos/ &Uibqf0vtA/comments'</pre>
   countHint='4426'/>
  </gd:comments>
                                                                        The number of times the
           The "gd" namespace stands for Google
                                                 The average user
                                                                        video has been viewed
           Data, and includes tags defined by
                                                 rating of the video.
           Google for representing various kinds
           of data - You Tube is part of Google.
```

One important clue toward understanding the video data buried in this XML code is the different namespaces being used. The media namespace accompanies most of the tags specifically related to video data, while the yt namespace is used solely with the <statistics> tag. Finally, comments are enclosed within the <comments> tag, which falls under the gd namespace. These namespaces will matter a great deal when you begin writing PHP code to find specific tags and their data.


Visualize the XML video data

Earlier in the chapter when working with RSS code, it was revealed that an XML document can be visualized as a hierarchy of elements (tags) that have a parent-child relationship. This relationship becomes increasingly important as you begin to process XML code and access data stored within it. In fact, it can be an invaluable skill to be able to look at an XML document and immediately visualize the relationship between the elements. Just remember that any element enclosed within another element is a child, and the enclosing element is its parent. Working through the XML code for the YouTube video on the facing page results in the following visualization.

An element is just an abstract way of thinking of an XML tag and the data it contains.



The significance of this hierarchy of elements is that you can navigate from any element to another by tracing its path from the top of the hierarchy. So, for example, if you wanted to obtain the title of the video, you could trace its path like this:



Q: Why do I even need to worry about namespaces?

A: Because XML code generated by others often involves namespaces, which affects how you access XML elements programmatically. As you're about to find out, the namespace associated with an element directly affects how you find the element when writing PHP code that processes XML data. So the namespace must be factored into code that is attempting to grab the data for a given element.


Q: How do I know if a tag is part of a namespace?

A: Although it's possible to have a default namespace that doesn't explicitly appear in the code for a tag, in most cases you'll see the namespace right there in the tag name, so the tag is coded as <media:title>instead of just <title>. The name to the left of the colon is always the namespace.

Access XML data with objects

There are lots of different ways to work with XML data with PHP, and one of the best involves objects. An **object** is a special PHP data type that combines data and functions into a single construct. But what does that have to do with XML? The entire hierarchy of elements in an XML document is contained within a single variable, an object. You can then use the object to drill down into the data and access individual elements. Objects also have **methods**, which are functions that are tied to an object, and let us further manipulate the object's data. For an object that contains XML data, methods let us access the collection of child elements for an element, as well as its attributes.

Objects are a special PHP data type that combine data and functions together.



You've already seen how to create this XML object for Owen's alien abduction YouTube keyword search:

Remember, this function requires PHP version 5 or later.

define('YOUTUBE_URL', 'http://gdata.youtube.com/feeds/api/videos/-/alien/abduction/head/first');

\$xml = simplexml load file(YOUTUBE URL);

This Constign (yeales a PHP)

This code results in a variable named \$xml that contains all of the XML YouTube video data packaged into a PHP object. To access the data you use object **properties**, which are individual pieces of data stored within an object. Each property corresponds to an XML element. Take a look at the following example, which accesses all of the entry elements in the document:


This function creates a PHP object of type SimpleXML Element containing all of the XML data in the YouTube video response.

This code accesses all the entry elements in the XML data using a property. Since there are multiple entry elements in the data, the \$entries variable stores an array of objects that you can use to access individual video entries. And since we're now dealing with an array, each video <entry> tag can be accessed by indexing the array. For example, the first <entry> tag in the document is the first item in the array, the second tag is the second item, etc.



From XML elements to PHP objects


When it comes to XML data and PHP objects, you're really dealing with a **collection** of objects. Remember that stuff about visualizing an XML document as a hierarchy of elements? Well, that same hierarchy is realized as a **collection of objects** in PHP. Take a look:



Drill into XML data with objects

Getting back to Owen, our goal is to pull out a few pieces of information for videos that are returned as part of the XML YouTube response. We know how to retrieve the XML data into a PHP object using the simplexml_load_file() function, but most of the interesting data is found down deeper in this data. How do we navigate through the collection of objects? The answer is the -> operator, which is used to reference a property or method of an object. In the case of an XML object, the -> operator accesses each child object. So this code displays the title of a video entry stored in a variable named \$entry:


This code relies heavily on the relationship between the title, group, and entry objects, which form a parent-child relationship from one to the next.



The -> operator references a child object from a parent object. So title is a child of group, which is a child of entry. Remember that the -> operator can be used to access both properties and methods. One method that comes in particularly handy is the attributes () method, which is able to pluck out the value of an XML attribute for a given element.

This code drills down to the duration element and then grabs all of its attributes and stores them in the Sattrs variable, which is an array of all the attributes. The value of the seconds attribute is then retrieved from the array.

A specific attribute value can be retrieved by using the name of the attribute as the array key.



698 Chapter 12

Not without a namespace!

There's a small problem with the code on the facing page that accesses XML data using objects, and it has to do with namespaces. If you recall, namespaces act as surnames for tags by organizing them into meaningful collections. So in a YouTube response, the <duration> tag is actually coded as <yt: duration>, and the title for a video is coded as <media:title>, not <title>. When an element is associated with a namespace, you can't just reference it by tag name in PHP code. Instead, you have to first isolate it by namespace by calling the children () method on the parent object.

Namespaces make it a bit trickier to access elements within XML data.

```
$media = $entry->children('http://search.yahoo.com/mrss/');
```

This code retrieves all the child objects of the video entry whose namespace is http://search.yahoo.com/mrss/. But that's the URL for a namespace, not the namespace itself. This URL is located in the <feed> tag at the start of the XML document. This is where you'll find all the namespaces being used.

The children() method returns an array containing all of the child elements that are within the specified namespace.

```
<feed xmlns='http://www.w3.org/2005/Atom'
xmlns:openSearch='http://a9.com/-/spec/opensearchrss/1.0/'
xmlns:gml='http://www.opengis.net/gml'
xmlns:georss='http://www.georss.org/georss'
xmlns:media='http://search.yahoo.com/mrss/'
xmlns:batch='http://schemas.google.com/gdata/batch'
xmlns:yt='http://gdata.youtube.com/schemas/2007'
xmlns:gd='http://schemas.google.com/g/2005'>
This namespace is for
tags starting in "<yt:".
```

This code reveals how each namespace is associated with a URL. More specifically, it shows how the media and yt namespaces are specified for use in the document. This is all you need to find tags related to these two namespaces.

Once you've isolated the child elements for a particular namespace by calling the children() method on the parent element, you can then resume accessing child objects with the -> operator. For example, this code obtains the video title from the <media:group> tag:

```
stitle = Smedia->group->title; The <title> tag is a child of the <media:group> tag.
```

Use the children() method to isolate all elements associated with a namespace.

| | | | 172 |
|------|-----|------|---------------|
| Shar | pen | Vour | pencil |
| | | 1 | -3003-0404040 |

Using the namespace information and PHP code above, finish the PHP code that gets the duration (in seconds) of a video clip.

```
$yt = $media->children('........;

$attrs = ......;
echo $attrs['......'];
```

Sharpen your pencil Solution

Using the namespace information and PHP code above, finish the PHP code that gets the duration (in seconds) of a video clip.

\$yt = \$media->children(' http://gdata.youtube.com/schemas/2007 ');
\$attrs = {yt->duration->attributes();
echo \$attrs[' seconds '];
6vab all of the attributes

the namespace as listed in the <feed> tag at the beginning of the document.

The name of the attribute is used as the key for accessing the attribute array.

Dumb Questions

Q: How is an object different than an array? Don't arrays also store collections of data?

A: Yes. Arrays and objects are actually a lot alike. But one huge difference is that objects can have executable code attached to them in the form of methods. Methods are pretty much the same as functions except that they are tied to an object, and are usually designed to work specifically with the data stored in an object. Arrays are purely about storing a set of related data, and have no notion of methods. Additionally, array elements are accessed by specifying the index or key of an element inside square brackets ([]), while object properties and methods are accessed by name using the -> operator.

Q: What exactly is an object? Is it like a normal variable?

A: Yes. An object is exactly like any other variable in PHP; it's just that it is able to store more complex data. So instead of just storing a string of text or a number, an object is able to store a combination of strings numbers, etc. The idea is that by combining related data together with functions that act on them, the overall design and coding of applications becomes more logical.

Q: So how do objects help in processing XML data?

A: Objects help in regard to XML data processing because they are able to model the element hierarchy of an XML document in nested child objects. The benefit to this approach is that you can navigate through child objects using the -> operator and access whatever data you need.

Q: I thought the -> operator was for accessing object properties. How does it allow me to access a child object?

A: The reason is that when dealing with XML objects in PHP, child objects are actually stored as properties. So when you use the -> operator to access a child object, you really are just accessing a property. The SimpleXMLElement object is what makes this possible.

Q: Hang on, what's the SimpleXMLElement object?


A: Every object in PHP has a specific data type, meaning that "object" is really a generic term. So when you create an object, you're creating an object of a specific type that is designed to accomplish a specific task. In the case of XML, the object type is SimpleXMLElement, and it is automatically returned by the simplexml_load_file() function. In other words, calling the simplexml_load_file() function results in the creation of an object of type SimpleXMLElement.

Q: What do | need to know about SimpleXMLElement?

A: Surprisingly, not a whole lot. The main thing to know is that it exposes the elements in an XML document as properties, and that these properties lead to child objects that themselves are instances of the SimpleXMLElement object, and so on. The SimpleXMLElement object also has methods that allow you to access data within an element, such as children() and attributes().


Fang sightings are on the rise

While Owen has been busy brushing up on XML and figuring out how to communicate with YouTube, Fang has been busy. Numerous video sightings have turned up with the little guy apparently serving as a tour guide for his alien abductors. Owen is ready to finish up the YouTube script, get some videos showing on the Aliens Abducted Me home page, and find his lost dog.





The idea behind the youtube.php script is that it will be included in the main index.php script for Aliens Abducted Me. This means that the youtube.php script needs to take care of submitting a video request, processing the XML response, and formatting the individual videos so that they are displayed via HTML in such a way that they can coexist with the alien abduction reports that are already on the main page. A good way to accomplish this is to arrange the videos horizontally along the bottom of the page.



Five video thumbnails is a decent number to arrange horizontally without taking up too much room.

These are the videos

dynamically accessed from YouTube as XML data.

The youtube.php script will be included so that the videos appear just below the alien abduction reports.

Aliens Abducted Me Welcome, have you had an encounter with extraterrestrials? Were you abducted? Have you seen my abducted dog, Fang? Most recent reported abductions: 2008-08-10 : Meinhold Ressner Abducted for: Alien description: Fang spotted: 3 hours They were in a ship the size of a full moon 2008-07-11 : Mickey Mikens Abducted for: Atien description: Fang spotted: Huge heads, skinny arms and legs 2008-07-05 : Shill Watner Abducted for: Alien description: Fang spotted: There was a bright light in the sky, followed by a bark or two. 2008-06-21 ; Belita Chevy Abducted for: Alien description: Fang spotted: almost a week Clumsy little buggers, had no rhythm. 2008-05-11 : Sally Jones Abducted for: Alien description: Fang spotted: □ Click to syndicate the abduction news feed.

Arranging the videos horizontally on the main page keeps them from detracting too much from the alien abduction reports. Also, we're talking about arranging the video thumbnail images, not the videos themselves, so users will have to click a thumbnail to visit YouTube and see the actual video. It would eat up too much screen real estate to attempt to show multiple videos large enough to be embedded directly on the Aliens Abducted Me page.

This is a good spot to show the row of video thumbnails so that visitors can easily access them.

702

Format video data for display


Although a video thumbnail image is certainly one of the most important pieces of information when assessing whether or not a video is worth watching, it isn't the only data useful for Owen's YouTube script. For example, the title of a video could hold some important information about the nature of the video—like whether it might include a dog. The length of the video could also be helpful. And of course, we need the URL of the video link to YouTube so that the user can click on a video thumbnail to actually view a video. So the following information is what we need to extract from the XML data in the YouTube response:

n the YouTube response:

Title Length Thumbnail


Link Several pieces of video data are required in order to place YouTube videos on a web page.

This data forms the basis for the HTML code that displays a horizontal row of videos. In fact, each video in the row ends up looking like this:



In the YouTube response data, the length of a video is specified in the seconds attribute of the <yt:duration> tag. Unfortunately, most people don't think in terms of total seconds because we're accustomed to times being specified in minutes and seconds. For example, it isn't immediately obvious that 330 seconds is a five-and-a-half-minute video—you have to do the math for the value to make sense as a length of time. Knowing this, it's a good idea to go ahead and do the math for users when displaying the length of a video, converting seconds into minutes and seconds.

That is, unless you're part of the YouTube Director program, in which case you can post videos longer than 10 minutes.





The youtube.php script uses PHP code to grab the top five matches for an alien abduction YouTube video search. It then displays thumbnail images for those videos in a horizontal row, with links to the actual videos on YouTube. Fill the missing code for the script, using the example YouTube XML video response data on the facing page as a guide.

```
<?php
define('YOUTUBE_URL', 'http://gdata.youtube.com/feeds/api/videos/-/alien/abduction/head/first');
define('NUM_VIDEOS', 5);
// Read the XML data into an object
$xml = (YOUTUBE_URL);
$num_videos_found = count( );
if ($num_videos_found>0) {
 echo '';
 for ($i = 0; $i < min($num_videos_found, NUM_VIDEOS); $i++) (
  // Get the title
  $entry = $xml->entry[$i];
  $media = $entry->children('http://search.yahoo.com/mrss/');
  $title = Smedia->group-> ;
  // Get the duration in minutes and seconds, and then format it
  $yt = $media->children('http://gdata.youtube.com/schemas/2007');
  $attrs = $yt->duration->attributes();
  $length_min = floor($attrs[' '] / 60);
  $length_sec = $attrs[' '] % 60;
  $length_formatted = $length_min . (($length_min != 1) ? 'minutes, ': 'minute, ') .
   $length_sec . (($length_sec != 1) ? 'seconds':'second');
  // Get the video URL
  $attrs = $media->group->player-> ();
  $video_url = $attrs['url'];
```

```
$attrs = $media-> ->thumbnail[0]->attributes();
            $thumbnail url = $attrs['url'];
            // Display the results for this entry
            echo '<td style="vertical-align:bottom; text-align:center" width="' . (100 / NUM VIDEOS) .
             $length_formatted . '</span><br /><img src="' . . . . . '" /></a>';
           echo '';
                                                                                 Feel free to
          else (
                                                                                 reference this
                                                                                 example XML code
           echo 'Sorry, no videos were found.';
                                                                                 while writing the
          )
                                                                                 missing PHP code
         2>
<id>http://gdata.youtube.com/feeds/api/videos/_6Uibqf0vtA</id>
                                                                     - The title of the video.
<published>2006-06-20T07:49:05.000-07:00</published>
 <media:title type='plain'>OFO Sighting in Yosemite Park near Area 5D / media:title>
<media:group>
 <media:description type='plain'>1 went on a trip to Yosemite Park in 2002. Yosemite Park is very
 close to the border between California and Nevada, and close to Area 51...</media:description>
 <media:keywords>51, alien, aliens, area, ca, california, nevada, sighting, sightings,
                                                                                  The duration (length) of
 ufo</media:keywords>
<yt:duration seconds 50' 
<media:category label='Travel & amp; Events'
                                                                                  the video, in seconds.
 scheme='http://gdata.youtube.com/schemas/2007/categories.cat'>Travel</media:category>
 <media:content url='http://www.youtube.com/v/ 6Uibqf0vtA'type='application/x-shockwave-flash'
medium='video'isDefault='true'expression='full'duration='50'yt:format='5'/>
 <media:thumbnailurl='http://img.youtube.com/vi/_6Uibqf0vtA/1.jpg'height='97' width='130' the video link</pre>
 <media:thumbnailurl='http://img.youtube.com/vi/_6Uibqf0vtA/3.jpg'height='97'width='130' on YouTube.</pre>
 time='00:00:37.500'/>
<media:thumbnail url= http://img.youtube.com/vi/_6Uibqf0vtA/0.jpg'height='240' width='320'
  time='00:00:25'/>
 </media:group>
 <yt:statistics viewCount='2478159' favoriteCount='1897'/>
                                                                                         The URL of
 <gd:ratingmin='1' max='5' numRaters='1602' average='4.17'/>
                                                                                         a thumbnail
 <gd:feedLinkhref='http://gdata.youtube.com/feeds/api/videos/_6Uibqf0vtA/comments'countHint='4426'/>
                                                                                         image (preview) of the video.
 <gd:comments>
 </gd:comments>
</entry>
<entry>
</entry>
```

// Get the thumbnail image URL



The youtube.php script uses PHP code to grab the top five matches for an alien abduction YouTube video search. It then displays thumbnail images for those videos in a horizontal row, with links to the actual videos on YouTube. Fill in the missing code for the script, using the example YouTube XML video response data on the facing page as a guide.


```
Owen's YouTube
keyword search URL
<?php
define ('YOUTUBE URL', 'http://gdata.youtube.com/feeds/api/videos/-/alien/abduction/head/first');
define ('NUM VIDEOS', 5);
                                 The number of videos to be
                                 displayed is stored as a constant.
 // Read the XML data into an object
                                            The simplexml load file()
$xml = simplexml load file (YOUTUBE_URL);
                                                function is used to request
                                                  the XML data from YouTube.
$num_videos_found = count(fxml->entry );
                                                       Check to see how many videos
                                                     - were actually returned by
if ($num videos found>0) {
                                                       YouTube by counting the
 echo '';
                                                       number of centrys tags.
  for ($i = 0; $i < min($num_videos_found, NUM_VIDEOS); $i++) (
                                                                           Loop through the
                                                                           video data one
  // Get the title
                                                                           entry at a time.
  $entry = $xml->entry[$i];
                                                                     Grab all of the children for this
  $media = $entry->children('http://search.yahoo.com/mrss/');
                                         Extract the title of the
                                                                     entry that are in the Yahoo
  $title = $media->group-> title ;
                                         video entry, which is stored
                                                                     media namespace, media.
                                         in the <media title> tag.
  // Get the duration in minutes and seconds, and then format it
                                                                                Grab all of the children
                                                                               for this entry that are in
  $yt = $media->children('http://gdata.youtube.com/schemas/2007');
                                                                               the YouTube namespace, yt.
                                                   Get the duration of the
  $attrs = $yt->duration->attributes();
  slength min = floor (sattrs[' seconds '] / 60); video in seconds from the
                                                   <yt:duration> tag, and
then convert it to minutes.
  $length_sec = $attrs[' seconds'] % 60; 
  $length_formatted = $length_min . (($length_min != 1) ? 'minutes, ': 'minute, ') .
   $length sec . (($length_sec != 1) ? 'seconds':'second');
  // Get the video URL
  $attrs = $media->group->player-> attributes ();
                                                   Grab the video link (URL) from the url
  $video_url = $attrs['url'];
                                                   attribute of the <media:player> tag.
```

```
// Get the thumbnail image URL
                          $attrs = $media-> 9roup ->thumbnail[0]->attributes();
                          sthumbnail_url = sattrs['url']; Extract the first thumbnail image
                                                                                                                 URL from the url attribute of the
                                                                                                                 <media thumbnail> tag.
                          // Display the results for this entry
                          echo '<td style="vertical-align:bottom; text-align:center" width="' . (100 / NUM VIDEOS) .
                            '%"><a href="' . $video_url . '">' . ftitle . '<br /><span style="font-size:smaller">' .
                            $length_formatted.'</span><br/>
thumbnail_url.'"/></a>';
                                                                              Format the video results 3 Build a request for YouTube videos.
                        echo '';
                                                                              as a table cell with the
                                                                                                                                 Street Street
                                                                              video title, length, and
                                                                              thumbnail image.
                                                                                                                                Receive YouTube's response data
                      else (
                                                                                                                                             containing information about the videos.
                        echo 'Sorry, no videos were found.';
                                                                                                                                    Process the response data and format it
                                                                                                                                             as HTML code.
                    2>
                                                                                                                                                                                                      Finished!
<id>http://gdata.youtube.com/feeds/api/videos/_6Uibqf0vtA</id>
                                                                                                                                                    The title of the video
<published>2006-06-20T07:49:05.000-07:00</publIshed>
  <media:title type='plain'>UFO Sighting in Yosemite Park near Area 5Dx/media:title>
<media:group>
  <media:description type='plain'>1 went on a trip to Yosemite Park in 2002. Yosemite Park is very
    close to the border between California and Nevada, and close to Area 51...</media:description>
  <media:keywords>51, alien, aliens, area, ca, california, nevada, sighting, sightings,
                                                                                                                                                                               The duration (length) of
  ufo</media:keywords>
<yt:duration seconds 50.0
                                                                                                                                                                                the video, in seconds.
   <media:category label='Travel &amp; Events'</pre>
   scheme='http://gdata.youtube.com/schemas/2007/categories.cat'>Travel</media:category>
  <media:content url='http://www.youtube.com/v/ 6Uibqf0vtA'type='application/x-shockwave-flash'
medium='video' isDefault='true' expression='full' duration='50' yt:format='5'/>
  medium='video'isDerault='true'expression='full'duration='50'yt:format='5'/>
<media:content url='rtsp://rtsp2.youtube.com/ChoLENy73wIaEQnQvvSnbiKl_xMYDSANFEgGDA==/0/0/0/video.3gp'
type='video/3gpp'medium='video'expression='full'duration='50'yt:format='1'/>
<media:content url='rtsp://rtsp2.youtube.com/ChoLENy73wIaEQnQvvSnbiKl_xMYESARFEgGDA==/0/0/0/video.3gp'
type='video/3gpp'medium='video'expression='full'duration='50'yt:format='6'/>
<media:player url<'http://www_youtube.com/watch?v= 6Uibqf0vtA/2-/pg'height='97'width='130'
<media:thumbnail url='http://img.youtube.com/vi/_6Uibqf0vtA/2-/pg'height='97'width='130'</pre>
The URI_AI
time='00:00:25'/>
   <media:thumbnailurl='http://img.youtube.com/vi/_6Uibqf0vtA/1.jpg'height='97' width='130' the video link</pre>
    <media:thumbnailurl='http://img.youtube.com/vi/_6Uibqf0vtA/3.jpg'height='97'width='130' on YouTube.</pre>
   <media:thumbnail url={http://img.youtube.com/vi/_6Uibqf0vtA/0.jpg'}height='240' width='320'</pre>
      time='00:00:25'/>
  </media:group>
  <yt:statistics viewCount='2478159' favoriteCount='1897'/>
                                                                                                                                                                                              The URL of
  <gd:ratingmin='1' max='5' numRaters='1602' average='4.17'/>
                                                                                                                                                                                              a thumbnail
    <gd:feedLinkhref='http://gdata.youtube.com/feeds/api/videos/_6Uibqf0vtA/comments'
countHint='4426'/>
  <gd:comments>
                                                                                                                                                                                               image (preview) of the video.
  </gd:comments>
 </entry>
 <entry>
 </entry>
```




Add the YouTube script to Aliens Abducted Me.


Create a new text file named youtube.php, and enter the code for Owen's YouTube script from the previous two pages (or download the script from the Head First Labs site at www.headfirstlabs.com/books/hfphp). You still need to plug the script into the index.php script to turn YouTube videos loose on the main Aliens Abducted Me page. Here are the two lines of PHP code to do it:



708 Chapter 12



you are here ▶ 709



710 Chapter 12

Your PHP & MySQL Toolbox

With Fang now accounted for, it's possible to reflect a little on what all it took to track him down. As it turns out, PHP and MySQL required some help from a few other technologies.

XML

A generic markup language used to provide a predictable structure to data. There are many different markup languages built from XML, such as XHTML and RSS. The idea is that you create a set of tags specific to whatever data you're storing as XML.

simplexml_load_file()

This built-in PHP function loads an XML file from a URL, and then makes the resulting XML data accessible through an object.

SimpleXMLElement

A built-in PHP object that is used to access XML data. This object is returned by the simplexml_load_file() function, and contains the entire document hierarchy of an XML document.

REST

A means of accessing information on the web purely through URLs. REST allows you to make powerful data requests simply by creating a URL. Such requests are often referred to as "RESTful" requests.

RSS

An XML-based language used to store syndicated content, such as news stories. RSS allows web sites to make their data available to other applications and web sites for syndication, and allows you to take advantage of data made available by other sites.

Namespace

A way of organizing a set of XML tags into a logical group, sort of like how your last name organizes your family into a named group. A namespace is always associated with a URL, which ensures uniqueness among all other namespaces.



appendix i: leftovers



* The Top Ten Topics * (we didn't cover)



Even after all that, there's a bit more. There are just a few more things we think you need to know. We wouldn't feel right about ignoring them, even though they only need a brief mention. So before you put the book down, take a read through these short but important PHP and MySQL tidbits. Besides, once you're done here, all that's left are a couple short appendices... and the index... and maybe some ads... and then you're really done. We promise!

this is an appendix

#1. Retrofit this book for PHP4 and mysql functions

With the exception of XML functions in Chapter 12, most of the code in this book will run on PHP 4 servers with only a little modification. We've used the mysqli family of functions in this book, which are only available in PHP 4.1 and later, and since the library has to be manually installed, some servers won't support mysqli.

Mysqli functions are generally faster, but this really only begins to matter when your database becomes huge. Small or average databases won't be perceptibly slower with the older mysql functions. This section is designed to tell you how to retrofit your mysqli functions to work as mysql functions with older versions of PHP.

```
If you see:
    $dbc = mysqli_connect(localhost, 'mork', 'fromork');
    mysqli_select_db($dbc, 'alien_database');

you'll use:
    $dbc = mysql_connect(localhost, 'mork', 'fromork');
    mysql_select_db('alien_database', $dbc);
    The database connection variable is not the first argument here, as it is with mysqli_select_db().
```

In general, you just remove the i from mysqli, making it mysql, and then swap the order of the arguments so that the database connection variable (\$dbc in this example) appears last.

But it gets a little trickier when the mysqli_connect() function sidesteps mysqli_select_db() and uses a database name. There's nothing quite like that in the mysql family of functions. For the single mysqli_connect() function that uses a database name, you'll need two mysql functions.

If you see:

```
$dbc = mysqli_connect(localhost, 'mork', 'fromork', 'alien_database');

there the database is selected as part of making the connection - something that isn't possible in one step with mysql functions.

mysql_select_db('alien_database', $dbc);

This connection variable is also known as a database connection with a specific database.
```

714 Appendix i

Here's how mysql and mysqli functions match up.

| Close MySQL connection | mysqli_close(conn) | mysqli_close(conn) | |
|--|---|--|--|
| Open a connection to a MySQL server | mysql_connect(host, username, password) You must use mysql_select_db() to select a database. | mysqli_connect(host, username, password, database) You don't need mysqli_select_db() to select a database. | |
| Return the text of the error message from previous MySQL operation | mysql_error(conn) | mysqli_error(conn) | |
| Escape a string | mysql_escape_string(string, conn) The order of arguments is opposite, expects the string, then the connection (link). | mysqli_escape_string(conn, string) Expects the connection (link) followed by the string. | |
| Fetch a result row as an associative array, a numeric array, or both | mysql_fetch_row(result) | mysqli_fetch_row(result) | |
| Get number of rows in result | mysql_num_rows(result) | mysqli_num_rows(result) | |
| Execute a MySQL query | mysql_query(conn, query) | mysqli_query(conn, query) | |
| Escape special characters in a string | mysql_real_escape_string(string, conn) The order of arguments is opposite, expects the string, then the connection (link). | mysqli_real_escape_string(conn, string) Expects the connection (link) followed by the string. | |
| Select a MySQL database | mysql_select_db(dbname, conn) The order of arguments is opposite, expects the string, then the connection (link). | mysqli_select_db(conn, dbname) Expects the connection (link) followed by the string. | |

#2. User permissions in MySQL

Suppose you've created a web application that only allows visitors to SELECT data from your table. You perform queries on your data using a specific database, and MySQL gives you power over your data.

But consider this: the login and password you use in your mysqli connection string would, if connected directly to the database via the MySQL terminal or GUI, allow the user to INSERT, UPDATE, and DELETE data.

If your application doesn't need to do those things, there's no reason why the user/password you are using to connect with needs to be able to. With MySQL, you can limit the access to your database. You can tell MySQL to only allow the user to SELECT. Or SELECT and INSERT. Or any combination you need.

And what's even more impressive, you can control access to specific tables. For example, if your application only works with a table called alien info and doesn't need access to the cyborg info table, you can limit it.

First, you may want to create an entirely new user/password to be used for your application. You can do this in the MySQL terminal:

```
mysql> CREATE USER alienguy IDENTIFIED BY 'aliensRsc4ry';
Query OK, 0 rows affected (0.07 sec)
```

Then you can use the MySQL GRANT command to control what alienguy can do to your database. If he only needed to SELECT and INSERT data into your database, this would work:

```
mysql> USE alien_database;

Database changed

mysql> GRANT SELECT, INSERT ON alien_info TO alienguy;

Query OK, 0 rows affected (0.03 sec)
```


If you don't like using the MySQL terminal to create users and set privileges, you can download and install a handy program caled MySQLAdministrator. Get it here: http://dev.mysql.com/downloads/gui-tools/5.0.html.

You can set very specific user privileges, even control what your user can do to a specific column. To learn more, check out Head First SQL.

716 Appendix i

The MySQL Administrator lets you control your user accounts and what each user account can access in your database. It even allows you to specify which kind of queries that user can perform on each table in your database. To control the access every user has to each table and each query, open the MySQL Administrator application, and click on the **Accounts** tab.

Here's the interface and an overview of how to control what each user can do. First, create an account:



#3. Error reporting for MySQL

In many of our code examples, you'll see lines like this:

```
mysqli connect(localhost, 'mork', 'fromork') or die ('Could not connect.')
```

When this command fails, the words "Could not connect." are displayed on the web page. It tells us that something went wrong, but it doesn't give us information beyond that.

Fortunately, PHP offers a function, **mysql_error()**, that will give us a clue as to exactly what went wrong. Consider this code where we are trying to connect to a MySQL server that doesn't exist:

```
<?php
   mysqli_connect('badhostname', 'mork', 'fromork') or die (mysqli_error());
?>
Unknown MySQL server host 'badhostname' (1)
   message you'll see.
```

This will return clear information as to what actually went wrong when the mysqli_connect() function fails. You can also use mysqli_error() with other mysqli functions:

```
<?php
    $dbc = mysqli_connect('localhost', 'mork', 'fromork');
    mysqli_select_db($dbc, 'alien_database');
    echo mysqli_error($dbc) . '<br/>
    mysqli_select_db($dbc, 'alien_database');
    mysqli_query($dbc, "SELECT * FROM alien_info");
    echo mysqli_error($dbc);

}

Here's the output:

Unknown database 'alien_database'
    Table 'alien_info' doesn't exist

Description

We try to connect
to a database
that doesn't exist

doesn't exist

doesn't exist

Table 'alien_info' doesn't exist

Description

We try to
select_from
a table that
doesn't exist
```

Here are some other error messages you might see:

```
Table 'test.no_such_table' doesn't exist

Can't create table

Can't create database 'yourdatabase'; database exists

Can't drop database 'yourdatabase(; database doesn't exist
```

There are dozens more, and it would be a waste of paper to list them here. Browse on over to this site to get more information:

http://dev.mysql.com/doc/refman/5.0/en/error-messages-server.html

If you're retrofitting your mysql functions, as mentioned in #1, you can use mysql_error() instead of mysqli_error().

718 Appendix i

#4. Exception handling PHP errors

Exception handling allows you to change the normal flow of your code and execute a special block of code when a specific exception occurs. PHP 5 and 6 offer exception handling. Here's a brief introduction.

Let's say you want to withdraw \$200 bucks from an ATM.

But maybe you're required to have a minimum balance of \$1000, and this withdrawal will put you under \$1000. That isn't allowed.

Transaction failed!

Here's how this scenario might play out in PHP code with the help of exception handling to catch the failure.

Error: Balance less than \$1000.



```
<?php
                                                                   Here's the feedback we'll
  function checkBalance($balance) {
                                                                   send out if our balance is
                                                                   less than 1000.
    if ($balance < 1000) (
       throw new Exception ("Balance is less than $1000.");
    return true;
                    The "try" block is used
                    to test our value without
                    ending the code flow.
    checkBalance (999);
    echo 'Balance is above $1000.';
  catch (Exception $e) {
                                                               If our exception occurs, we
                                                              execute the code in this block.
    echo 'Error: ' . $e->getMessage();
                                                               In this case, we echo our message.
?>
When the code runs, you'll see this:
```

719

#4. Exception handling PHP errors (cont.)

Exception handling consists of three blocks of code:

1. Try - This block is where you check to see if your value is what you expect it to be.

If it is, everything is great, and your code continues on its way. If not, an exception has ocurred. In programmerese, an exception is "thrown,"

And when something is thrown, there needs to be something to catch it. If there is an exception, the "catch" block code is executed. If not, the code will continue as normal.

```
<?php
2. Throw - The "throw" commands
the "catch" block and sends it an error
                                      function checkBalance($balance) {
message. Each "throw" has at least
                                        if ($balance < 1000) {
one "catch."
                                        > throw new Exception ("Balance is less than $1000.");
                                        return true;
                                      try {
                                        checkBalance (999);
3. Catch - An object is created
                                        echo 'Balance is above $1000.';
with the exception information.
More information on objects, on
the facing page.
                                      catch(Exception $e) {
                                        echo 'Error: ' . $e->getMessage();
```

?>

#5. Object-oriented PHP

Object-oriented languages use a very different progamming model than their procedural counterparts. You've been using PHP procedurally, but it also has an object-oriented side. Instead of a chronological step-by-step set of instructions, particular structures become objects. Objects include not only a definition of your data, but also all the operations that can be performed on it. When you use object-oriented PHP, you create and work with objects.

Before we discuss why you might want to use OO PHP, let's write some:

Write your class.

```
class Song
                        These are instance
  var $title;
  var $1yrics;
                                                  This sets the title
                                                   and lyrics of a song
  function Song($title, $length) ( <
                                                   when we create one
    $this->title = $title;
    $this->lyrics = $lyrics;
                               This is a method that uses the
                            — instance variables of the object
  function sing() ( 	←
   echo 'This is called ' . $this->title . '.<br />';
   echo 'One, two, three ... ' . $this->lyrics;
```

This is our Song class that defines our object. Song title, lyrics sing()

Create a new object.

Our new song has the value "Blue Suede Shoes" for its name. \$shoes_song = new Song('Blue Suede Shoes', 'Well it\'s one for the money...'); \$shoes song->sing(); Here's where we call the sing() method for our object.

Your song can sing itself!

When you run this code, you get this:



But if you can just write the echo code without all the object stuff, why use OO PHP?

There are some great reasons...

you are here > 721

#5. Object-oriented PHP (cont.)

Instead of a chronological step-by-step set of instructions, your data structures become objects. **Objects include not only a definition of your data, but also all the operations that can be performed on it.** In our Song example, we set the title and lyrics of the song inside the class, and we create the sing() method inside the class. If we needed to add more functionality to our Song object, we'd add new methods and variables to our Song class. For example, if we wanted the songwriter for each song to be associated with each song object, we could add that as a variable in our class.

The power of OO really shines as an application grows. Suppose we decided to use the Song class as part of a karaoke application with hundreds or even thousands of individual song objects, all with their own unique titles, lyrics, and songwriters. Now let's say someone wants to choose from only songs that were written by Elvis. All we'd have to do is look at the songwriter instance variable of each object.

And to actually feed the lyrics to the karaoke application? We could just call the sing () method on each song object when it is being performed. Even though we're calling the exact same method on each object, it is accessing data unique to each of the objects.

So two big advantages of using Object Oriented PHP are:

Objects can be easily reused. They are designed to be independent of the code where they are used and can be reused as needed.


The code is easier to understand and maintain. If a data type needs to change, the change occurs only in the object, nowhere else in the code.

A big disadvantage is that, in general, OO code can be longer and take more time to write. If you simply need to display the lyrics from one song, then writing a small procedural program might be your best bet. But if you think you might want to build that online karaoke app, consider diving further into object-oriented PHP.

#6. Securing your PHP application

There are some simple steps you can follow to protect your PHP scripts from those nefarious hackers that are crouched over their keyboards waiting for you to slip up.

- Remove phpinfo() references. When you first start building PHP applications on new web servers, you'll probably create a script that contains the phpinfo() function, so you can see what version of PHP you are using and if it has MySQL support, along with a list of other installed libraries. It's fine to check with phpinfo(), but you should remove that function after you've taken a look. If you don't, any hacker out there who discovers a new PHP vulnerability will be able to see if your site is susceptible to it.
- If you aren't using a web hosting service and have access to the php.ini file, there are a few changes you can make to it to further secure your PHP applications. Ironically, the location of your php.ini file can be found by using phpinfo():



you are here > 723

#6. Securing your PHP application (cont.)

Here are some specific settings you should consider changing in the php.ini file. Open the file in a text editor, make the changes, save them, and then restart your web server.

```
safe mode = On
```

When you turn on safe_mode, no PHP scripts can be called by another script with a different owner on the same web server. Obviously, if you need to allow scripts from other owners to call yours, you can't use this setting.

```
open basedir = directory[:...]
```

This restricts the scripts and files that PHP will be able to execute or access to this directory and subdirectories beneath it.

```
expose php = Off
```

With this set to On, every web browser that visits your site will be sent header information that reveals information about you PHP server. Turning it off hides that information and makes your server a little less exposed.

```
display_errors = Off
```

Once you've developed your application and are running it on your live web server, you don't need to see all those error messages. Hopefully, you've already addressed errors, but sometimes things slip through the cracks. To hide the error messages from site visitors, set this to Off.

```
log errors = On
```

This sends your errors to an error log. When you want to check your application for errors, this is a good place to begin. With display_errors set to Off and log errors set to On, you'll be able to see problems, but your site's visitors won't.

```
error log = filename
```

You'll have to check with your particular web server software to locate this file. This is where your errors will be written when log_errors is set to On.

#7. Protect your app from cross-site scripting

You may have heard of cross-site scripting sometimes referred to as XSS. Cross-site scripting is an attack against a web app where script code is passed to your form processing script and hijacks your output. It's a big security problem in PHP web apps. Let's take a look at precisely what it is and how to defend against it.

Cross-site scripting usually takes advantage of sites that display user-submitted data. Any data you get from your users and display could potentially be corrupt and cause visitors to your site to be vulnerable to a hacker.

Using an XSS attack, a hacker can do any number of things. One of the worse is to redirect your results page to a page on a site under their control that might ask the user for further information. Your user might not notice that he's no longer on your site, and since he trusts your site, he might willingly submit sensitive information directly on the attackers server.

Here's how it might happen on the Guitar Wars site:

Ethel, instead of submitting her name in the Name field on the form, types in some JavaScript code. In the example, she's using the window.location function to redirect the browser to her own site. And since she controls her own site, she can show the visitor anything she wants, including a site that looks just like Guitar Wars. She could do something even more nefarious with sites that expect people to submit more important information than high scores, such as financial information.

There are other, even more insidious things that she could do, including stealing cookies or presenting the user with a screen that appeared to be a login screen. As soon as the user logs in, she has his username and password and can pretend to be him back on the original site.

So how do you avoid cross-site scripting attacks on your web applications?



you are here > 725

#7. Protect your app from cross-site scripting (cont.)

Fortunately, if you are validating your data, you are already on the road to protecting your application. You've already learned how to do just that in Guitar Wars. Here are three guidelines that will keep your applications safe:

Validate everything

Any data that you receive, such as form input, needs to be validated so that hacker code is detected before it can harm your application. If you assume the data is bad until you prove that it's not through validation, you'll be much safer.

Built-in PHP functions can help

Use built-in PHP functions such as strip_tags() to help you sanitize external data.
strip_tags() is a great function that removes any html tags from a string. So if you use strip_tags() on Ethel's \$ POST['name'], you'll end up with this:

window.location='http://ethelrulz.com'

While this is still not a name, it won't actually redirect the browser because the important JavaScript tags have been removed.

Pata is guilty until proven innocent

Start with the most restrictive validation you can, and then only ease up if you have to. For example, if you begin by accepting only numbers in a phone number field, then start allowing dashes or parentheses, you'll be much safer than if you allowed any alphanumeric characters in the first place. Or in the case of Guitar Wars, if we don't allow anything except letters in the name field, we'll never even get the less than sign (<) that opens Ethel's evil JavaScript code. Regular expressions (Chapter 10) can go a long way toward making sure only the exact data you want is allowed.

#8. Operator precedence

Consider this line of code.

The value stored by \$marbles could be either 1 or 4. We can't tell from the code, but we can assume certain rules of **precedence**. By precedence, we mean the **order** in which they are executed. Operators in PHP are carried out in a certain order. In the example above, the division will take place before the subtraction does, so \$marbles will equal 1.

Depending on what we need our code to output, we could have written it two different ways

```
smarbles = (4 / 2) - 1;
smarbles = 4 / (2 - 1);
```

In the first expression, we divide 4 by 2 and then subtract 1. In the second case, we subtract 1 from 2 and then divide 4 by the resulting 1. Using parentheses allow you to precisely control the order of operations. But knowing the precedence of operators in PHP can help you figure out what's going on in a complex expression. And, trust us, it will help you debug your code when you've forgotten to use parentheses.

Before we get to the PHP operator precedence list, here's another reason why you should use parentheses. Consider this:

```
$marbles = 4 - 3 - 2; \( \tag{| t will be -1.}
```

No precedence rules apply here. The result could be either 3 or -1. This is pretty confusing when you're writing code. Instead, it's better to code with parentheses, like in these two lines:

```
smarbles = 4 - (3 - 2);
smarbles = (4 - 3) - 2;
```

Now the list, from highest precedence (evaluated first) to lowest (evaluated last).

| Operator | Operator Type | |
|---|----------------------------------|--|
| ++ | increment/decrement | |
| */ % | arithmetic | |
| + | arithmetic and string comparison | |
| < <= > >= <> | | |
| ! ! | comparison | 7 |
| 8.8 | logical | Comparison |
| 11 | logical | operators, like those you use in IF |
| = += -= *= /= .= %= &= = ^= <<= >>= | assignment | statements, also have a precedence |
| and | logical | 1933 |
| xor | logical | |
| or | logical | |

#9. What's the difference between PHP 5 and PHP 6

As of the writing of this book, PHP 5 is the latest production version of PHP. But PHP 6 is being worked on and is available for developers here: http://snaps.php.net/.

The differences between PHP 4 and 5 are much greater than between 5 and 6. In many ways, 6 offers a refinement of the object-oriented features introduced in 5. Other changes include more support for XML and Unicode.

More Unicode support

Suppose your application needed to output text in Greek.



Consider the kinds of things you sometimes have to do with strings, such as needing to know the length of them or sorting them. It's straightforward in English, but when you are working with characters in other languages, string operations become more complicated.

Unicode is a set of characters and technologies to encode them. In Unicode, the Greek character that looks like a triangle has a specific numeric value assigned to it, along with other characters in other languages. Unicode is a standard, which means it receives wide support from major technology providers. In Unicode, every character has a unique number, no matter what language, program, or platform is used. Before the advent of PHP 5, PHP had no real support for Unicode. PHP 6 has enhanced support for Unicode strings in its functions and functions built specifically for creating and decoding Unicode.

728 Appendix i

#9. What's the difference between PHP 5 and PHP 6 (cont.)

00 refinements, XML support, and other changes

PHP 5 offers an object-oriented programming model but still allows for the mingling of procedural style. PHP 6 moves farther into the object-oriented realm. One of the biggest changes here is that dynamic functions will no longer be permitted to be called with static syntax. There are any number of small, but important, changes to the way PHP handles its OO code that make it more consistent with other OO languages such as C++ and Java.

None of the code in this book uses dynamic functions, so you don't have to worry about any of the code not working in PHP b.

A few other changes are:

- Both XML Reader and XML Writer will be extensions in PHP 6, making it easier to work with XML files.
- The register_globals, magic_quotes, and safe_mode options in the php.ini file will no longer be available.
- The ereg extension, which provided another way to build regular expressions, is removed. Fortunately, the same preg_match() code covered in this book will be the main way to build regular expressions in PHP 6.
- A 64-bit integer type will be added.
- Multi-dimensional arrays will be able to use foreach.
- Version 6 of PHP is, more than anything, a version that cleans up and refines the language,

#10. Reusing other people's PHP

It's not always necessary to write your own PHP code from scratch. Sometimes it's best to reuse someone else's. The following are several popular and highly successful PHP-based software packages that you should consider using if you have a need and would prefer not reinventing the PHP wheel. Oh, and they're all free!

Drupal

One of the most impressive PHP projects to date, Drupal is a powerful content management system that can be used to build just about any kind of content-driven web site. NASA, The Onion, the Electronic Frontier Foundation, and Popular Science all use Drupal for their web sites. It's flexible enough to build just about anything that is heavy on content. Check it out at http://drupal.org/.

phpBB

A category killer in the realm of online message boards (forums), phpBB is easy-does-it when it comes to building your own forum. It is extremely flexible and hard to beat at the one thing it does so well—managing threaded discussions. Find out more at http://www.phpbb.com/.

Coppermine Gallery

If image hosting is what you have in mind, Coppermine Gallery is the PHP application to check out. In an era of Flickr, Photobucket, Shutterfly, and Snapfish, hosting your own photo library sounds downright quaint. But with control comes power, and if you want complete control over your photos, take a look at Coppermine Gallery at http://coppermine-gallery.net/.

WordPress

One of the heavy hitters in the blogosphere, WordPress is PHP-based blogging software that lets you build and maintain a blog with minimal hassle. There's lots of competition out there, so you might want to do some exploring, but you could do worse than to pick WordPress if you're launching a blog. Download it at http://wordpress.org/.

Hold it right there! Why bother learning PHP if you're just going to reuse other people's code?

other really nice
P-based content
anagement system is

Another really nice
PHP-based content
management system is
Joomla!, which you can
learn about at
http://www.joomla.org/.



Because reusing code isn't always as simple as it sounds—sometimes it requires PHP skills.

Many PHP software packages still require customization, and that often requires some strong PHP development skills. Not only that, but you may elect to only reuse a small component of someone else's code, or not reuse it at all. Either way, by having PHP knowledge, you have options, and options are always a good thing!

730 Appendix i

appendix ii: set up a development environment





You need a place to practice your newfound PHP and MySQL skills without making your data vulnerable on

the web. It's always a good idea to have a safe place to develop your PHP application before unleashing it on the world (wide web). This appendix contains instructions for installing a web server, MySQL, and PHP to give you a safe place to work and practice.

this is an appendix

Create a PHP development environment


Before you can put your finished application on the web, you need to develop it. And it's never a good idea to develop your web application on the Web where everyone can see it. You can **install software locally that lets you build and test your application before you put it online.**

There are three pieces of software you'll need on your local computer to build and test PHP applications:

- 1. A web server
- 2. PHP
- 3. A MySQL database server

PHP isn't a server; it's a set of rules that your web server understands that allow it to interpret PHP code. Both the web server and the MySQL server are executable programs that run on a computer.

Keep in mind that we're talking about setting up your **local computer** as a web server for PHP development. You'll ultimately still need an **online** web server to upload your finished application to so that other people can access and use it.



Find out what you have

Before trying to install any of the pieces of the PHP development puzzle, your best bet is to first evaluate what you already have installed. Let's take a look at the three pieces and how you can tell what's already on your system.


The platform of your local computer makes a big difference when it comes to what's already installed. For example, Mac OS X has a web server installed by default, while most Windows computers do not.

NOTE: This appendix covers Windows 2000, XP, Vista, Windows Server 2003/2008, or other 32-bit Windows operating system. For Mac, it applies to Mac OS X 10.3.x or newer.

732 Appendix ii

Do you have a web server?

You probably already have a web server if you are using a newer PC or Mac. To find out quickly on either system, open a brower window and type http://localhost in the address bar. If you get an introductory page, that means your web browser is alive and well on you local machine.



Do you have PHP? Which version?

If you have a web server, you can check to see if you have PHP installed very easily, as well as which version you have. Create a new script named info.php and type this in it:

<?php phpinfo(); ?>


Save this file to the directory your web server uses. On Windows it's typically:

C: inetpub/wwwroot/

On the Mac, it's usually something like:

/Users/yourname/sites/


If you try to open this file in your browser by typing http://localhost/info.php, you'll see something like this if you have PHP installed:



you are here > 733

Do you have MySQL? Which version?

On Windows, you can tell by opening the Control Panel --> Administrative Tools --> Services:




734 Appendix ii

Start with the Web Server


Depending on the version of Windows you have, you can download Microsoft's Internet Information Server (IIS), or the open source Apache web server. If you need a server on the Mac, you should probably go with Apache since it's already installed.

Here's a brief overview of installing Apache on Windows:



Apache installation... concluded

You're nearly finished, Click *Install* and wait a minute or so for the installation to complete. That's it!




Your web server is set to start automatically when you start up your computer. But you can control it using the **Services** panel by stopping and starting it in the the **Control Panel** --> **Administrative Tools** --> **Services** dialogue where it will now show up.

PHP installation

Go to http://www.php.net/downloads.php.

Just as with Apache, if you're using Windows, we suggest you download the Windows installer version, php-5.2.6-win32-installer.msi. This will automatically install PHP for you after you download and double click it.



736 Appendix ii


PHP installation steps

It starts with a basic Setup.

Accept the License Agreement to continue, Selecting the default installation folder is usually a good idea.



Careful on this screen. If you're using Apache, select the right version. If you're using IIS, you will probably select the IISAPI module. Check with your particular software to determine exactly what you need.



you are here >

737

PHP installation steps... concluded

That's it. Click on *Install*, then *Done* to close the installer.

Now try looking at your http:// localhost/info.php file in your web browser and see what version is showing up.



Installing MySQL

Instructions and Troubleshooting

You still need MySQL, so let's work through the downloading and installing of MySQL. The official name for the free version of the MySQL RDBMS server these days is MySQL Community Server.

The following is a list of steps for installing MySQL on Windows and Mac OS X.

This is **not** meant to replace the excellent instructions found on the MySQL web site, and **we strongly encourage you to go there and read them!** For much more detailed directions, as well as a troubleshooting guide, go here:

[Set version 6.0 or newer.

http://dev.mysql.com/doc/refman/6.0/en/windows-installation.html


You'll also like the MySQL Query Browser we talked about. There, you can type your queries and see the results inside the software interface, rather than in a console window.

738 Appendix ii


Steps to Install MySQL on Windows

Go to:

http://dev.mysql.com/downloads/mysql/6.0.html and click on the MySQL Community Server download button.




Choose Windows from the list.




you are here > 739

Pownload your installer

Under *Windows downloads*, we recommend that you choose the Windows ZIP/Setup.EXE option because it includes an installer that greatly simplifies the installation. Click on *Pick a Mirror*.



- You'll see a list of locations that have a copy you can download; choose the one closest to you.
- When the file has finished downloading, double-click to launch it. At this point, you will be walked through the installation with the **Setup Wizard**. Click the **Next** button.



Pick a destination folder

6

You'll be asked to choose *Typical*, *Complete*, or *Custom*. For our purposes in this book, choose *Typical*.

You can change the location on your computer where MySQL will be installed, but we recommend that you stay with the default location:

C:\Program Files\MySQL\MySQL Server 6.0

Click the Next button.



www.it-ebooks.info

Click "Install" and you're done!



You'll see the **Ready to Install**' dialog with the **Destination Folder** listed. If you're happy with the destination directory, click **Install**. Otherwise, go **Back**, **Change** the directory, and return here.

Click Install.

Enabling PHP on Mac OS X

PHP is included on Macs with OS X version 10.5+ (Leopard), but it's not enabled by default. You have to access the main Apache configuration file and comment out a line of code in order to get PHP going. This file is called http.conf, and is a hidden file located down inside the Apache install folder.

You're looking for the following line of code, which has a pound symbol (#) in front of it to comment it out:

#LoadModule php5 module libexec/apache2/libphp5.so

You need to remove the pound symbol and restart the server to enable PHP. The http.conf document is owned by "root," which means you'll have to enter your password to change it. You'll probably also want to tweak the php.ini file so that Apache uses it. For more detailed information about how to carry out these steps and enable PHP, visit http://foundationphp.com/tutorials/php_leopard.php.

Steps to Install MySQL on Mac OS X

If you are running Mac OS X Server, a version of MySQL should already be installed.

Before you begin, check to see if you already have a version installed. Go to Applications/Server/MySQL Manager to access it.



Go to:


http://dev.mysql.com/downloads/mysql/6.0.html and click on the MySQL Community Server *Download* button.



742

Appendix ii

Choose Mac OS X (package format) from the list.



- Choose the appropriate package for your Mac OS X version, Click on Pick a Mirror.
- You'll see a list of locations that have a copy you can download; choose the one closest to you.
- When the file has finished downloading, double-click to launch it. You can now open a Terminal window on your Mac and type:

shell> cd /usr/local/mysql
shell> sudo ./bin/mysqld_safe

(Enter your password, if necessary)

(Press Control-Z)

shell> bg

(Press Control-D or enter exit to exit the shell)

If you're using a GUI tool such as phpMyAdmin, check its documentation for how to access it once MySQL is successfully installed.

Moving from production to a live site

You've spent days or weeks working on your site, and you feel it's ready to go live. To move your PHP and MySQL site from your local computer to the web requires a little planning and a few specific techniques.

First, you need to make sure that the place your site is going has the same versions of PHP and MySQL you expect. If not, you may need to make your code to match what is available. Most of the code in this book is portable, but you may need to retrofit your PHP code back to the mysql functions, as opposed to the mysqli functions we use in this book. If that's the problem, check out #1 of The Top Ten Topics (we didn't cover) for more information.

If the software on your live site is compatible, then moving your site over is simple. Here are the steps:

Your PHP files need to be FTP'ed to the web directory of your live site.

- Upload the PHP files from your production server to the web directory on your live server. Keep the file structure intact, and make sure you don't lose any folders you might have created to contain your included files.
- 2. Do a database dump (which we'll show you in a moment) to get the MySQL statements you need to create your tables and the INSERT statements you need to move your data from the table on the production server to the live server.

You need to get at the structure of your tables and the data stored in them Here's how:

Log in to your live database where you can run the CREATE and INSERT
 MySQL statements to move your data from your local site to the live site.

4. Modify any database connection code in your PHP files to point at the live database server. If you don't change this, your live code will try to connect to your production site and won't be able to connect. Your SQL dump will give you the exact syntax of your CREATE TABLE statements and INSERT statements

Change those mysqli_connect() statements' to point at your MySQL server associated with your live site, along with the correct username and password to get you connected.

Dump your data (and your tables)

You've FTP'ed your PHP files to the live server, but your data is still not on the live site's MySQL server. When your table is full of data, the idea of moving it to another MySQL server can be daunting. Fortunately, bundled with MySQL is the MySQLdump program, which gives you an easy way to recreate the CREATE TABLE statement that can recreate your table and all the INSERT statements with the data in your table. You simply need to use the MySQLdump program. To make a copy of your data that you can move to another MySQL server, type this in your terminal:

```
S mysqldump
Usage: mysqldump [OPTIONS] database [tables]
OR mysqldump [OPTIONS] --databases [OPTIONS] DB1 [DB2 DB3...]
OR mysqldump [OPTIONS] --all-databases [OPTIONS]
For more options, use mysqldump --help
Smysqldump riskyjobs jobs > riskyjobstable.sql
```

This sends the CREATE TABLE statement for the jobs table to a text file we just created named riskyjobsttable.sql. If you leave off the >riskyjobstable.sql part, then the CREATE TABLE and INSERT statements will simply scroll by you on the screen in your terminal. Try it to see what we mean. It's not very useful, but you'll see all your data fly by, nicely formatted in INSERT statements.

Once you've sent all that data to your new file using the greater than sign, you can grab that file and use the contents as MySQL queries at your hosting site to move your tables and your data.

Prepare to use your dumped data

Get ready to move your data by running a CREATE DATABASE statement on your live MySQL statement. Then run a USE DATABASE on your new database. Now you are ready to move your data from your production server to your live server.

you are here > 745

Move dumped data to the live server

You've created a file called riskyjobstable.sql that contains MySQL statements that create your table and insert data into it. The file riskyjobstable.sql probably looks a bit like this: riskyjobstable.sql -- MySQL dump 10.11 These are all comments, -- Host: localhost Database: riskyjobs you can ignore them -- Server version 5.0.51b /*! 40101 SET @OLD CHARACTER SET CLIENT=@@CHARACTER SET CLIENT -- Table structure for table 'jobs' If you know there isn't a table named "jobs" where you are creating this one, you can ignore this command. DROP TABLE IF EXISTS 'jobs'; CREATE TABLE 'jobs' (< The 'job id' int(11) NOT NULL auto increment, mysaldump Here's the title varchar (200) default NULL, always writes, CREATE description blob, a DROP 'city' varchar(30) default NULL, TABLE statement to statement. state char(2) default NULL, start with 'zip' char(5) default NULL, a clean slate 'co id' int(11) default NULL, before doing PRIMARY KEY ('job id') a CREATE) ENGINE=MyISAM AUTO_INCREMENT=14 DEFAULT CHARSET=utf8; and INSERT. You can ignore this LOCK statement and copy and -- Dumping data for table 'jobs' paste starting at the INSERT statement LOCK TABLES 'riskyjobs' WRITE; /*!40000 ALTER TABLE "riskyjobs" DISABLE KEYS */; INSERT INTO 'riskyjobs' VALUES (8,'Custard Walker','We need people willing to test the theory that you can walk on Mysaldump custard.\r\n\r\nWe\'re going to fill a swimming pool with makes custard, and you\'ll walk on it. \r\n\r\nCustard and other a single kinds of starchy fluids are known as non-Newtonian fluids. INSERT They become solid under high pressure (your feet while you statement walk) while remaining in their liquid form otherwise.\r\n\r\ that nTowel provided, own bathing suit, a must.\r\n\r\nNote: if inserts you stand on for too long on the custard\'s surface, you will every row slowly sink. We are not liable for any custard sinkages; in the table.

746 Appendix ii



Take the entire text of the .sql file and paste it into your MySQL terminal or the query window of your MySQL graphical client (like phpMyAdmin).


This performs the queries in the file. In the case of the example on this page, the dumped file contains a CREATE TABLE statement and an INSERT statement. Along the way, the dumped file tells your MySQL server to drop any existing table and to LOCK (or keep anyone from using) the table while you INSERT the new data.

Connect to the live server

You've moved your PHP files to your live site. You've taken your table structures as CREATE TABLE statements and your data as a massive INSERT statement from the mysqldump and executed them on your live web server, so your data has been moved.

There's a small step left. The PHP code you FTP'ed to your live web site isn't connecting to your live MySQL server.

You need to change the connection string in your mysqli connect () function to point to your live MySQL server. Anywhere in your PHP code where you call the mysqli connect () function, you'll need to change it.



That's it!

- You've copied your FTP files to your web server,
- you've dumped your tables and data into a .sql file,
- you've run the queries in the .sql file on your live MySQL server,
- and you've changed your PHP file to call your live MySQL server database.

Your site should now be live!

747 you are here >

appendix iii: extend your php



I know I have everything any run-of-the-mill, heartbreakingly beautiful, fiendishly clever femme fatale needs, but it's not enough.



Yes, you can program with PHP and MySQL and create great web applications. But you know there must be more to it. And there is. This short appendix will show you how to install the mysqli extension and GD graphics library extension. Then we'll mention a few more extensions to PHP you might want to get. Because sometimes it's okay to want more.

this is an appendix

Extending your PHP

This book discusses installing both the mysqli and GD modules on Windows. In this section, we'll show you how to see what modules you have, how to get GD or mysqli if you are missing them, and how to install them in Windows. Unfortunately, installing these modules on a Mac or Linux system is kinda tricky. More on that at the end of this appendix.

NOTE: This appendix covers Windows 2000, XP, Vista, Windows Server 2003/2008, or other 32-bit Windows operating system.


If you're using Windows, you're in luck

You probably already have both the mysqli and GD modules on your computer. And even if you don't, adding them is relatively easy. We'll show you how to check to see what you have, if you're missing one of them, how to get it, and how to activate one or both modules.

It starts with checking to see what you have.




First, figure out if GD or mysqli is on your system. To do that, begin by navigating to the directory where the PHP extensions are installed. They are typically in the C:/PHP/ ext directory, although the path may be different on your machine, Open the ext directory and look for php gd2.dll and php mysqli. dll. In general, these are installed with PHP 5 and later, and simply need to be activated. If you have them, great, move on to step 3. If not, go to step 2.



If you're missing either php_mysqli.dll or php_gd2.dll, you'll have to get it.

Chances are you already have both DLLs on your machine, but if you don't, you can find php_gd2.dll at: http://www.libgd.org/Downloads. Download it and copy it to the folder ext under your PHP install. In our examples, it's located at C:/PHP/ext.


You can get the mysqli extension from MySQL.com. First, browse to http://www.mysql.com. Click on *Downloads* (along the top) --> *Connectors* (it's in the left menu) --> *MySQL native driver for PHP* --> *Download* php_mysqli.dll for PHP 5.2.1 (Windows) (Make sure this is your version).



C:\Program Files\PHP 趣 File Enit View Favorites Tools Help Glad . D Search Croders III. By now you should have w 5 00 Address (C: Program Files PHP php mysqli.dll and Date Modif Size Type php gd2.dl1 copied to your 9/2/2008 19 File and Folder Tasks Folder dev 9/2/2008 1 Folder ext Firstal tot /PHP/ext folder. We need to tell 160 Rename that file 951B Text Document 5/2/2008 68 Move that lie our php.ini file to use these 2,028 KB Application Externion 5/2/2008 65 Microse.txt Copy this file 5/2/2008 6: 416 Text Coowent DLLs. To do that, browse to the @ Publish the Se to the 183 KB Text Document 5/2/2008 6:1 news.txt 4/30/2005 4 654 KB LIS File directory it's in, and open the file TiphuSembed.lib () treat tru fie 29 KB Application Externion 5/2/2008 6 Sipropissopi.dl in a text editor. 5/2/2008 6: Print the Ne 4,761 KB Application Extension %php5ts.dl 5/2/2008 6: imphp.exe 33 KB Application Celete tres file 5/2/2008 60 3 KB GIF Image Total of 48 KB Configuration Settings 9/2/2008 10 S pha.m Sometimes your PHP install Other Places Type: Configuration Settings Date Modified: 9/2/2006 10:55 AM ends up in the Program Size: 47.7 (2) My Decuments Files PHP directory. Find Chartel Documents your php ini file and open it Type: Configuration Servings Date Modified: 9/2/2008 10:55 AM See: 47.7 KB My Compute 47.7 83 for the next step.


you are here > 751

installing new php modules (continued)



The last step is to restart your Apache web server so that the changes you made to your php.ini file will take effect. To do this, go to your Windows Control Panel, double-click on **Administrative Tools**, then click **Services**. You should see this:





Select Apache and then click the Restart link.

Click the **Apache** service, then click on **Restart** from the menu on the left. The next time you try to use the GD or mysqli functions, they should work correctly.

752 Appendix iii

And on the Mac ...

Unfortunately, it's quite a bit more difficult. Adding modules on the Mac means recompiling the PHP source code and passing in arguments to add in the modules you want. There are simply too many possible combinations of Mac operating systems and PHP versions to include in this short appendix. There is a terrific guide that may help you install the GD module located here:

http://macoshelp.blogspot.com/2008/02/adding-gd-library-for-mac-os-x-leopard.html

It will only work if you have the right OS X version (Leopard), and the right PHP version (5). If you don't, or the instructions don't work for you, you may want to dig through the comments on that site and on the original GD website, http://www.libgd.org/, for more detailed and specific installation instructions for your flavor of OS X and PHP.

For help in adding mysqli to your Mac version of PHP, which also means recompiling PHP, we recommend the instructions here:

http://dev.mysql.com/downloads/connector/php-mysqlnd/

Keep in mind that this complication of installing the GD and mysqli extensions only applies if you're trying to run a web server on a Mac, such as a local development server. But if you're just using a Mac to write PHP code that is being uploaded and tested on some other server, it's not an issue.